

OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 3980-83
 Dated. 03-11-2020

M. A. Iqbal Majid Kaw
 Contractor,
 S/o Ghulam Hassan Kaw,
 R/o. Char-i-Sharief District Budgam
 Regd. No. SE/Hyd/Sgr/AAY/Class-89/Civil od 2004-05

Sub :- Retrofitting of Water Supply Scheme Rohmu (old) by way of providing, laying & fitting of GI pipes, construction of PST including construction of chain lin fencing around sgructurms, including installation of 241 No. FHTC's (JMM).

Ref:- E-NIT S.No. 49/PHEP of 2020-21, job No. (1), Circulated vide this officu No. PHEP/3523-34 Dated:- 13-10-2020.

Advertised Amount of work: ₹ 87,81,000.00
Alloted Amount of work: ₹ 85,68,000.00
Rupees Eighty Five Lakh(s) Sixty Eight Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following rates quoted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earthwork in excavation by manual means in trenches for foundation, drains, pipes cablesetc (not exceeding 1.5mtrs in width and for shafts, wells cesspits anmd the like not exceeding 10 Sqm on plain depth upto 1.5 mtrs, including disposal of excavated earthj upto 1mtr from cutting edge disposal earth to be levelled and neatly dressed in all kinds of soil	1953.25	Cum	240.45	300.00	Rupees Three Hundred Only
2.00	P/F of flanged pipe with flanged joints 12mm thick of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.					
2.10	100mm dia GI flanged pipe	1000.00	Mtr	RQC	750.00	Rupees One Thousand Two Hundred Only
2.20	80mm dia GI flanged pipe	500.00	Mtr	RQC	830.00	Rupees Eight Hundred Thirty Only
3.00	Providing, laying and fitting of G.I. pipes including cost of pipes but excluding cost of earth work:					
3.10	100mm dia	1300.00	Mtr	RQC	900.00	Rupees Nine Hundred Only
3.20	40mm dia	2000.00	Mtr	RQC	330.00	Rupees Three Hundred Eighty Only
3.30	25mm dia	1500.00	Mtr	RQC	255.00	Rupees Two Hundred Fifty Five Only
3.40	20mm dia	2000.00	Mtr	RQC	180.00	Rupees One Hundred Eighty Only
3.50	15mm dia	3500.00	Mtr	RQC	140.00	Rupees One Hundred Forty Only
4.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.					
4.10	25mm to 40mm nominal bore	25.00	Pty	400.00	400.00	Rupees Four Hundred Only
5.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	1370.25	Cum	102.20	89.00	Rupees Eighty Nine Only
6.00	Providing and laying of stone scling hand packed horizontally excluding cost of stones	28.27	Cum	327.05	450.00	Rupees Four Hundred Fifty Only
7.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement: 4 fine coarse 8 grade stone upg. 40 mm nominal size crushed	20.27	Cum	3112.00	3000.00	Rupees Three Thousand Only
8.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:3:6 (1 cement: 3 coarse sand 4 grade stone upg. 40 mm nominal size	71.28	Cum	3543.05	3500.00	Rupees Four Thousand Five Hundred Only
9.00	Centering and shuttering including strutting, propping etc and removal of form for:-					
9.10	Foundation, footings, bases of columns etc. for mass concrete.	255.57	Sqm	178.25	200.00	Rupees Two Hundred Only
9.20	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	405.70	Sqm	342.50	300.00	Rupees Three Hundred Only
9.30	Suspended floors, roofs, landings, balconies and access platform	37.00	Sqm	372.00	300.00	Rupees Three Hundred Only
10.00	12 mm thick cement plaster of mix 1:4	420.00	Sqm	150.00	250.00	Rupees Two Hundred Fifty Only
11.00	Structural steel work welded in built up section, trusses and framing work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	1911.25	Kg	80.00	80.00	Rupees Eighty Nine Only
12.00	Structural steel work welded in built up section/frames work including cutting hoisting fixing in position and applying painting cost of approved steel primer using structural steel etc as required in girders, frames, beams and columns, walls, brackets and accessories.	100.00	Kg	80.00	80.00	Rupees Eighty Nine Only

b :- Retrofitting of Water Supply Scheme Rohmu (old) by way of providing, laying & fitting of GI pipes, construction of PST including construction of chain link fencing around structures, including installation of 241 No. FHTC's (JJM).

14.00	Painting with synthetic enamel paint of approved brand with manufacture using re-oxide painting coat over new steel work	109.80	Sqm	69.30	100.00	Rupees One Hundred Only
14.00	Painting wood work with deluxe multi surface paint of required shade. Two or more coats applied @ 0.90 litre/1 Osqm over an under coat of primer applied @ 0.75 litre/1 Osqm of approved brand and manufacture	109.80	Sqm	80.35	90.00	Rupees Ninety Only
15.00	Providing and fixing of G.I. chain link fencing of required width in mesh size 50x50mm including strengthening with 2mm dia wire or nuts, bolts and washers as required complete as per direction of Engineer incharge. Made of G.I. wire 4mm dia	183.00	Sqm	571.00	700.00	Rupees Seven Hundred Only
16.00	Finishing walls with water proofing cement paint of required shade (new work)	237.60	Sqm	56.90	80.00	Rupees Eighty Only
17.00	P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	RQC	10000.00	Rupees Ten Thousand Only
18.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3) Raft (1 cement: 1 1/2 course sand: 3 grade stone agg. 20 mm nominal size)	34.82	Cum	5504.20	6900.00	Rupees Six Thousand Nine Hundred Only
19.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement: 1 1/2 course sand: 3 graded crushed stone 20 mm nominal size)	49.03	Cum	6280.95	7500.00	Rupees Seven Thousand Five Hundred Only
20.00	Providing and laying upto floor five level reinforced cement concrete, in kerbs, steps and the like excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	7.84	Cum	5395.50	6200.00	Rupees Six Thousand Two Hundred Only
21.00	Providing and fixing of Baramulla slabs including all carriages from Baramulla upto site of work including loading unloading, head load if any complete (size of stones as required at site)	33.57	Sqm	RQC	900.00	Rupees Nine Hundred Only
22.00	Providing and laying of filter media from Ganderbal including all carriages lead lifts and placing in layers into plant complete job.	59.50	Cum	RQC	7500.00	Rupees Seven Thousand Five Hundred Only
23.00	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete (thermo-mechanically treated bars)	8072.00	Kg	71.00	80.00	Rupees Eighty Only
24.00	Extra for providing and mixing of water proofing material in cement conc work in doses by weight of cement as per manufacturer specification	655.00	Kg	43.95	59.00	Rupees Fifty Nine Only
25.00	P/F of different dias of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirtoskar or VAGE) including all carriages upto site of work complete including tail pieces					
25.10	100mm dia sluice valve	2.00	No	RQC	10500.00	Rupees Ten Thousand Five Hundred Only
25.20	100mm dia GI Bend	4.00	No	RQC	1900.00	Rupees One Thousand Nine Hundred Only
26.00	Carriage of materials from source upto actual site of work by mechanical transport including cost of loading, unloading, stacking complete.					
26.10	Stone Solling (avg lead 15 Kms)	28.27	Cum	244.51	190.00	Rupees One Hundred Ninety Only
26.20	Sand Bajri (avg lead 15 Kms)	261.06	Cum	207.80	190.00	Rupees One Hundred Ninety Only
26.30	Cement + steel (avg lead 15 Kms)	62.54	M.T.	184.75	190.00	Rupees One Hundred Ninety Only
27.00	Maintenance cost for a period of two years	1.00	Complete Job	RQC	60000.00	Rupees Sixty Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 185149/- deposited by your vide CLR No. 3050422 dated 20-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked
Head Draftsman

Tech. Officer

Executive Engineer
JSD (S&E) Div. Pulwama

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.