

9

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 4276-79
Dated: 13-11-2020

Mr. Bashir Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zaglam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Wasanmarg by way of providing, laying & fitting of GI pipes including face lifting of various structures by way of painting & whitewashing, including painting to chain link fencing around structures including installation of 87 No. FHTCs for village Wasanmarg. (J J M)

Ref:- E-NIT S.No. 42/PHEP/Fresh of 2020-21, job No. (2), Circulated vide this office No. PHEP/3225-38 Dated: 01-10-2020.

Advertised Amount of work: ₹ 35,56,300.00
Alloted Amount of work: ₹ 36,10,000.00
Rupees Thirty Six Lakh(s) Ten Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, this contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	R A T E	
				Figures	Words
1.00	Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.				
1.10	Above 40mm dia bore	1000.00	Mtr	59.00	Rupees Fifty Nine Only
2.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil	1640.70	Cum	300.00	Rupees Three Hundred Only
3.00	Providing & laying of 100mm dia flanged pipes including cost of pipes, flanged joints with nuts, bolts, washers, welding cutting of threads and making good for joints complete	560.00	Mtr.	1100.00	Rupees One Thousand One Hundred Only
4.00	Providing, laying and fitting of G.I. pipes including cost of pipes but excluding cost of earth work:				
4.10	85mm dia	800.00	Mtr	490.00	Rupees Four Hundred Ninety Only
4.20	50mm dia	1040.00	Mtr	400.00	Rupees Four Hundred Only
4.30	40mm dia	1160.00	Mtr	290.00	Rupees Two Hundred Ninety Only
4.40	25mm dia	1904.00	Mtr	195.00	Rupees One Hundred Ninety Five Only
4.50	20mm dia	2890.00	Mtr	120.00	Rupees One Hundred Twenty Only
4.60	15mm dia	1500.00	Mtr	140.00	Rupees One Hundred Forty Only
5.00	Laying & fitting of dismantling G.I. pipes excluding cost of pipes (65mm dia)	1000.00	Mtr	65.00	Rupees Sixty Five Only
6.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete				
6.10	25mm to 40mm nominal bore	15.00	No	450.00	Rupees Four Hundred Fifty Only
7.00	Filling available excavated earth (excld Rock) in trenches, plinth bases of foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and up to 1.50 Mtr	1476.63	Cum	125.00	Rupees One Hundred Thirty Five Only
8.00	Finishing walls with water proofing cement paint of required shade old work (one or more coats) applied @ 2.20 kg/10 Sqm over priming coat of primer applied @ 0.80 liters/10 Sqm complete including cost of priming coat	185.00	Sqm	70.00	Rupees Seventy Only
9.00	Painting with ready mixed synthetic emulsion paint of approved brand and manufacture in all shades to give an even shade old steel work (one or more coats)	429.35	Sqm	65.70	Rupees Sixty Five And Paise Seventy Only
10.00	Providing and fixing of sign board including writing, painting, earth work, concrete work for fixing of angle iron poles and M/S board including all accessories	1.00	No	15250.00	Rupees Fifteen Thousand Only
11.00	Providing and fixing of sluice valves including all carnages leads, lifts, tail pieces, nuts, bolts, washers, welding, R cloths, spun yarn flanged joints of Kirlosker/ VAGE make including earth work etc complete				
11.10	65mm dia	2.00	No	6000.00	Rupees Six Thousand Only
11.20	80mm dia	1.00	No	7100.00	Rupees Seven Thousand One Hundred Only
12.00	Removal of unhygienic material (so classified by the site Engineer from designated sites and its disposal as per directions all inclusive)	50.00	Cum	110.00	Rupees One Hundred Ten Only
13.00	Structural steel work welded in built up section, trusses and framed work including cutting, noising, fixing in position and applying a primer coat of approved steel primer all complete	205.00	Mtr	58.00	Rupees Ninety Eight Only

Terms and Conditions:-

- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 - double will hold good even before the award of an agreement with the department.
- You have to attend the Divisional office along with your enlistment card for draw of an agreement within a week's time positively from the date of issuance of allotment. However, non draw of agreement will not prevent the contract from being enforced upon you.
- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- Earnest Money of ₹ 71200/- deposited by your vide CDR No. 593494 dated 13-10-2020 has been retained in the Divisional office as security deposit.
- All other terms and conditions will remain same as per the original agreement form No. 25 - double Form No. - 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- Superintending Engineer, Hydraulic Circle, Shopian, for information
- District Development Commissioner Pulwama for information
- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action
- File Concerned.

Tech. Officer

Executive Engineer
JSD (PHE) Div. Pulwama