

Government of Jammu and Kashmir  
**OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA**

No. PHEP/ 11291-94  
Dated. 3/11/2020

Mr. Ahmad Naik,  
Contr. For,  
S/o. Ghulam Ahmad Naik,  
R/o Zagigam, Pulwama  
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- *Retrofitting of Water Supply Scheme Uricharsoo by way of providing, laying and fitting of GI pipes, including construction of spring protection and face lifting of various structures including installation of 73 No. FHTCs for Uricharsoo (JJM).*

Ref:- E-NIT S.No. 45/PHEP of 2020-21, job No. (2), Circulated vide this office No. PHEP/3358-70 Dated: 05-10-2020.

\*\*\*\*\*  
**Advertised Amount of work: ₹ 38,70,000.00**

**Allotted Amount of work: ₹ 43,74,000.00**

**Rupees Forty Three Lakh(s) Seventy Four Thousand Only**

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	985.96	Cum	324.00	Rupees Three Hundred Twenty Four Only
2.00	P/F of flanged pipe with flanged joints 12mm thck of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.				
2.10	100mm dia GI pipe with flanges	1000.00	Mtr	1200.00	Rupees One Thousand Two Hundred Only
2.20	80mm dia GI pipe with flanges	700.00	Mtr	850.00	Rupees Eight Hundred Fifty Only
3.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.				
3.10	65mm dia	1000.00	Mtr	600.00	Rupees Six Hundred Only
3.20	40mm dia	500.00	Mtr	380.00	Rupees Three Hundred Eighty Only
3.30	25mm dia	1000.00	Mtr	245.00	Rupees Two Hundred Forty Five Only
3.40	20mm dia	1500.00	Mtr	182.00	Rupees One Hundred Eighty Two Only
3.50	15mm dia	2000.00	Mtr	140.00	Rupees One Hundred Forty Only
4.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.				
4.10	25mm to 40mm nominal bore	73.00	No	550.00	Rupees Five Hundred Fifty Only
4.20	above 40mm nominal bore	20.00	No	1220.00	Rupees One Thousand Two Hundred Twenty Only
5.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	873.90	Cum	178.00	Rupees One Hundred Seventy Eight Only
6.00	Clearance of silt from PST, FP, clear water sump, SR intake filter media etc including disposal from the premises all leads and lifts complete job.	2367.78	Cff	10.00	Rupees Ten Only
7.00	Centering and shuttering including strutting, propping etc and removal of form for:-				
7.10	Foundation, footings, bases of columns etc. for mass concrete.	73.72	Sqm	220.00	Rupees Two Hundred Twenty Only
8.00	Providing and laying of stone soling hand packed horizontally excluding cost of stones	4.99	Cum	441.00	Rupees Four Hundred Forty One Only
9.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	756.61	Kg	100.00	Rupees One Hundred Only
10.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	627.26	Sqm	37.33	Rupees Thirty Seven And Paise Fifty Three Only
11.00	P/F of different dias of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirtoskar or VAGE) including all carriages upto site of work complete including tail pieces				
11.10	100mm di sluice valve	2.00	No	12000.00	Rupees Twelve Thousand Only
12.00	Painting on G.S sheets with synthetic enamel paint of approved band and manufacture of required colour to give an even shade. New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution.	627.26	Sqm	107.00	Rupees One Hundred Seven Only
13.00	Finishing walls with water proofing cement paint of required shade old work (one or more coats) applied @ 2.20 kg/10 Sqm over priming coat of primer applied @ 0.80 liters/10 Sqm complete including cost of priming coat.	519.21	Sqm	11.55	Rupees Seventy One And Paise Fifty Five Only
14.00	Painting with synthetic enamel paint of approved band and manufacture of give an even shade two or more coats on new work	58.61	Sqm	90.58	Rupees Ninety And Paise Fifty Eight Only
15.00	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new works (two or more coats) over and including primary coat with cement primer.	57.50	Sqm	115.00	Rupees One Hundred Fifteen Only
16.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement:4 fine sand)	73.72	Sqm	250.00	Rupees Two Hundred Fifty Only
17.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement:4 fine sand 8 grade stone agg.)	4.99	Cum	4200.00	Rupees Four Thousand Two Hundred Only



Sub :- **Retrofitting of Water Supply Scheme Uricharsoo by way of providing, laying and fitting of GI pipes, including construction of spring protection and face lifting of various structures including installation of 73 No. FHTCs for Uricharsoo (JJM).**

	Providing and laying in position cement concrete of specified grade excluding the cost of centering, shuttering all work up to plinth level in (1:2:4) Mix (1 cement:2 course sand : 4 grade stone 20 mm nominal size of stone agg.)	16.75	Cum	5500.00	Rupees Five Thousand Five Hundred Only
19.00	P/F of 2"x2" steel mesh over PST including angle iron strips, nuts, bolts, washers, welding et complete.	130.00	Sqm	220.00	Rupees Two Hundred Twenty Only
20.00	Carriage of different materials from source upto actual site of work by mechanical transport including cost of loading, unloading and stacking complete.				
20.10	Stone Solling (avg lead 10 Kms)	4.99	Cum	270.00	Rupees Two Hundred Seventy Only
20.20	Sand + Bajri (avg lead 10 Kms)	30.51	Cum	230.00	Rupees Two Hundred Thirty Only
20.30	Cement + steel (avg lead 10 Kms)	7.55	M.T.	205.00	Rupees Two Hundred Five Only

**Terms and Conditions:-**

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (30) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 77500/- deposited by your vide CDR No. 593498 dated 13-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,  
JSD (PHE) Div. Pulwama