

Government of Jammu and Kashmir
Office of the Executive Engineer, Jal Shakti (PHE) Division, Pulwama

Allotment Order No. 38 Dated. 14-09-2022

Mr. Abdul Hamid Mir,
Contractor,
S/o Abdul Khaliq Mir,
R/o Litter, Pulwama
Regd. No. 3/AAY/SE/Hydl/Shopian/2004-05

Sub :- Construction of 0.60 lac gallons RCC S.R. , Chain link fencing around structures, Approach path , Development of premises, laying and fitting of G.I./D.I pipes, , installation of 143 FHTCs for WSS Tenghar Payer (JJM)

- Ref:-
- 1- This office ENIT S. No. 03/PHEP of 2022-23 published under endorsement No: PHEP/216-26 Dated: 19-04-2022.
 - 2- This office letter No. PHEP/1177-79 dated. 03-06-2022 and No. PHEP/1374-76 Dated. 14-06-2022.
 - 3- Superintending Engineer, Hydraulic Circle Shopian's letter No. SE/Hydl/DB/1436-38 Dated. 06-06-2022 (addressed to Chief Engineer)
 - 4- DJJM Pulwama's Minutes of Meeting held in 14-06-2022 and endorsed by Superintending Engineer Hydraulic Circle, Shopian vide No. 1773-06 Dated. 24-06-202.
 - 5- This office Authorization Committee Endorsement No. PHEP/1924-26 Dated. 13-07-2022
 - 6- Letter of Intent issued vide this office No. PHEP/1959-53 Dated. 14-07-2022.
 - 7- Technical Sanction No. CE/PHE/DB/490 of 09/2022 Dated. 09-09-2022

Advertised Amount of work: ₹ 98,58,000.00

Alloted Amount of the work:- ₹ 81,03,268.00

Rupees Eighty One Lakh(s) Three Thousand Two Hundred Sixty Eight Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following rates quoted/accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	RATE
1	All items of work as per BoQ (Specified Below as Annexure A)	(-17.8000%) Seventeen and Eight Tenths Percent Below the Estimated Rates.

Annexure (A)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P
1	2	3	4	5
1.00	Earth work in excavation by manual means in trenches for foundations ,drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts ,wells ,cesspits, and the like not exceeding 10sqm on plan ,including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	4369.30	Cum	436.00
2.00	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth, lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge. All kinds of soil	1312.50	Cum	83.45
3.00	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.			
3.10	80 mm dia G.I pipes	1500.00	Mtr	73.05
3.20	65 mm dia G.I pipes	700.00	Mtr	73.05
3.30	50 mm dia G.I pipes	2200.00	Mtr	40.80
3.40	40 mm dia G.I pipes	3800.00	Mtr	40.80
3.50	25 mm dia G.I pipes	2000.00	Mtr	30.65
3.60	20 mm dia G.I pipes	2000.00	Mtr	20.25
3.70	15 mm dia G.I pipes	5940.00	Mtr	20.25
4.00	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe) 150mm/100mm dia DI pipes	617.55	qll	245.55
5.00	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket			
5.10	100 mm dia DI pipes	250.00	joints	89.70

:- Construction of 0.60 lac gallons RCC S.R , ,Chain link fencing around structures, Approach path , Development of premises, laying and fitting of G.I/D.I pipes, , installation of 143 FHTCs for WSS Tenghar Payer (JJM)

5.20	150 mm dia DI Pipes			
6.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete	250.00	Jointa	144.70
6.10	(a) 25 to 40 mm nominal bore			
6.20	(b) Above 40 mm nominal bore	30.00	No	666.25
7.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	15.00	No	1266.75
8.00	Providing fixing double flanges C.I sluice valves /NRV's/Air valves of standard quality Kirlosker /vage make confirming to IS 780 of 1984 read with upto date amendments standard mark ISI make PN-1 including cost of nuts bolts IR cloth including all sorts of carriage upto site of work complete job including cost of pedestals and handles as required at site (to be paid as per actual details with supporting vouchers dully verified by AEE concern)	3428.55	Cum	198.70
8.10	(a) 100 mm sluice valve	5.00	No	13164.00
8.20	(b) 150 mm dia sluice valve	3.00	No	20243.00
8.30	(c) NRV	2.00	No	8000.00
8.40	(d) Air valve	4.00	No	4000.00
9.00	Providing and laying of stone solling 50 mm thick hand packed including watering dressing and ramming ,filling , spreading , including all carriages leads and lifts	176.32	Cum	1320.00
10.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 mix (1 cement :4 coarse sand :8 graded stone aggregate 40 mm nominal size)	62.27	Cum	4861.83
11.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:3:6 mix (1 cement :3 coarse sand :6 graded stone aggregate 20 mm nominal size)	220.50	Cum	5437.74
12.00	Providing and laying specified grade of reinforced cement concrete including curing but excluding the cost of centring , shuttering , finishing and reinforcement all works upto plinth level 1:2:4 mix (1cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	15.00	Cum	6465.19
13.00	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	914.16	Sqm	260.05
14.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	28.23	Cum	7800.76
15.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	34.03	Cum	9408.13
16.00	Reinforced cement concrete work in arches, archribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level including curing but excluding the cost of centering, shuttering finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	11.38	Cum	10404.51
16.10	Centring shuttering including strutting , propping etc. and removal of form work for			
16.20	Foundation footings , bases for columns	639.95	Sqm	262.30
16.30	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	19.12	Sqm	502.85
16.40	Suspended floors, roofs, landings, balconies and access platforms	19.14	Sqm	635.60
16.50	Columns, pillars, piers, abutments, posts and struts.	14.64	Sqm	680.15
16.60	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	282.00	Sqm	573.85
16.70	Extra for circular work in walls	244.00	Sqm	114.77
16.80	Arches, domes, vaults upto 6 m span	91.06	Sqm	2086.80
16.90	Extra for arches, domes, vaults exceeding 6 m span	91.06	Sqm	1008.45
17.00	Steel reinforcement for RCC work including straightening, cutting , bending, placing in position and binding all complete upto plinth level thermo -Mechanically -Treated bars of grade Fe-500D or more	6581.00	Kg	87.17
18.00	12mm Cement plaster finished with a floating coat of neat cement of mix: (1 cement : 3 fine sand)	125.60	Sqm	343.75
19.00	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	80.00	Kg	57.90
20.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	4862.82	Kg	91.02
21.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	549.00	Sqm	121.95
22.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer incharge. Made of G.I. wire of dia 4 mm	549.00	Sqm	733.50

Construction of 0.60 lac gallons RCC S.R , ,Chain link fencing around structures, Approach path ,
Development of premises, laying and fitting of G.I/D.I pipes , , installation of 143 FHTCs for WSS
Tenghar Payer (JJM)

23.00	Steel work welded in built up sections/framed work, including cutting, Hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	235.00	Kg	146.66
24.00	Applying priming coats with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron/ steel works	549.00	Sqm	52.75
25.00	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 ton capacity in stages to proper grade and camber, applying and booming requisite type of screening /binding material to fill up interstices of coarse aggregate, watering and compacting to the required density.	262.50	Cum	710.85
26.00	Supplying and stacking at site Graded crushed stone aggregate of size			
26.10	63 mm to 45 mm			
26.20	53 mm to 22.4 mm	129.93	Cum	564.60
27.00	Supplying and stacking at site Graded crushed stone aggregate of size	129.94	Cum	575.30
27.10	13.2 mm nominal size (Type A)	17.71	Cum	504.40
27.20	11.2 mm nominal size (Type B)	25.59	Cum	504.40
28.00	Supplying and stacking of crusher dust (as a binding material including spreading over surface and carriage complete job)	7.88	Cum	377.50
29.00	Carriage of WBM upto site avg lead 10km	259.86	Cum	371.28
30.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	500.00	Sqm	11.36
31.00	Supplying and stacking of good earth at site including royalty (earth measured in stacks will be reduced by 20% for payment)	255.00	Cum	258.25
32.00	Spreading of sludge, dump manure or/and good earth in required thickness as per directions of officer in-charge (cost of sludge, dump manure or/and good earth to be paid separately)	255.00	Cum	48.70
33.00	providing fixing of PGI constructional joint during concreting to S.R	64.61	mtr	600.00
34.00	Provision for face lifting of scheme including painting priming ,beautification of site whichever is required at site complete job(to be paid as per actual measurements and rates adopted on the time of bill @SSR 2020 Atpar)	1.00	Job	20000.00
35.00	providing , fixing , supplying pipe specials such as nipples , bends , sockets, tail pieces , union , gate valve , air valve subject to non availablity at divisional store and to be paid as per GST voucher item by item dully verified by AEE concern/ J.E concern.	1.00	Job	70000.00
36.00	Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete			
36.10	Sand and Bajri avg lead 15km	797.20	Cum	341.57
36.20	Cement and steel avg lead 15km	184.10	M.T	303.64
36.30	Good earth avg lead 10km	255.00	Cum	351.04
36.40	carriage of pipes from Divisional Store upto site of work including loading , unloading , stacking complete avg lead 15km	46.36	M.T	303.64
36.50	100 mm dia DI pipes	1500.00	mtr	7.46
36.60	150 mm dia DI Pipes	1500.00	mtr	12.44

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- The work shall be completed within a period of (180) days months from the date of Issuance of letter of intent/allotment. The date of start shall be reckoned 07 days from the date of issuance of letter of intent/allotment
- 4- Performance Security of Rs 243098/- deposited by you under CDR No. 192521 dated. 28-07-2022 has been retained in the divisional office.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked
Head Draftsman

Tech. Officer

Executive Engineer,
Jal Shakti (PHE) Division,
Pulwama
Dated. 14-09-2022

No. PHE/ 3254-57

Copy to the:-

- 1- Chairman District Jal Jeevan Mission (DJJM) Pulwama for favour of information.
- 2- Superintending Engineer, Hydraulic Circle, Shopian, for information.
- 3- Assistant Executive Engineer, (JSD) PHE Sub-Div., Tahab for information and necessary action.

