

Government of Jammu and Kashmir
Office of the Executive Engineer, Jal Shakti (PHE) Division, Pulwama

Allotment Order No. 34 Dated. 08-08-2022

Mr. Ghulam Nabi Wani,
Contractor,
S/o Ghulam Rasool
R/o Mitrigam Pulwama
Regd. No. 20/DEE/SE/Hydl/Spn/2013-14

Sub :- Retrofitting of Water Supply Scheme Gadhanjipora by way of laying and fitting of GI pipes, construction of anchor blocks, providing jacketing to RCC SR, renovation of operator quarter and including installation of 141 No. FHTC's for Gadhanjipora (JJM).

- Ref:-
- 1- This office ENIT S. No. 02/PHEP of 2022-23 published under endorsement No: PHEP/193-203 Dated: 18-04-2022.
 - 2- This office letter No. PHEP/1177-79 dated. 03-06-2022 and No. PHEP/1374-76 Dated. 14-06-2022.
 - 3- Superintending Engineer, Hydraulic Circle Shopian's letter No. SE/Hydl/DB/1436-38 Dated. 06-06-2022 (addressed to Chief Engineer)
 - 4- DJJM Pulwama's Minutes of Meeting held in 14-06-2022 and endorsed by Superintending Engineer Hydraulic Circle, Shopian vide No. 1773-06 Dated. 24-06-202.
 - 5- This office Authorization Committee Endorsement No. PHEP/1924-26 Dated. 13-07-2022
 - 6- Letter of Intent issued vide this office No. PHEP/1970-74 Dated. 14-07-2022.
 - 7- Technical Sanction No. 14/JJM of 28-07-2022.

.....
Advertised Amount of work: ₹ 8,99,000.00
Alloted Amount of the work:- ₹ 8,58,051.00

Rupees Eight Lakh(s) Fifty Eight Thousand Fifty One Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following rates quoted/accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	RATE
1	All items of work as per BoQ (Specified Below as Annexure A)	(-4.600%) Four and Six tenths Below the Estimated Rates.

Annexure (A)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P
1	2	3	4	5
1.00	Earth work in excavation by manual means in trenches for foundations ,drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts ,wells ,cesspits, and the like not exceeding 10sqm on plan ,including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	249.86	Cum	436.00
2.00	Providing and laying of stone solling 50 mm thick hand packed including watering dressing , filling, spreading , dressing , ramming all leads , lifts and all carriages	1.10	Cum	1320.00
3.00	Providing and laying specified grade of reinforced cement concrete including curing but excluding the cost of centring , shuttering , finishing and reinforcement all works upto plinth level 1:2:4 mix (1cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	5.49	Cum	6978.40
4.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	4.96	Cum	7800.76
5.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	9.11	Cum	9408.13
6.00	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete upto plinth level thermo -Mechanically -Treated bars of grade Fe-500D or more	1336.00	Kg	87.17

Retrofitting of Water Supply Scheme Gadhanjipora by way of laying and fitting of GI pipes, construction of anchor blocks, providing jacketing to RCC SR, renovation of operator quarter and including installation of 141 No. FHTC's for Gadhanjipora (JJM).

7.00	Centring shuttering including strutting , propping etc. and removal of form work for			
7.10	Foundation footings , bases for columns	111.84	Sqm	262.30
8.00	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	161.45	Sqm	260.05
9.00	Providing and fixing of sanitary items of standard quality like 500 liters sintex , W.C Indian type , flush tank , with all accessories . pvc pipe , pipe specials , C.P items , p trap, floor trap, bends , steel sink , connecting with soakage , whichever be necessary to make functional all complete (to be paid as per actual details /measurements with supporting voucher dully verified by AEE concern)	1.00	Job	15000.00
10.00	Providing fixing supplying P.C.C rings including earthwork excavation and disposal of surplus excavated material outside the premises including providing and laying cement concrete in 1:2:4 mix over septic tank and soakage pit . construction of man hole chambers with angle iron frame and covering arrangements .providing fixing of P.V.C pipe (price make B class) including bends whichever is required at site or as per directions of Engineer-in- charge (3 compartments for septic tank and 1 for soakage pit . (to be paid as per actual details /measurements)	6.00	Mtr	1106.00
11.00	Providing ,supplying fixing instillation of electric fittings of standard quality incl. 19/18 copper wire cable connection with transformer , instillation of panel board, switch board, switches, lighting points, heating points, fans , exhaust fans pvc conduit, havels wire , MCB, changeover , whichever is related to the item and found necessary at site or as per directions of Engineer- in- charge (to be paid as per actual details /measurements with supporting vouchers)	1.00	Job	8000.00
12.00	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1: 4 (1 cement : 4 coarse sand) including pointing the joints with white Cement and matching pigment etc., complete. In colour such as White, Ivory, Grey, Fume Red Brown	9.60	Sqm	1210.66
13.00	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete Welded	260.00	Kg	102.13
14.00	Providing corrugated G.S sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks , bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I filled with white lead , including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal / vertical or curved surface) excluding the cost of purlins , rafters and trusses and including cutting to size and shape wherever required 0.63mm thick with zinc coating not less than 275gram/sqm	33.45	Sqm	951.80
15.00	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.			
15.10	50 mm dia G.I pipes	400.00	Mtr	40.80
15.20	40 mm dia G.I pipes	600.00	Mtr	40.80
15.30	25 mm dia G.I pipes	650.00	Mtr	30.65
15.40	20 mm dia G.I pipes	650.00	Mtr	20.25
15.50	15 mm dia G.I pipes	1692.00	Mtr	20.25
16.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete			
16.10	(a) 25 to 40 mm nominal bore	20.00	No	666.25
16.20	(b) Above 40 mm nominal bore	8.00	No	1268.75
17.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	221.07	Cum	198.70
18.00	Replacement of damaged parts of sluice valves by way providing /fixing of tail pieces , nuts , bolts , washers , welding including excavation and refilling including all carriages complete job			
18.10	150mm dia sluice valve	2.00	No	20243.00
18.20	100mm dia sluice valve	2.00	No	13164.00
19.00	Engagement of labours for removal of unserviceable filter media from plant including disposal of same outside the premises complete	4.00	Lab	503.00
20.00	Providing , laying of filter media from Gandarbal including all carriages leads lifts and placing in layers into plant complete job (to be paid as per actual details / measurements)	4.00	Cum	6500.00
21.00	Renovation of M.S rotating bridge moving with MS rail on the base of clarifloculator including greasing, checking of fly wheel , chain reduction gear motor MS wheel bridge , pinion bearings shafts and replacement of damaged parts including checking of copper wire & electric conductor with all electric cable , starters complete job (to be paid as per actual details / supporting documents dully verified by AEE concern)	1.00	Job	10000.00
22.00	Checking and greasing of air blowers complete with all accessories including motor and electric fittings and checking of rate of flow gauge , Lol gauge , Head gauge , etc and replacement of damaged part if any including all sorts of carriage complete (to be paid as per actual details / supporting document dully verified by AEE concern)	1.00	Job	5000.00

Retrofitting of Water Supply Scheme Gadhanjipora by way of laying and fitting of GI pipes, construction of anchor blocks, providing jacketing to RCC SR, renovation of operator quarter and including installation of 141 No. FHTC's for Gadhanjipora (JJM).

23.00	Renovation of back wash pump and motor including all accessories, replacement of damaged foot valves , non-return valves etc including repair to damaged drain complete (to be paid as per actual details / supporting document dully verified by AEE concern)	1.00	Job	10000.00
24.00	Providing, fixing, supplying pipe specials such as nipples, bends, sockets, tail pieces, unions, gate valves, air valves subject to non availability at divisional stores and to be paid as per GST voucher item by item dully verified by AEE concerned and JE.	1.00	Job	7000.00
25.00	Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete			
25.10	Sand and Bajri avg lead 15km	69.67	Cum	341.57
25.20	Cement and steel avg lead 15km	12.00	M.T.	303.64
25.30	pipes avg lead 15km	6.91	M.T.	303.64

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- The work shall be completed within a period of (30) days months from the date of Issuance of letter of intent/allotment. The date of start shall be reckoned 07 days from the date of issuance of letter of intent/allotment
- 4- Performance Security of Rs 10000/- & Rs 16000/- deposited by you under CDR No. 3127992 & 3127994 dated.16-04-2022 & 16-04-2022 respectively have been retained in the divisional office.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Tech. Officer

No. PHEP/

2489-92

Executive Engineer,
Jal Shakti (PHE) Division,
Pulwama

Dated. 08-08-2022

Copy to the:-

- 1- Chairman District Jal Jeevan Mission (DJJM) Pulwama for favour of information.
- 2- Superintending Engineer, Hydraulic Circle, Shopian, for information.
- 3- Assistant Executive Engineer, (JSD) PHE Sub-Div., Tahab for information and necessary action.