

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND

Allotment Order No: PHQ/CCI/ of 2022-23 dated /11/2022
DATE: /11/2022

No: PHQ/
NAME : Ghulam Nabi Malik S/o Ali Mohammad Malik R/o Malikpora Verinag Cell No. 9797813324

email: @gmail.com

REGD. NO: 72-BEE/UPGRD/SE-RandB/ANG-PUL/2006-07 ACCOUNT NO:

PAN: AMWPM2511Q

GSTN: 01AMWPM2511Q1Z5

Name of Schemes:- Laying and fitting of pipes and revamping of 30,000 gallons capacity slow sand filtration plant for WS Scheme Gutligund

Administrative Approval No. (7th ACM) S.E

Technical Sanction No.

Allotted Cost; Rs:- 2398114/=

Completion Time

References:- 1. Your tender received in response to e-NIT.No.21 of 8/2022 OF 2022-23 Dated:23-08-2022 (Fresh)
ISSUED UNDER NO.No: PHQ/2961-75 Dated 23/08/2022

Reference:- The tender appreciation upto 2-4% over the advertized cost for works(s) having predominant pipe laying and civil structures cost respectively has been authorized by the DJJM vide NO.DDC-A/DJJM/9413 dated:- 04-11-2022

For & on behalf of Lt. Governor of J&K, contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms in upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed				
1.01	All kinds of soil	1825.200	Cum	436.000	795787.20
1.02	Ordinary Rock	202.800	Cum	967.850	196279.98
2	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes and Earth work but incl. cost of pipe fittings				0.00
2.01	80 mm dia GI Pipe	2700.000	Mtr	73.050	197235.00
2.02	40 mm dia GI pipe	700.000	Mtr	40.800	28560.00
2.03	25 mm dia GI pipe	1000.000	Mtr	30.650	30650.00
2.04	20 mm dia GI pipe	1500.000	Mtr	20.250	30375.00
2.05	15 mm dia GI pipe	1500.000	Mtr	20.250	30375.00
3	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe) 100 mm dia DI (K7)	237.150	Qtl	245.550	58232.18
4	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket(100 mm dia DI)	273.000	Joints each.	89.700	24488.10
5	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc. if required will be paid separately)	5.000	No	5147.150	25735.75

20-7-2022
22-08-2022
22-08-2022

59

175-DB of 2022

152-59-DB of 2022

Rupees :- Twenty Three Lacs Ninety Eight thousands One Hundred and Fourteen only

90 Days

T.D

Handwritten initials

Handwritten initials

The allotted materials used for evaluating of the project shall be that of an agency must execute relevant applicable

6	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete	12,000	Each	656.250	169500.00
6.01	25 to 40 mm nominal bore	3,000	Each	1268.750	3806250.00
6.02	50 to 80 mm nominal bore	1825.200	Cum	198.700	362567.24
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	113,000	No	1500.000	169500.00
8	Installation of house hold connections to unconnected households including providing and fixing of necessary pipes specials, earth work at connections whatever necessary.	94,000	No	503.000	47282.00
10	Engagement of labour for extracting of old choked filter media from SSFP.	117,000	No	503.000	58851.00
11	Engagement of labour for laying back of old filter media of required size and quality after grading and cleaning.	976,320	cft	250.000	244080.00
13	Providing and laying of filter media effective size of sand varies from 0.45 mm to 0.70 mm having uniformity coefficient between 1.30 to 1.75 and should be dust free from other organic impurities to be obtained from Ganderbal and the size of gravel should vary from 2mm to 40 mm including all carriages complete.				
14	Carriage of pipes from divisional store up to actual site of work by M.T. Avg lead 10 Km including loading, unloading and stacking complete.				0.00
14.01	100 mm dia GI Pipe	1500.000	Mtr	6.130	9195.00
14.02	50/40/25/20/15 mm dia nominal bore	25,760	MT	249.654	6431.09
15	Carriage of pipes from dumping site to actual site of work by manual labour for an Avg lead 500 mtr.				0.00
15.01	100 mm dia DI Pipe	1500.000	Mtr	9.603	14404.50
15.02	50/40/25/20/15 mm dia nominal bore	25,760	MT	355.695	9162.70
G.TOTAL					2351092.99
Negotiable rate				2.00%	Above
Alloted Cost					2398114.85
Twenty Three Lacs Ninty Eight thousands One Hundred and Fourteen only					

 **Heed Draftsman** **Tech. Officer** **Ex. Engineer PHE Div. Qozigund**

Terms & Conditions	
1	The cost of work is restricted to Rs. 2398114 /- (Twenty Three Lacs Ninty Eight thousands One Hundred and Fourteen only)
2	Earnest money deposited by you vide CDR No.3371808 Dated:- 02-09-2022 of Rs 48000/- & CDR No.3371853 Dated:- 24000/-in JK Bank Vrinag is being retained as security deposit and shall be released after as per the general terms and condition of the Contract

<p>The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating the performance of the Contract during the Contract Period</p>	<p>4 Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS codes/s</p>	<p>5 The rates are including the charges for submission of progress. Geo tagged photographs through the professional person before , during and after construction and progress reports in both hard and soft copies</p>	<p>6 The date of start of work shall be reckoned within one week form the date of issue of LOI / Contract Allotment whichever is earlier</p>	<p>7 No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever.</p>	<p>8 In case of quantity variation OR required as per the direction of the Engineer in charge , the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.</p>	<p>9 Retention many / Security deposit shall be 10% of the contract value . The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of the work and recommendation from the concerned Engineer in charge</p>	<p>10 Liquidated damages (LD) In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT: a) Terminate the contract after 15 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract. and/or e) Forfeit the performance security and blacklist the firm.</p>	<p>11 Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.</p>	<p>12 No mobilization advance shall be paid.</p>	<p>13 The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.</p>	<p>14 The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.</p>	<p>15 The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.</p>	<p>16 The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, work or safety and convenience of the Public etc</p>	<p>17 The Agency shall in advance communicate with incharge store keeper, of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required</p>
---	--	--	--	---	--	--	---	--	--	--	---	---	--	--

7995 04
25

16) As soon as letter of award is communicated to the firm, the contract shall be complete and binding on them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.

19) All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No.25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.

20) Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.

to the :-

1 Chairman District Jal Jeevan Mission (DDC) Anantnag / Kulgam for information.

2 Superintending Engineer Hydraulic Circle Anantnag for information.

3 Assistant Executive Engineer Jal Shakti (PHE) Sub-Division **Dooru** for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work does not exceed beyond the provision of allotment in any case for which he shall be personally responsible.

4 File concerned.


Head Draftsman

Tech. Officer

Ex. Engineer PHE Div.