

*Kokernag JJKM*  
2020-21

**OFFICE OF THE EXECUTIVE ENGINEER PHE, JAL SHAKTI DIVISION BIJBEHARA**

Name:- MOHD IQBAL RATHER  
S/o MOHD HUSSAIN RATHER  
R/O:- HILLER  
Regd. No:- KMR/PHED/RCR/96-97/CEE/42 OF 5/96  
GST NO. 01AFFPR5088D17P

No. *AMB/9497-95*  
Dt. *31-03-2021*  
Advt. Cost Rs 18.26 Lacs  
Alloted. Cost Rs 18.257 Lacs  
Time for completion: 20 days  
Head of Account = JJM

**Subject:-** Retrofitting of WSS Guridraman for 100% coverage of FHTC under Jal Jeevan Mission Incd. successful commissioning of entire system and maintenance for a period of 3 years after completion (Under Jal Jeevan Mission)

**Reference:-** Your Tender in response to this office e-NIT No.35 of 2020-21 issued vide No. 7695-7712 dt: 18-02-2021  
For & on behalf of Lt. Governor of Union territory of J&K, contract for above noted work is here by fixed with you on the following quoted rates :-

S.No		Qty.	Unit	Alloted Rates	Amount
1.00	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m. including getting out excavated earth and disposal of surplus excavated earth as directed: 20% ordinary rock and 80% all kinds of soil	432.00	cum	542.37	234303.84
2.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)				
2.10	25mm dia GI pipes	1200.00	Mtr	249.00	298800.00
2.20	20mm dia GI pipes	1900.00	Mtr	182.65	347035.00
2.30	15mm dia GI pipes	1500.00	Mtr	144.40	216600.00
3.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	388.80	cum	198.70	77254.56
4.00	Providing/Fixing water meter and stop cock in G I pipe line including cutting and threading the pipe and making long screws etc. complete.	398.00	No	1500	597000.00
5.00	Making connection of G I. distribution branch with G I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				
5.10	Upto 40 mm nominal bore	83.00	No	660	54780.00
Rates checked as per approved C/S				Total:-	1825773.40
					<b>Rs: 18.257 LACS</b>

*[Signature]*  
Head Draftsman

*[Signature]*  
Technical Officer

*[Signature]*  
Executive Engineer  
PHE Division Bijbehara

**Terms & Conditions**

- The cost of work should in no case exceed beyond Rs 18.257 Lacs (Rupees Eighteen Lac & Twenty Five Thousand Seven Hundred only)
- The work shall have to be completed within a period of 20 days from the date of issuance of this allotment order failing which penalty upto 10% of the total value of contract shall be imposed upon you.
- You have to attend the Divisional Office along with your enlistment card for drawl of agreement within three days from the date of issuance of this allotment order. However non drawl of agreement will not prevent the contract from being enforced upon you.
- All other terms & conditions will remain same as laid down in the original NIT / PWD form No 25- double. And FC-33

**Copy to the :-**

- SuperIntending Engineer Hyd. Circle Anantnag for favour of information
- Assistant Executive Engineer PHE Sub -Division Kokernag for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work does not exceed beyond the provision of allotment in any case for which he shall be personally responsible.
- File concerned

*[Signature]*