

OFFICE OF THE EXECUTIVE ENGINEER PHE, JAL SHAKTI DIVISION BIJBEHARA

Name:- AB GAFFAR BHAT
 /o MOHD ISMAIL
 /o HILLER
 Regd. No:- 33-DEE/SE/HYD/ANG/2008-09
 GST NO. 01AGTPR1918K1ZJ

No PHB/0342-44
 Dt 06-03-2020


Advt. Cost Rs 08.52 Lacs
 Alloted. Cost Rs 08.52 Lacs
 Time for completion: 30 days
 Head of Account = JJM


Subject:- Retrofitting of WSS Bunteng Wataldar for 100% coverage of FHTC incld. successful commissioning of entire system and maintenance for a period of 3 years after completion (Under Jal Jeevan Mission)

Reference:- Your Tender in response to this office e-NIT No.35 of 2020-21 issued vide No. 7695-7712 dt: 18-02-2021 For & on behalf of Lt Governor of Union territory of J&K, contract for above noted work is here by fixed with you on the following quoted rates :-

S.No	Qty.	Unit	Alloted Rates	Amount
1 00	285.00	cum	542.37	154575.45
Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m. including getting out excavated earth and disposal of surplus excavated earth as directed. 20% ordinary rock and 80% all kinds of soil				
2 00	1000.00	Mtr	249.00	249000.00
Providing and fixing G.I pipes complete with G.I. fittings excluding trenching and refilling etc (external work)				
2 10	1000.00	Mtr	182.65	182650.00
25mm dia GI pipes				
2 20	1000.00	Mtr	144.40	144400.00
20mm dia GI pipes				
2 30	256.50	cum	198.70	50966.55
15mm dia GI pipes				
3 00	36.00	No	1500	54000.00
Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.				
4 00				0.00
Providing/fixing water meter and stop cock in G.I pipe line including cutting and threading the pipe and making long screws etc complete Light				
5 00	25.00	No	660.00	16500.00
Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				
5 10				852092.00
Upto 40 mm nominal bore				
Rates checked as per approved C/S			Total:-	Rs: 8.52 LACS


 Head Draftsman


 Technical Officer


 Executive Engineer
 PHE, Division Bijbehara

Terms & Conditions

- The cost of work should in no case exceed beyond Rs 08.52 Lacs (Rupees Eight Lac & Fifty Two Thousand only)
- The work shall have to be completed within a period of 30 days from the date of issuance of this allotment order failing which penalty upto 10% of the total value of contract shall be imposed upon you.
- You have to attend the Divisional Office along with your enlistment card for drawl of agreement within three days from the date of issuance of this allotment order. However non drawl of agreement will not prevent the contract from being enforced upon you.
- All other terms & conditions will remain same as laid down in the original NIT / PWD form No 25- double. And FC-33

Copy to the :-

- Superintending Engineer Hyd. Circle Anantnag for favour of information
- Assistant Executive Engineer PHE Sub -Division Kokernag for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work does not exceed beyond the provision of allotment in any case for which he shall be personally responsible.
- File concerned

