

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND

Allotment Order No:PHQ/CC/ 52 of 2022-23 dated 31/08/2022			
No:PHQ/3235A.52		DATE: 31/08/2022	
NAME : Shabir Ahmad Shah S/O.Ab.Razak R/O.Chowgam			
email: shahshabir3666@gmail.com		Cell No.9797905301	
REGD. NO 20-DEE/SE/R&B/Ang-Kul/2014-15		ACCOUNT NO 0442020500000005 JK Bank Devsar	
GSTN: 01FUKPS0816M1ZE		PAN: FUKPS0816M	
Name of Schemes:- L/F of pipes incl. P/F of pipe specials WSS Kherman Ganash (UNDER JJM)			
Adminstrative Approval No.	60-DB of 2022	Dated	20-07-2022
Technical Sanction NO.	PHEQ/DB/49 of 2022	Dated	25-8-2022
Alloted Cost;	Rs:- 618055/=	Rupees; Six Lacs eighteen thousands and fifty five	
Completion Time	60 Days		

References:1. Your tender received in response to E-NIT No.13 of 2022-23 ISSUED UNDER NO:PHQ/1384-99 Dated 13/06/2022 (Tender ID: 2022_PHE_173949_36) 2. This office Corrigendum No. PHQ/CC/1620-28 dated:- 24-06-2022 and Corrigendum 2nd No: PHQ/CC/ 1680-88 Dated:- 27-06-2022

For & on behalf of Lt. Governor of J&K , contract for above noted work is here by fixed with you on your quoted percentage rates. terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Rate	Amount
1	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge :				
1 01	15 mm to 40 mm nominal bore	850 000	Mtr	99.750	84787.50
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				0.00
2 01	All Kinds of soils	499.830	Cum	436.000	217925.88
3	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe fittings, excluding cost of pipes, and Earth work				0.00
3 01	65mm dia GI Pipe	550 000	Mtr	73.050	40177.50
3 02	50mm dia GI Pipes	700 000	Mtr	40.800	28560.00
3 03	40 mm dia GI Pipes	570 000	Mtr	40.800	23256.00
3 04	25 mm dia GI pipes	570 000	Mtr	30.650	17470.50
3 05	20 mm dia GI pipes	700 000	Mtr	20.250	14175.00
3 06	15 mm dia GI pipes	200 000	Mtr	20.250	4050.00
4	Provision for installation of house connections to unconnected household including providing and fixing of necessary pipe specials, Earth work at connection and Whatever Necessary.	46.000	No	1500.000	69000.00
5	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				0.00
5 01	25 to 40 mm nominal bore	20.000	each	666.250	13325.00
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	449.840	Cum	198.700	89383.21
7	Welding charges of leaking/Damaged joints at spot etc complete job. The work should be leakproof and should be painted with anti corrosive red oxide primer complete job	20.000	No	500.000	10000.00

	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc. if required will be paid separately).				0.00
8.01	50 mm dia	2.000	No	5147.150	10294.30
9	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. (Welded)	120.000	kg	106.778	12813.36
10	Replacement of Damaged 150mm dia Sluice Valve by new Sluice Valve with all accessories and carriage complete job	1.000	job	15000.000	15000.00
11	Carriage of pipes from Divisional store Qazigund upto dumping site of work by mechanical transport avg. distance 15 KMs including loading ,unloading and Stacking complete				0.00
11.01	65,50,40,25,20, and 15 mm dia GI Pipes	9.278	MT	325.243	3017.60
12	Carriage of pipes material from road site upto actual site of work by manual labour for avg. lead of 300 mtrs.				0.00
12.01	65,50,40,25,20, and 15 mm dia GI Pipes	9.278	MT	452.686	4200.02
Grand Total					657435.87
Quoted Percentage rate		5.99%		Below	
Alloted Cost					618055.46
Rupees :- Six Lacs Eighteen thousands and Fifty Five only					


Head Draftsman


Tech. Officer

Ex. Engineer PHE Div. Qazigund

Terms & Conditions	
1	Earnest money deposited by you vide CDR No.3092373 dtd.02/07/22 JK Devsar of Rs 13748/- and CDR No. 3098072 dated:- 26-08-2022 of Rs. 6500/- is being retained as security deposit and shall be
2	Client/Paying Authority. The client/paying authority shall be the concerned Executive Engineer. Besides, the supervision of the various components of the work shall be carried out by the concerned Engineers of the Division/TPIQM consultants under the overall coordination of the concerned
3	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period
4	Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
5	The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before , during and after construction and progress reports in both hard and soft copies.
6	The date of start of work shall be reckoned within one week form the date of issue of LOI / Contract Allotment whichever is earlier.
7	No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever.
8	In case of quantity variation OR required as per the direction of the Engineer in charge , the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.
9	Retention many / Security deposit shall be 10% of the contract value. The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of the work and recommendation from the concerned Engineer in charge

	<p>Liquidated damages (LD) In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT</p> <p>a) Terminate the contract after 15 days' notice and/or</p> <p>b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or</p> <p>c) Recover the extra cost, if any, involved in allotting contract to other party and/or</p> <p>d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract and/or</p> <p>e) Forfeit the performance security and blacklist the firm</p>
11	Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.
12	No mobilization advance shall be paid.
13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
17	The Agency shall in advance communicate with incharge store keeper, of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required.
18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No.25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.
Copy to the :-	
1	Chairman District Jal Jeevan Mission (DDC) Anantnag / Kulgam for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division Dooru for information & necessary action. He will ensure the execution of works under stage contract after submission of damages reports duly recorded check certificate & proper geo tagged photographs before, during & after execution.
4	File concerned


Head Draftsman


Tech. Officer


Ex. Engineer PHE Div. Qazigund

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND
Allotment Order No: PHQ/CC/ 73 of 2022-23 dated 16/09/2022

No: PHQ/ 4205-08-09 DATE: 16-09-2022 / 16/09/2022

NAME : Mushtaq Ahmad Wani R/o Sernal Anantnag

email: shairiqbal6720@gmail.com Cell No.7006284893

REGD NO. CE/UEED/DEE/01/2004-2005 ACCOUNT NO. 0472030080000011 Jk Bank Sadiqabad

GSTN: 01ABYPW7749R128 PAN: ABYPW7749R

Administrative Approval No. 60-DB of 2022 Dated 20/7/2022

Technical Sanction No. 171-DB of 2022 Dated 22-08-2022

Alloted Cost; Rs:- 1161624/= Rupees:- Eleven Lacs Sixty One Thousands Six Hundred Seventy four only

Completion Time 90 Days

Name of Schemes: -Laying and fitting of pipes incl. P/F of pipe fittings & construction of chain link fencing around structures WSS Lalan Ganoor

References: 1. Your tender received in response to e-NIT.No.17 of 2022 -23 uploaded on tender portal vide No.PHQ/1818-33 dated 02-07-2022.(Tender ID: 2022_PHE_177435_8)

For & on behalf of Lt. Governor of J&K , contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Estd. Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				0.00
1.01	All kinds of soil	293.160	Cum	436.000	127817.76
2	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a load of 50 metres:				0.00
2.01	All kinds of soil	29.650	Cum	252.050	7475.80
3	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes and Earth work but including cost of pipe specials				0.00
3.01	100 mm dia GI pipe	61.000	Mtr	73.050	4456.05
3.02	40 mm dia GI pipe	300.000	Mtr	40.800	12240.00
3.03	25 mm dia GI pipe	500.000	Mtr	30.650	15325.00
3.04	20 mm dia GI pipe	800.000	Mtr	20.250	16200.00
3.05	15 mm dia GI pipe	600.000	Mtr	20.250	12150.00
4	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				0.00
4.01	25 to 40 mm nominal bore	10.000	Each	666.250	6662.50

5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited	252 410	Cum	198 700	50153.61
6	Providing and fixing of regulation valve etc (to be paid as per actual)				0.00
6 01	40/20/25/and 15 mm dia	2 000	No	6000 000	12000 00
7	Installation of house hold connections to unconnected households including providing and fixing of necessary pipes specials, earth work at connections whatever necessary.	34 000	No	1500 000	51000.00
8	Providing and fixing of MS Flanges to GI Pipes including cost Welding charges, nuts, bolts, washers etc complete	12.000	pair	1500.000	18000 00
9	Providing and laying of dry stone solling tightly hand packed on horizontal levels	10.510	Cum	616.400	6478.36
10	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	10.510	Cum	4861.835	51097.89
11	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	39.930	Cum	6465.195	258155.24
12	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.648	Cum	6978.675	4522.18
13	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.520	Cum	9408.135	14300.37
14	Centering and shuttering including strutting, propping etc. and removal of form for:				0.00
14.01	Foundations, footings, bases of columns etc. for mass concrete.	172 500	Sqm	262 300	45246.75

4.02	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	13.500	Sqm	573.850	7746.98
15	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1501.000	Kg	95.163	142839.66
16	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.	250.000	Kg	153.295	38323.75
17	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level: Thermo-Mechanically Treated bars of grade Fe-500D or more	152.000	Kg	91.138	13852.98
18	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in charge.	210.450	Sqm	843.525	177519.84
19	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	117.000	Sqm	260.050	30425.85
20	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	325.790	Sqm	121.950	39730.09
21	Carriage of material from source to dumping site at road by mechanical transport. Including loading, unloading and stacking complete.				0.00
21.01	Cement & steel for avg. lead of 17Km	18.440	MT	325.243	5997.48
21.02	Sand for avg. lead of 20 Km	25.080	Cum	402.293	10089.51
21.03	20mm Aggregate for avg. lead of 05 Km	47.350	Cum	224.204	10616.06
21.04	Stone solling For avg lead of 03 km	10.510	Cum	203.056	2134.12
22	Extra carriage of material from dumping site to actual site of work Avg lead 150 Mtr				0.00
22.01	Cement	15.380	MT	157.240	2418.35
22.02	steel	3.060	MT	337.732	1033.46
22.03	Sand	25.080	Cum	301.300	7556.60
22.04	20mm Aggregate	47.350	Cum	325.726	15423.13
22.05	Stone solling	10.510	Cum	354.465	3725.43
23	Carriage of pipes from divisional store up to actual site of work by M.T Avg lead 20 Km				0.00
23.01	100 mm dia	61.000	Mtr	7.993	487.57
23.02	50/40/25/20 mm dia	4.080	MT	357.535	1458.74

SHD

T.0

[Signature]
Xen

24	Carriage of pipes from dumping site to actual site of work by manual labour for an Avg lead 250 mtr .				0.00
24.01	50/40/25/20 mm	4.080	MT	243.225	992.36
Total					1225653.71
Quoted Percentage rate		5.22%		Below	
Alloted Cost					1161674.59

Rupees:- Eleven Lacs Sixty One Thousands Six Hundred Seventy four only

S.K. Head Draftsman

Tech. Officer

[Signature]
Ex. Engineer PHE Div. Qazigund


Terms & Conditions

- 1 The cost of work is restricted to Rs.1161674 /=(Eleven Lacs Sixty One Thousands Six Hundred Seventy four only)
- 2 Earnest money deposited by you vide CDR No.3107992 dated 13/07/2022 for Rs.28720/= and CDR No. 3107849 dated:- 22-09-2022 of Rs. 14400 in JK Bank Sadiqabad Anantnag is being retained as security deposit and shall be released after as per the general terms and condition of the Contract
- 3 The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period
- 4 Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
- 5 The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before , during and after construction and progress reports in both hard and soft copies .
- 6 The date of start of work shall be reckoned within one week form the date of issue of LOI / Contract Allotment whichever is earlier.
- 7 No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever.
- 8 In case of quantity variation OR required as per the direction of the Engineer in charge , the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.
- 9 Retention many / Security deposit shall be 10% of the contract value . The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of
- 10 Liquidated damages (LD): In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT:
 - a) Terminate the contract after 15 days' notice and/or
 - b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department. and/or
 - c) Recover the extra cost, if any, involved in allotting contract to other party and/or
 - d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract. and/or
 - e) Forfeit the performance security and blacklist the firm.
- 11 Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.
- 12 No mobilization advance shall be paid.


13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc.
17	The Agency shall in advance communicate with incharge store keeper of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required.
18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No.25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.

Copy to the :-

1	Chairman District Jal Jeevan Mission (DDC) Anantnag for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division Mir-Bazar for information & necessary action. He will ensure the execution of work strictly in accordance with approved proposal/guidelines under JJM. The cost of work should not exceed beyond allotted cost for which he shall be personally responsible.
4	File concerned.


Head Draftsman

Tech. Officer


Ex. Engineer PHE D.C. Qazigund