

Government of Jammu and Kashmir
Office of the Executive Engineer, Jal Shakti (PHE) Division, Pulwama

Allotment Order No. 35 Dated. 08-08-2022

Mt. Abdul Gani Khan,
Contractor,
S/o Gh Mohi-ud-Din Khan,
R/o Tantraypora, Pulwama
Regd. No. CK/PHE/S&B/Bud/15/Civil/CEE/1998-99

Sub :- Retrofitting of Water Supply Scheme Tahab old by way of laying & fitting of GI pipes, including dismantling of CGI Truss over RCC SR, providing RCC jacketing to existing SR, construction of wooden trusses over existing quarter, providing sanitary fitting to washroom, construction of ring type soakage pit and septic tank including installation of 299 No. FHTC's for Tahab old (JJM).

Ref:- 1- This office ENIT S. No. 02/PHEP of 2022-23 published under endorsement No: PHEP/193-203 Dated: 18-04-2022.
2- This office letter No. PHEP/1177-79 dated. 03-06-2022 and No. PHEP/1374-76 Dated. 14-06-2022.
3- Superintending Engineer, Hydraulic Circle Shopian's letter No. SE/Hyd/DB/1436-38 Dated. 06-06-2022 (addressed to Chief Engineer)
4- DJJM Pulwama's Minutes of Meeting held in 14-06-2022 and endorsed by Superintending Engineer Hydraulic Circle, Shopian vide No. 1773-06 Dated. 24-06-202.
5- This office Authorization Committee Endorsement No. PHEP/1924-26 Dated. 13-07-2022
6- Letter of Intent issued vide this office No. PHEP/2014-18 Dated. 16-07-2022.
7- Technical Sanction Issued vide No. 16/JJM of 28-07-2022

.....
Advertised Amount of work: ₹ 24,63,000.00
Alloted Amount of the work:- ₹ 24,63,000.00

Rupees Twenty Four Lakh(s) Sixty Three Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following rates quoted/accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	RATE
1	All items of work as per BoQ (Specified Below as Annexure A)	(@ PAR) AT PAR the Estimated Rates.

Annexure (A)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P
1	2	3	4	5
1.00	Dismantling of truss with CGI roofing including wooden beams , rafters , purlins , etc of S.R including stacking of serviceable material within 50m lead and carriage of serviceable material upto divisional store Pulwama (to be paid as per actual details/measurements)			
1.10	Carpenter 2nd class	1.00	No	666.00
1.20	Labour/helper	4.00	No	503.00
2.00	Earth work in excavation by manual means in trenches for foundations ,drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts ,wells, cesspits, and the like not exceeding 10sqm on plan ,including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	379.75	Cum	436.00
3.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	20.09	Cum	7800.76

Sub :- Retrofitting of Water Supply Scheme Tahab old by way of laying & fitting of GI pipes, including dismantling of CGI Truss over RCC SR, providing RCC jacketing to existing SR, construction of wooden trusses over existing quarter, providing sanitary fitting to washroom, construction of ring type soakage pit and septic tank including installation of 299 No. FHTC's for Tahab old (JJM).

4.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	25.66	Cum	9408.13
5.00	Reinforced cement concrete work in arches, archribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level including curing but excluding the cost of centering, shuttering finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	18.94	Cum	10404.51
6.00	Steel reinforcement for RCC work including straightening, cutting , bending , placing in position and binding all complete upto plinth level thermo -Mechanically -Treated bars of grade Fe-500D or more	3881.00	Kg	87.17
7.00	Centering shuttering including strutting , propping etc. and removal of form work for			
7.10	Foundation footings , bases for columns	150.72	Sqm	262.30
7.20	Columns, pillars, piers, abutments, posts and struts.	45.84	Sqm	680.15
7.30	Arches, domes, vaults upto 6 m span	189.48	Sqm	2086.80
7.40	Extra for arches, domes, vaults exceeding 6 m span	189.48	Sqm	1008.45
8.00	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	541.16	Sqm	260.05
9.00	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	90.00	Kg	57.90
10.00	Provision for making bypass arrangements by way of laying of pipes including earthwork excavation and refilling , providing necessary fittings i.e collars , bends if required and dismantling the same after completion of S.R and make the S.R functional	1.00	Job	5000.00
11.00	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.			
11.10	50 mm dia G.I pipes	375.00	Mtr	40.80
11.20	40 mm dia G.I pipes	1500.00	Mtr	40.80
11.30	25 mm dia G.I pipes	1000.00	Mtr	30.65
11.40	20 mm dia G.I pipes	1000.00	Mtr	20.25
11.50	15 mm dia G.I pipes	3647.00	Mtr	20.25
12.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete			
12.10	(a) 25 to 40 mm nominal bore	28.00	No	666.25
12.20	(b) Above 40 mm nominal bore	5.00	No	1268.75
13.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	189.87	Cum	198.70
14.00	Providing and fixing of sanitary items of standard quality like 1000 liters sintex , W.C Indian type , flush tank , with all accessories . pvc pipe , pipe specials , C.P items , p trap , floor trap, bends , steel sink , connecting with soakage , whichever be necessary to make functional all complete (to be paid as per actual details /measurements with supporting voucher dully verified by AEE concern)	1.00	Job	10000.00
15.00	Providing fixing supplying P.C.C rings including earthwork excavation and disposal of surplus excavated material outside the premises including providing and laying cement concrete in 1:2:4 mix over septic tank and soakage pit . construction of man hole chambers with angle iron frame and covering arrangements .providing fixing of P.V.C pipe (prince make B class) including bends whichever is required at site or as per directions of Engineer- in- charge (3 compartments for septic tank and 1 for soakage pit . (to be paid as per actual details /measurements)	13.00	Mtr	1106.00

Retrofitting of Water Supply Scheme Tahab old by way of laying & fitting of GI pipes, including dismantling of CGI Truss over RCC SR, providing RCC jacketing to existing SR, construction of wooden trusses over existing quarter, providing sanitary fitting to washroom, construction of ring type soakage pit and septic tank including installation of 299 No. FHTC's for Tahab old (JJM).

16.00	Providing fixing of poplar wood of standard quality including necessary nails , and carriage complete . (to be paid as per actual details /measurements with supporting vouchers dully verified by AEE concern)	140.00	Cft	520.00
17.00	Providing corrugated G.S sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks , bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I filled with white lead , including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal / vertical or curved surface) excluding the cost of purlins , rafters and trusses and including cutting to size and shape wherever required 0.63mm thick with zinc coating not less than 275gram/sqm	75.21	Sqm	951.80
18.00	Providing and fixing plained eaves boarding. 250x32 mm (nomlnal size)	10.65	Mtr	693.90
19.00	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete .with 0.63 mm thick with zinc coating not less than 275 gram/m2	10.00	Mtr	691.35
20.00	Providing face lifting of various structures by way of face lifting of painting , beautification of scheme leveling , dressing , repairs to electric switches , main board all complete as per the directions of Engineer-in-charge (to be paid strictly as per actual measurements a@ SSR 2020 at par)	1.00	Job	20000.00
21.00	Providing, fixing, supplying pipe specials such as nipples, bends, sockets, tail pieces, unions, gate valves, air valves subject to non availability at divisional stores and to be paid as per GST voucher item by item dully verified by AEE concerned and JE.	1.00	Job	17000.00
22.00	Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete			
22.10	Sand and Bajri avg lead 15km	158.51	Cum	341.57
22.20	Cement and steel avg lead 15km	32.22	M.T	303.64
22.30	pipes avg lead 15km	12.20	M.T	303.64
22.40	Dismantled truss/CGI roofing to Divisional store	1.00	Trip	1500.00

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- The work shall be completed within a period of (60) days months from the date of Issuance of letter of intent/allotment. The date of start shall be reckoned 07 days from the date of issuance of letter of intent/allotment
- 4- Performance Security of Rs75000/- deposited by you under CDR No. 3213519 dated. 10-06-2022 has been retained in the divisional office.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked
Head Draftsman

Tech. Officer

Executive Engineer,
Jal Shakti (PHE) Division,
Pulwama

No. PHEP/ 2497-2500

Dated. 08-08-2022

Copy to the:-

- 1- Chairman District Jal Jeevan Mission (DJJM) Pulwama for favour of information.
- 2- Superintending Engineer, Hydraulic Circle, Shopian, for information.
- 3- Assistant Executive Engineer, (JSD) PHE Sub-Div., Tahab for information and necessary action.
- 4- File Concerned.