

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND

Allotment Order No: PHQ/CC/ 63 of 2022-23 dated 10/09/2022

No: PHQ/ 63/23-25	DATE: 10/09/2022
NAME : Mohd Lateef Channa S/O Ali Mohammad R/O Srinagar	
email: aqiblateef68@gmail.com	Cell No. 7006087917
REGD SE/HYD/BEE/CIVIL/379 OF 2021-22	ACCOUNT NO 0185010100011256
GSTN: 01BDJPC0995D1Z1	PAN: BDJPC0995D
Administrative Approval No.	58-DB of 2022 ✓ Dated 20/7/2022
Technical Sanction No.	166-DB of 2022 ✓ Dated 22-08-2022
Alloted Cost; Rs:- 2690794/=	Rupees:- Twenty Six Lakhs Ninety thousands Seven Hundred and Ninety Four only
Completion Time	90 Days

Name of Schemes: -Laying and fitting of pipes incl. P/F of pipe fittings, const. of sluice chamber, const. of chain link fencing N.C Sadoora

References: 1. Your tender received in response to e-NIT No. PHQ/03_OF 2022-23 Dated: 18-04-2022 (Tender ID: 2022_PHE_167144_11) read with CORRIGENDUM-3 vide No. PHQ/CC/1060-70 Date:- 28-05-2022

For & on behalf of Lt Governor of J&K, contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Estd. Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				0.00
1.01	All kinds of soil	667.810	Cum	436.000	291165.16
1.02	Ordinary Rock	407.670	Cum	841.600	343095.07
2	Extra for every additional lift of 1.5 m or part there of in excavation/banking excavated or stacked material. All kinds of soil.	10.890	Cum	81.650	889.17
3	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, but including cost of pipe fittings.				0.00
3.01	65 mm dia. G.I. pipes	300.000	Mtr	73.050	21915.00
3.02	50 mm dia. G.I. pipes	500.000	Mtr	40.800	20400.00
3.03	40 mm dia. G.I. pipes	1200.000	Mtr	40.800	48960.00
3.04	25 mm dia. G.I. pipes	2000.000	Mtr	30.650	61300.00
3.05	20 mm dia. G.I. pipes	1500.000	Mtr	20.250	30375.00
3.06	15 mm dia. G.I. pipes	600.000	Mtr	20.250	12150.00
4	Installation of house hold connections to unconnected households including providing and fixing of necessary pipes specials, earth work at connections whatever	94.000	No	1500.000	141000.00
5	Providing and fixing MS Flanges to GI pipes including cost of cutting of threaded portion, flanges, welding, nuts, bolts, Rubber Washer and carriage etc complete job.				0.00
5.01	100mm dia G I Pipes	16.000	Pair	1500.000	24000.00
5.02	80mm dia G I Pipes	81.000	Pair	1100.000	89100.00
6	Providing and fixing of regulation valve etc (to be paid as per actual)				0.00
6.01	100/80 mm dia sluice valves	2.000	No	10000.000	20000.00
6.02	65/50/40 mm dia sluice valves	4.000	No	6000.000	24000.00

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
Ex Engineer




7	Provision for Providing and fixing of Sluice valves /Pipe specials for regulation of water supply if not supplied by deptt. Store(to be paid as per actual)				0.00
7.01	100 mm dia Sluice valve	2.000	No	8500.000	17000.00
7.02	80 mm dia Sluice valve	3.000	No	7500.000	22500.00
8	Providing and laying of dry stone solling tightly hand packed on horizontal levels	14.010	Cum	616.400	8635.76
9	Dismantailing of cement cvoncrete manually/ mechanically including disposal of material within 50m lead in 1:3:6 mix	18.000	Cum	1569.200	28245.60
10	P/L of cement concrete in 1:3:6 mix over lains /Concrete drains for embedment of GI Pipes including all carriages	12.000	Cum	7269.185	87230.22
11	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	13.470	Cum	4861.835	65488.92
12	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	27.080	Cum	7269.185	196849.53
13	Providing and laying in position specified grade of cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level. 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	9.030	Cum	8296.640	74918.66
14	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.630	Cum	7800.760	12715.24
15	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement of mix 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	7.020	Cum	9408.135	66045.11

SH/1/2

to

BR - Engineering

16	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.670	Cum	9849.345	6599.06
17	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above/up to plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more	783.000	kg	91.138	71361.05
18	Structural steel work in single sections, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Welded	2297.000	kg	95.163	218589.41
19	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	795.000	kg	153.295	121869.53
20	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in charge. Made of G.I. wire of dia 4 mm	182.340	Sqm	843.525	153808.35
21	Centering and shuttering including strutting, propping etc. and removal of form for:				0.00
21.01	Foundations, footings, bases of columns etc. for mass concrete.	75.530	Sqm	262.300	19811.52
21.02	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	157.500	Sqm	573.850	90381.38
21.03	Suspended floors, roofs, landings, balconies and access platforms	5.760	Sqm	635.600	3661.06
21.04	Edges of slabs and breaks in floors and walls Under 20 cm wide.	10.800	Mtr	242.300	2616.84
21.05	Columns, pillars, piers, abutments, posts and struts.	18.600	Sqm	680.150	12650.79
22	12mm Cement plaster of mix 1 : 4 (1 cement : 4 coarse sand)	71.580	Sqm	260.050	18614.38
23	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.	127.640	Sqm	121.950	15565.70
24	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	904.330	Cum	198.700	179690.37
25	Carriage of material from source to dumping site at road by mechanical transport. Including loading, unloading and stacking complete.				0.00

25 01	Cement & steel for avg. lead of 15 Km	17.677	MT	303.646	5367.55
25 02	Sand for avg. lead of Km	30 27.570	Cum	551.333	15200.25
25 03	20mm Aggregate for avg. lead of 30 Km	41.350	Cum	501.653	20743.35
25 04	40mm Aggregate for avg. lead of 20 Km	11.540	Cum	545.284	6292.58
25 05	Stone solling For avg lead of 10 km	13.360	Cum	330.418	4414.38
25 06	80/65/50/40/25/20 mm dia GI pipe for avg. lead of 15 Km	17.607	MT	303.646	5346.30
25 07	100 mm dia GI pipe (15)	100.000	M	9.879	987.90
26	Carriage of pipes material from road site upto actual site of work by manual labour for avg. lead of 100 mtrs.				0.00
26 01	Cement	17.625	MT	175.743	3097.47
26 02	Steel	24.502	MT	255.645	6263.81
26 03	Sand and 20mm aggregate	44.970	Cum	276.437	12431.37
26 04	40mm Aggregate	11.540	Cum	276.437	3190.08
26 05	Stone solling	13.360	Cum	300.702	4017.38
26 06	80/65/50/40/25/20/ mm dia GI pipe	17.607	MT	355.695	6262.72
26 07	100 mm dia GI pipe (100)	100.000	M	11.615	1161.50
	Total				2717974.51
	Quoted Percentage rate		1.00%	Below	
	Alloted Cost				2690794.77
	Rupees :- Twenty Six Lakhs Ninety thousands Seven Hundred and Ninety Four only				
					
	Head Draftsman	Tech. Officer	Ex. Engineer PHE Div. Qazigund		

Terms & Conditions

1	The cost of work is restricted to Rs. 2690794 (Rupees Twenty Six Lakhs Ninety thousands Seven Hundred and Ninety Four only)
2	Earnest money deposited by you vide FDR No. 347963 dated 17/08/2022 Rs.81000/= in J&K Bank Barbarshah Srinagar is being retained as security deposit and shall be released after as per the general terms and condition of the Contract
3	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period
4	Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
5	The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before , during and after construction and progress reports in both hard and soft copies .
6	The date of start of work shall be reckoned within one week form the date of issue of LOI / Contract Allotment whichever is earlier.
7	No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever.
8	In case of quantity variation OR required as per the direction of the Engineer in charge , the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.
9	Retention many / Security deposit shall be 10% of the contract value . The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of


10	Liquidated damages (LD) In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT. a) Terminate the contract after 15 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department. and/or c) Recover the extra cost, if any, involved in allotting contract to other party and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract and/or e) Forfeit the performance security and blacklist the firm.
11	Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.
12	No mobilization advance shall be paid.
13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
17	The Agency shall in advance communicate with incharge store keeper, of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required.
18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No.25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.

Copy to the :-

1	Chairman District Jal Jeevan Mission (DDC) Anantnag for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division Dooru for information & necessary action. He will ensure the execution of work strictly in accordance with approved proposal/guidelines under JJM. The cost of work should not exceed beyond allotted cost for which he shall be personally responsible.
4	File concerned.


Head Draftsman


Tech. Officer


Ex. Engineer
PHE Div.