

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND

Allotment Order No:PHQ/CC/ 117 of 2022-23 dated 05/10/2022

No:PHQ/ 4759-61	DATE: 05/10/2022
NAME :Abdul Ahad Bhat S/o Ab. Rehim Bhat R/o Gund Kilam	
email: abahadbhat987@gmail.com	Cell No.7789492647
REGD. NO:KMR/PHED/RCR/1995-96/BEE/100 of 12/1995.	ACCOUNT NO:0923040100000156 JK Bank Kilam
GSTN: 01AKFPB8831R1Z0	PAN: AKFPB8831R
Administrative Approval No.	207-DB of 2022 Dated 27-08-2022
Technical Sanction No.(Issued By C.E)	Dated
Alloted Cost; Rs:- 3705268/=	Rupees:-Thirty Seven Lacs Five thousands two hundred Sixty Eight only.
Completion Time	90 Days

Name of Schemes:-Laying and fitting of pipes and Construction of chain link fencing , construction of Retaining Wall /Anchor block for supporting pipes at spots ,WSS Maskhud/Videkhud (Under JSM)

References:1. Your tender received in response to E-NIT No.25 of 2022-23 ISSUED UNDER NO:PHQ/CC/4105-20 Dated:- 06-10-2022 (Tender ID: 2022_PHE_191181_3)

For & on behalf of Lt. Governor of J&K , contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Estd. Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				0.00
1.01	All kinds of soil	1498.17	Cum	436	653202.12
1.02	Ordinary Rock	110.45	Cum	841.6	92954.72
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	994.05	Cum	198.7	197517.74
3	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials excluding cost pipes and earth work				0.00
3.01	100 mm dia G.I pipes	600.00	Mtr	107.7	64620.00
3.02	80 mm dia G.I pipes	450.00	Mtr	73.05	32872.50
3.03	65 mm dia. G.I. pipes	700.00	Mtr	73.05	51135.00
3.04	50 mm dia. G.I. pipes	300.00	Mtr	40.8	12240.00
3.05	40 mm dia. G.I. pipes	600.00	Mtr	40.8	24480.00
3.06	25 mm dia. G.I. pipes	1000.00	Mtr	30.65	30650.00
3.07	20 mm dia. G.I. pipes	1500.00	Mtr	20.25	30375.00
3.08	15 mm dia. G.I. pipes	500.00	Mtr	20.25	10125.00
4	Provision for installation of house connections to	24.00	No	1500	36000.00

[Handwritten signature]

T.O

[Handwritten signature]


5	Providing and fixing MS Flanges to GI pipes including cost of cutting of threaded portion, flanges, welding, nuts, bolts, Rubber Washer and carriage etc complete job.				
5.01	100mm dia G.I Pipes	65.00	Pair	1450	94250.00
5.02	80mm dia G.I Pipes	57.00	Pair	1300	74100.00
6	Making connection for mains and sub mains for distribution system				0.00
6.01	50/80mm bore	8.00	No	1268.75	10150.00
6.02	25/40mm bore	24.00	No	666.25	15990.00
7	Providing and laying of dry stone setting tightly hand packed on horizontal levels	34.29	Cum	616.4	21136.36
8	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	33.69	Cum	4861.835	163795.22
9	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with. (1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	71.62	Cum	8296.64	594205.36
10	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with. (1:3:6 (1 cement : 3 coarse sand : 3 graded stone aggregate 20 mm nominal size)	44.80	Cum	7269.185	325659.49
11	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	21.06	Cum	6465.195	136157.01

7.0

12	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement of mix 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	2.43	Cum	9408.135	22861.77
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above/up to plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	231.00	kg	87.175	20137.43
14	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	225.00	kg	146.63	32991.75
15	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3615.00	kg	91.025	329055.38
16	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in charge. Made of G.I. wire of dia 4 mm	318.60	Sqm	806.85	257062.41
17	Centering and shuttering including strutting, propping etc. and removal of form for:				0.00
17.01	Foundations, footings, bases of columns etc. for mass concrete.	243.48	Sqm	262.3	63864.80
17.02	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	327.26	Sqm	573.85	187798.15
17.03	Columns, pillars, piers, abutments, posts and struts	27.11	Sqm	680.15	18438.87
18	12mm Cement plaster of mix 1 : 4 (1 cement : 4 coarse sand)	318.55	Sqm	260.05	82838.93
19	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	223.02	Sqm	121.95	27197.29
20	Carriage of material from source to dumping site at road by mechanical transport.				0.00
20.01	Cement & steel for avg. lead of 15 Km	53.39	MT	303.646	16211.66
20.02	Sand for avg. lead of 35 Km	82.56	Cum	551.333	45518.05
20.03	20mm Aggregate for avg. lead of 30 Km	125.83	Cum	501.653	63123.00
20.04	40mm Aggregate for avg. lead of 30 Km	30.35	Cum	545.284	16549.37



T.O.



20.05	Stone soling / quarry stone for avg lead of 10 km	34.29	Cum	330.418	11330.1
20.06	100/80/65/50/40/25/20/15 mm dia GI pipe	27.03	MT	303.646	8207.55
21	Extra Carriage of material from road site upto actual site of work by manual labour for avg. lead of 100mtrs.				0.00
21.01	Cement	29.07	MT	139.403	4052.45
21.02	Sand and 20mm Aggregate	113.54	Cum	255.599	29020.71
21.03	40mm Aggregate	12.12	Cum	276.322	3349.02
21.04	Stone/ Soling	14.04	Cum	300.702	4221.86
22	Extra Carriage of material from road site upto actual site of work by manual labour for avg. lead of 500 mtrs				0.00
22.01	100/80/65mm dia G.I Pipe	19.40	Mtr	282.095	5472.64
	Total				3920918.61

Quoted Percentage rate

5.50% Below

Allotted Cost

3705268.09

Rupees:- Thirty Seven Lacs Five thousands two Hundred and Sixty Eight only

Head Draftsman

Tech. Officer

Ex. Engineer PHE Div, Qazigund

Terms & Conditions

1	The cost of work is restricted to Rs.3705268 (Thirty Seven Lacs Five thousands two Hundred and Sixty Eight only)
2	Earnest money deposited by you vide CDR 3093522 dated:- 11-10-2022 for an amount of Rs. 80000/= and CDR No. 3093533 dated:- 18-10-2022 of Rs. 40000/= in JK bank Kilam. is being retained as security deposit and shall be released after as per the general terms and condition of the Contract
3	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period
4	Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
5	The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before, during and after construction and progress reports in both hard and soft copies.
6	The date of start of work shall be reckoned within one week from the date of issue of LOI / Contract Allotment whichever is earlier.
7	No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever.
8	In case of quantity variation OR required as per the direction of the Engineer in charge, the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.
9	Retention money / Security deposit shall be 10% of the contract value. The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of the work and

10	Liquidated damages (LD): In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT a) Terminate the contract after 15 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract and/or e) Forfeit the performance security and blacklist the firm.
11	Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.
12	No mobilization advance shall be paid.
13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
17	The Agency shall in advance communicate with incharge store keeper, of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required .
18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award .
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No.25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.
Copy to the :-	
1	Chairman District Jal Jeevan Mission (DDC) Anantnag for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division Qazigund for information & necessary action. He will ensure the execution of work strictly in accordance with approved proposal/guidelines under JJM. The cost of work should not exceed beyond allotted cost for which he shall be personally responsible.
4	File concerned.


Head Draftsman

Tech. Officer


Ex. Engineer PHE Div. Qazigund