

Government of Jammu & Kashmir
Office of the Executive Engineer, PHE (Jal Shakti) Division Chadoora

ALLOTMENT LETTER (JJM)

No: PHEDC/6306-08
 Dated: 15-11-2022

M/S: Mohammad Yousuf Paul
 S/o: Ab Karim Paul
 R/o: Ganjibagh Chadoora
 Regd: SE/Hyd/Sopore/AYY/2004-05
 GST Tin: 01AQDPP4948B1Z7
 Pan No: AQDPP4948B

Adv. Cost: Rs.94.83 lac (Ninety Four lacs Eighty Three Thousand only)
 Allotted Cost: Rs.8812415.00 (Rupees Eighty Eight Lacs Twelve Thousand Four Hundred Fifteen only)
 Earnest Money: Rs.189660.00
 Time of completion: 50 days
 Head of account: Jal Jeevan Mission (JJM)

Subject: Allotment for: Laying and Fitting/testing and commissioning of pipes WSS Bugam-Doonwari.

- Reference:**
- Your tender in response to this office e-NIT No: 05/PHEDC of 04/2022 (2022-23) issued vide endorsement No: PHEDC/296-307 Dated. 19-04-2022.
 - Chief Engineer, Kmr. Jal Shakti PHE Department Srinagar's No. CE/PHE/MC/DB/13745-83 Dated. 26-07-2022.
 - District Dev. Commissioner, Budgam's Authorization No. 6027-47 Dated 01.08.2022.
 - Superintending Eng., Hyd. Circle Budgam's No. SE/Hyd/Bud/2640-42 Dated 01-08-2022.
 - This office L.O.I No. PHEDC/3337-44 Dated: 04-08-2022.

For and on behalf of the Lt Governor of Jammu & Kashmir UT the contract for above noted work is fixed with you on the following quoted rates, terms and conditions:

S.	Items of work	Qty.	Unit	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All kinds of Soil	2576.00	Cum	436.00	1123136.00
2	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil	5238.00	Cum	188.75	988672.50
3	Metalled Surface	455.00	Cum	646.05	293952.75
4	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe): 200/150/100/80mm dia DI pipes	1346.99	Qtl	245.55	330753.39
5	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket: 200mm dia pipes	156.00	No	213.00	33228.00
6	150mm dia pipes	274.00	No	144.70	39647.80
7	100mm dia pipes	819.00	No	89.70	73464.30
8	80mm dia pipes	365.00	No	80.50	29382.50
9	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work: 65 mm dia G.I pipes	1300.00	Rm	73.05	94965.00
10	50 mm dia G.I pipe	5300.00	Rm	40.80	216240.00
11	40 mm dia G.I pipes	3000.00	Rm	40.80	122400.00
12	25 mm dia G.I pipes	5000.00	Rm	30.65	153250.00
13	20 mm dia G.I pipes	4460.00	Rm	20.25	90315.00
14	Making connection of G.I. distribution branch with G.I. main of following sizes by P/F Tee, including cutting and threading the pipe etc. complete: 15 to 40mm nominal bore	150.00	No	666.25	99937.50
15	50 mm to 80 mm dia nominal bore	30.00	No	1268.75	38062.50
16	Manufacture / Providing and fixing of MS Flanged joints including cutting of pipes, threads, cost of nuts bolts, rubber jams, testing (complete): 200mm dia.	30.00	Joints	3480.00	104400.00
17	150mm dia	30.00	Joints	2150.00	64500.00

Drawing Branch

H/D
 15/11/22
 Binjy

(Signature)
 Ex. Engineer

Government of Jammu & Kashmir
Office of the Executive Engineer, PHE (Jal Shakti) Division Chadoora
ALLOTMENT LETTER (JJM)

No: PHEDC/6306-00
 Dated: 15-11-2022

18	100mm dia	32.00	Joints	1520.00	48640.00
19	80mm dia	32.00	Joints	1100.00	35200.00
20	65mm dia	30.00	Joints	1000.00	30000.00
21	Fabrication and Providing and fixing of MS Flanged bends, Tee's etc at required spots including earthwork refilling and all carriages: 150mm dia	6.00	No	15000.00	90000.00
22	100mm dia	16.00	No	12000.00	192000.00
23	80mm dia	16.00	No	9000.00	144000.00
24	65mm dia	8.00	No	3600.00	28800.00
25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	7253.00	Cum	198.70	1441171.10
26	P/fixing of 50mm dia C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions complete (The tail pieces, tapers etc. if required will be paid separately)	5.00	No	5147.15	25735.75
27	P/F of ISI make sluice valve including all carriages upto site of work including cost of tail pieces, nuts bolts, MS flanges complete (Kirkoskar or Zolto make): 200mm dia sluice valve	3.00	No	35000.00	105000.00
28	150 mm dia sluice valve	8.00	No	30000.00	240000.00
29	100 mm dia sluice valve	8.00	No	20000.00	160000.00
30	80 mm dia sluice valve	5.00	No	16000.00	80000.00
31	200mm dia NRV	2.00	No	45000.00	90000.00
32	100mm dia NRV	1.00	No	20000.00	20000.00
33	Providing and Laying of 100 mm Dia MS Flanged pipes for rising main including all carriages from SR to 2 No. OHT's.	1300.00	Mtr	1233.33	1603329.00
34	Setting right the damages by way of stabilization and strengthening of joints, tightening of sockets, arresting of leakages etc.including earth work , refilling & fixing of double collars joints n/sockets	90.00	No	1200.00	108000.00
35	Pulging of leakages & rectification of damaged pipe spots by way of welding to G.I pipes at vulnerable spots at site including earth work in excavation & refilling complete job.	50.00	Job	3000.00	150000.00
36	Providing and fixing of pipe specials during execution of works.: 40 mm dia G.I elbow	150.00	No	250.00	37500.00
37	25 mm dia G.I elbow	150.00	No	200.00	30000.00
38	20 mm dia G.I elbow	150.00	No	150.00	22500.00
39	40 mm dia G.I Union	150.00	No	350.00	52500.00
40	25 mm dia G.I Union	150.00	No	250.00	37500.00
41	20 mm dia G.I Union	150.00	No	150.00	22500.00
42	40x25mm G.I Reducer	150.00	No	140.00	21000.00
43	25x20mm G.I Reducer	150.00	No	110.00	16500.00
44	40 mm Dia G.I Nipple	150.00	No	60.00	9000.00
45	25 mm Dia G.I Nipple	150.00	No	50.00	7500.00
46	20 mm Dia G.I Nipple	150.00	No	40.00	6000.00
47	Carriage of pipes by Mechanical transport from store upto dumping site of work including loading , un-loading and stacking etc avg lead 10 Kms: 200 mm dia D.I pipe	850.00	Mtr	14.47	12299.50
48	150 mm dia D.I pipe	1500.00	Mtr	8.90	13350.00
49	100 mm dia D.I pipe	3500.00	Mtr	5.33	18655.00
50	80mm DI pipe and 65mm to 20mm dia G.I pipe	80.28	MT	217.09	17427.99
				Total:	8812415.5

(Rupees Eighty Eight Lacs Twelve Thousand Four Hundred Fifteen only)

(Rates & quantity checked)

Head Draftsman




Executive Engineer
 Jal Shakti PHE Division
 Chadoora



Drawing Branch

Terms and conditions

1. The work shall have to be started by you at site immediately and ensure its successful completion within period of 150 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the shall have to be executed through any other means at your risk and cost, besides, the CDR deposited by you security against this contract shall be forfeited.
2. Date of start of the work shall be reckoned with in 07 days from the date of issue of LOI. However, date of start for laying and fitting of pipes will start within two days of issuance of pipe materials by the department.
3. An agreement shall have to be drawn up by you with the department within a period of 7 days from the date of issuance of allotment failure to execute such a formal deed shall however prevent the contract from being enforced upon you.
4. The allotted works shall be subject to check by third party monitoring agency appointed by the department.
5. Payment shall be released as per actual and measured work done not less than 20% of allotted cost.
6. Performance security equivalent to 03% of the value of the contract is to be deposited by you in shape of CDR/FDR/Bank Guarantee valid for a period of 03 months beyond expiry of warranty period of the contract.
7. The firm shall be bound for satisfactory performance of works for 03 months after the successful commissioning of the work. If during warranty period any malfunctioning/defect arises, you shall have to rectify the same within a period of ten days of receipt of intimation. In case of any failure on your part, then department may get the defects removed/repared any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under relevant clause of contract including black listing.
8. After testing and commissioning of works you shall have to make a trial run of the works for a period of three months during which you have to operate and maintain the executed works to the full satisfaction of the department.
9. Any item of work not included in the allotment but required for the completion of the work, shall be executed by the contractor, as directed by the department. Such extra item shall be paid at J&K SSR 2020 rates with allotted appreciation/depreciation of the contractor. In case such item does not figure in J&K SSR 2020, the same shall be paid as per the current market rate analysis, to be approved by the competent authority.
10. The defect liability period shall be for a period of 12 months and shall commence after the successful completion of trail run.
11. The advertised quantities in the tender documents are tentative and subject to increase or decrease, depending upon actual requirement at site as per the design and other considerations.
12. Pre & post geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
13. All other terms and conditions shall be applicable as laid down in standard bidding document (SBD) and PWD form No. 25/33.
14. Any rules/terms and conditions if not stipulated in the bidding document, shall be strictly deemed in accordance with the relevant rules/guidelines stipulated in General Financial Rule (GFR-2017) and manual for procurement of works 2019 G.O.I.
15. The agency shall adhere to and comply with orders and instructions of the Engineer in charge and Third Party Inspection and Monitoring Agency and any other verification agency.
16. CDR No. 3079481 dated 29/05/2022 Rs: 95000/-
CDR No. 3079482 dated 09/05/2022 Rs: 100000/-


Executive Engineer,
Jal Shakti PHE Division
Chadoora

Copy to the:

1. Chief Engineer, Kashmir Jal Shakti PHE Department Srinagar, for favour of information.
2. Superintending Engineer Hydraulic Circle Budgam (Member Secretary DJJM) for favour of information.
3. Assit. Ex. Engineer Jal Shakti PHE Sub-Division _____ for Information and necessary action. He shall ensure execution of work as per JJM guidelines, monitoring by TPIMA, and observance of all relevant IS codes and Government Orders in vogue.
4. M/S WAPCOS Ltd. Humhama for information.
5. AAO/Head Draftsman of Divisional office for information.