## OFFICE OF THE EXECUTIVE ENGINEER R.W.S. DIVISION SRINAGAR / GANDERBA

\*\*\*\*\*

Slo Abdul Hamid Paswal,

Mohammad Ismail Paswal.

→ Mohammad Ismail Paswal.

R/o: Haknar Kangan.

Class:- DEE

Regd.No:- 534/DEE/CE/KCC/PDC of 2009-10.

Advertised cost :- 0.70 Lacs

Allotted Cost :- Rs.56,000/-

Time of completion: - 05 Days

Head of Acct. :- JJM

Fixation of contract for, Providing water supply facilities to Anganwari Center at Arhama-A; Sub:-Kurag-A; Panchayat Ghar at Anderwan-A; Panchayat Ghar at Anderwan-B & Panchayat Ghar at Manigam-B by way of laying/fitting of G.I. Pipes of RWS Sub-Division Ganderbal.

Your tender in response to this office Short term e-NIT No:- 39/PHE/JSD/RWSD/Civil of 2020-21 (S. Ref:-No.03). Issued under No:-10322 – 46, dated:- 22.01.2021.

For and on behalf of the Lieutenant Governor of J&K U.T. the above noted work is hereby allotted to you, on your quoted rates, terms & conditions as laid down here under :-

A). RAT S. No.	PARTICULARS	QTY.	Unit	RATE (Rs.)	AMOUNT (Rs.)
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: 1 meter from cutting edge				
1.1	In all kinds of soils	44.40	Cum	300.00 (Three hundred)	13320.00
1.2	Ordinary rock	19.03	Cum	700.00 (Seven hundred)	13321.00
2	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.				,
2.1	20 mm dia G.I. pipes	635.00	RM	30.00 (Thirty)	19050.00
3	Filling available excavated earth excld. rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to	57.09	Cum	100.00 (One hundred)	5709.00
4	1.5m.  Dismantelling of dry stone masonary garden walls by way of manual labour including construction of same	11.23	Cum	50.00 (Fifty)	561.50
5	Carriage of pipes from divisional store up to dumping/ actual site of work, including loading, unloading and stacking etc. complete by Mechanical Transport for an Avg. lead of 15 Kms.				-
5.1	pipes .	0.90	M.T.	200.00 (Two hundred)	180.00
6	Provision for pipes & pipe specials	1.00	Job	3858.50 (Three thousand eight hundred fifty eight point fifty)	3858.50
				G. Total :-	56,000/-

Rates & Qty. Checked As per Comparative Statement

B). Terms and Conditions:-

This letter of allotment and tender of the contractor will constitute a legal contract and the conditions as laid down in the detailed NIT/PWD form No:-25 & 33 (Double leaf) and hold good even before the drawal of agreement between the contractor and the Department.

The contractor is directed to attend the Divisional Office along-with his registration card for drawal of an agreement within a period of (07) days from the date of issuance of this letter of allotment and non-drawal of agreement with the Department does not exclude you from contractual obligations.

(K.T.O)

The total amount of the work on your above quoted rates works out to be Rs. 56,000/- (Rupees; Fifty six thousand) on

4. The work is to be completed within a period of 05 days to be reckoned after 3 days from the date of issue of this att. case of any delay caused in the execution of work, penalty upto 10% shall be imposed upon the contractor or the depoling Re shall be at liberty to terminate the contract in part or in full (as the case may be) and the contract shall be completed through same other available sources at the risk and cost of the defaultiy agency after serving not more than two notices which should st be strictly noted.

CDR No:- 0405814 dated:-28.01.2021 for Rs.1400/- is retained in the divisional office as security against the said work and will be released after successful testing, commissioning and handing over the complete contract to the department and additional performance deposit in the shape C.D.R bearing Nos:- 0405813 dated:-28.01.2021 for Rs.2700/- &

No.3121945 dated:-08.02.2021 for Rs.800/- only.

6. 10% of the amount of the bill shall be retained as "Normal Deposit" in all payments and suitable amount as may be deemed fit shall be held back for successful water test / commissioning of work till defective liability period.

7. All other terms and conditions will be the same as laid down in the detailed Master NIT of the year / PWD form No:-25 double

agreement form.

Executive Engineer. Division Ganderbal/ Sgr.

No:- RWS/Allot/21/12581-85 Dated: 20 - 02 - 204

## Copy to the:-

Superintending Engineer Hydraulic Circle Srinagar for favour of information.

Asstt. Ex. Engineer R.W.S. Sub-Division Ganderbal for information and n/action. He is directed to ensure the work is executed strictly within the provision of the estimate. The progress of work should be strictly monitored and incase of slow progress proper time bound notice should be issued to the contractor and incase the contractor fails to accelerate the progress of work, the case should be recommended for termination and action under rules shall be initiated against the 3.

Head Draftsman Divisional Office for information.

A.A.O. Divisional Office for information.