

10
OFFICE OF THE EXECUTIVE ENGINEER (JSD) PHE DIVISION BARAMULLA

Email: kmrphebla@gmail.com (FAX) 01952234575 (Tel) 01952234244

No. 6247-58
dt. 12-9-022

Page No. 68

M/s. Mohammad Maqbool Ganaie & Sons
R/o. Doubgah Sopore
Regd No.

Sub: Retrofitting of W.S.Scheme Achbal Doabgah by way of :- Laying and fitting of Main /Submain /Distribution System at various spots and RCC Jacketting to old PSY for providing 100% FHTC) under JJM.

- Ref: 1/- Constitution of District JalJeevan Mission, Administrative Council Decision No: 23-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 120 Dated: 24-04-2020.
2/- UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).
3/- Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.
4/- Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.
5/- District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No. SE/Hyd/DB/4538-50 dated 22.07.2022.
6/- Your tender received in response to this office ENIT No: 24 of 05/2022 (S. No: 09)
7/- This office LOI No. PHE/Bla/4158-72 dated 21.07.2022

1/- Amount of work advertised: 835000

2/- Allotted cost of work: 831015.00

(Rupees Eight Lacs Thirty One Thousand Five Hundred Only)

3/- Time of completion: (30 days)

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory the above noted work is hereby allotted to you on quoted rates given in the Annexure of this allotment, on the terms and conditions given here under :


Conditions:


01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of 30 days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. Earnest Money amounting to the tune of Rs. 167000 deposited by you on CDR No. 3145595 Dated 14-6-022
04. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal agreement shall however prevent the contract from being enforced upon you.
05. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
06. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
07. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of

[Handwritten signature]

- allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 08. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 09. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 10. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 11. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 12. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 13. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14. Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

(Encl: Annexure "A")


Technical Officer to
 Executive Engineer
 PHE Division Baramulla


Executive Engineer
 Jal Shakti Department
 PHE Division Baramulla

Copy to the :-

- 1/- Mission Director, Mission Directorate JalJeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 2105-14 Dated: 04-06-2022.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- File Concerned.

Comp. by: ShahidFarooq (Correspondence)

eProcurement System Government of Jammu And Kashmir

Annexure "A"

Work:

of W.S.Scheme Achbal Doabgah by way of :- Laying and fitting of Main /Submain /Distribution System at various spots sketting to old PST (for providing 100% FHTC) under JJM.


	Description of Work / Item(s)	No.of Qty	Units	Rate	Total Amount
	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1	All kinds of soil.	770.580	Cum	433.820	334293.016
2	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	7.880	cum	9361.094	73765.423
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	343.500	Kg	86.739	29794.889
4	12mm Cement plaster finished with a floating coat of neat cement of mix: 1 : 4 (1 cement : 4 fine sand)	66.720	sqm	323.823	21605.454
5	Centering and shuttering including strutting, propping etc. and removal of form for:- Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	42.180	sqm	570.981	24083.968
6	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work.			0.000	0.000
6.1	15 mm dia. nominal bore	1812.000	Mtr	20.149	36509.535
6.2	20 mm dia. nominal bore	1500.000	Mtr	20.149	30223.125
6.3	25 mm dia. nominal bore	1000.000	Mtr	30.497	30496.750
6.4	40 mm dia. nominal bore	1000.000	Mtr	40.596	40596.000
6.5	50 mm dia. nominal bore	1000.000	Mtr	40.596	40596.000
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	693.520	cum	197.707	137113.412
8	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete			0.000	0.000
8.1	25 to 40 mm nominal bore	3.000	No	662.919	1988.756
8.2	50 to 80 mm nominal bore	2.000	No	1262.406	2524.813
9	Providing and fixing gun metal gate valve with C.I. wheel of approved quality incl. all accessories and all carriages complete.			0.000	0.000
9.1	25 mm nominal bore	2.000	No	541.131	1082.262
9.2	40 mm nominal bore	2.000	No	701.177	1402.353
9.3	50 mm nominal bore	3.000	No	938.036	2814.109
9.4	60 mm nominal bore	2.000	No	1561.006	3122.012

(10)

Description of Work / Item(s)	No.of Qty	Units	Rate	Total Amount
Manufacturing providing fixing of MS Bends/ Tees Including range of welding machine upto site of work incl. cost of nuts, nuts, rubber washers etc., complete job.	30.000	Kg	208.950	6268.500
Removal of old plaster or skirting, raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.	66.720	sqm	35.173	2346.759
Carriage of material from source to dumping site of work by Mechanical Transport including loading unloading and stacking etc.			0.000	0.000
Pipes (below 100mm dia) for 15 Kms	12.670	M.ton	302.128	3827.959
Cement /Steel avg. lead 18 KMs	3.500	M.ton	334.362	1170.266
Sand for 06 Kms	3.550	Cum	220.085	781.302
Stone Aggregate 20mm for 40 Kms	7.090	Cum	650.003	4608.519
Total				831015.18

(Rupees Eight Lacs Thirty One Thousand Fifteen Only)

Qty checked by:

Head Draftsman


Technical Officer


Executive Engineer
PHE Division Baramulla
