



**UNION TERRITORY OF JAMMU & KASHMIR**  
**OFFICE OF THE EXECUTIVE ENGINEER PHE (JAL SHAKTI) GROUND WATER DIVISION**  
 BAGHI-ALI-MARDAN, NOWSHARA SRINAGAR.



E-mail: - [phegwd@yahoo.com](mailto:phegwd@yahoo.com) Tel. No:- 0194-2411285 Fax No: - 0194-2411285.

\*\*\*\*\*

M/S E.O.S. Healthcare Prop:Sangeet Stanley  
 R/o. Stanley Building Kochi,  
 (Lead Partner JV M/S E.O.S.Healthcare & M/S Maruti Engineering)  
 E-mail ID. eos.kochi@gmail.com.

No:PHE/GWD/7432-41  
 Dated: 16-03-2023

**ALLOTMENT ORDER NO: PHE/GWD/JJM/132 OF 03/2023**  
**DATED: 16-03-2023.**

Sub: Formal allotment for Construction of Production tube well at W.S. Scheme Shiward Ratherporam Panzgam, Anantnag under Jal Jeevan Mission (JJM).

- Ref: i) Chief Engineer, Kashmir Jal Shakti (PHE) Department Srinagar's e-NIT No: 02 of 2022-23 Dated: 22-07-2022 issued under endorsement No: CE/PHE/DB/13307-19 Dated: 22-07-2022 read with corrigenda, I.  
 ii) UT Level committee meeting held on 28-10-2022 and 12-11-2022 under the Chairmanship of Development Commissioner Works PW (R&B).  
 iii) Chief Engineer, Kashmir Jal Shakti (PHE) Department Srinagar's fixation of Rate Contract issued vide No: CE/PHE/JJM/41246-61 Dated:06-02-2023.  
 iv) Chief Engineer, Kashmir J.S. (PHE) Department Srinagar's fixation of Rate Contract issued vide No: CE/PHE/JJM/E&T/32387-431 Dated: 28-11-2022, for "Construction of Production wells in different Divisions/Districts of Kashmir Province under Jal Jeevan Mission (JJM).  
 v) Superintending Engineer, PHE Hydraulic Circle Anantnag / Kulgam's authority letter No: SE/Hyd/Cors/12170-74, Dated: 15-02-2023.  
 vi) This office letter No: PHE/GWD/6367-74 Dated: 16-02-2023 & No: PHE/GWD/6839-45 Dated: 03-3-2023

Dear Sir,

For and on behalf of Lieutenant Governor of Jammu and Kashmir, the contract for Construction of Production tube well at W.S. Scheme Shiward Ratherporam Panzgam, Anantnag under Jal Jeevan Mission (JJM) is allotted to you with contract value of Rs. 33,88,000.00 (Rupees: Thirty-three lacs & Eighty-eight thousand only) on the following rates, terms and conditions as per Annexure "A" & "B"

S.No	Items of NIT	Unit	Qty.	Rate	Amount
1.	Boring /Drilling bore well of required dia for casing /strainer pipe, by suitable method prescribed in IS 2800 (Part-1), including collecting samples from different strata preparing and submitting strata chart/bore log, including hire and running charges of all equipment tools plants and machineries required for the job, all complete as per direction of Engineer-in-Charge upto 90 m depth below ground level				
1.1	All Kinds of soil (Diameter of casing/Strainer pipe of 250 mm.	Mtr	90	Rs.10900/-	981000.00
2.	Boring/drilling bore well of required dia for casing /strainer pipe, by suitable method prescribed in IS 2800 (Part-1), including collecting samples from different strata preparing and submitting strata chart/bore log, including hire and running charges of all equipment tools plants and machineries required for the job, all complete as per direction of Engineer-in-Charge beyond 90 m & upto 150m depth below ground level.				
2.1	All Kinds of soil (Diameter of casing/Strainer pipe of 250 mm.	Mtr	60	Rs.11800/-	708000.00



3.	Grovel packing in tube well construction in accordance with IS: 4097, including providing gravel fine/ medium/coarse in required grading and sizes as per actual requirement all complete as per direction of Engineer in-charge.	Cum	30	Rs.9000/-	270000.00
4.	Supplying, assembling, lowering and fixing in vertical position in bore well, ERW (Electric Resistance Welded)FE 410 mild steel screwed and socketed /plain ended casing pipes of required dia, conforming to IS: 4270 of reputed & approved make, including painted with outside surface with two coats, of anticorrosive paint of approved brand and manufacture including required hire & labour charges, fitting and accessories, all complete for all depths, as per direction of Engineer-in charge 250mm nominal dia having wall thickness as per IS: 4270.	Mtr	110	Rs.7500/- Mtr	825000.00
5.	Supplying, assembling, lowering and fixing in vertical position in bore well, ERW (Electric Resistance Welded)FE 410 plain slotted (having lot of size 1.6/3.2 mm)mild steel threaded and socketed/plain bevel ended pipes (type-A) of required dia and wall thickness conforming to IS:8110, of reputed & approved make having including painted with outside surface with two coats of anticorrosive bitumestic paint of approved brand and manufacture including required hire and labour charges fitting ad accessories all complete for all depths as per direction of Engineer in-charge. 250 nominal size dia.	Mtr	40	Rs. 9100/-	364000.00
6.	Development to tube well in accordance with IS: 2800 (Part-1) and IS:11189 to establish maximum rate of usable water yield without sand content (beyond permissible limit) with required capacity air compressor ruing the compressor for required time till well is fully developed measuring yield of well by "V" notch method or any other approved method measuring static level and draw down etc. by step draw down method collecting water sample & getting tested in approved laboratory I/c disinfection of tube well all complete including required hire and labour charges of air compressor tools and accessories etc. all as per direction of Engineer In-charge.	Job	01	Rs.240000/-	240000.00
Rs. Thirty-three lacs and Eighty-eight thousand only)				TOTAL Rs.	33,88,000.00

Head Draftsman

Technical Officer

Executive Engineer  
Jal Shakti PHE Ground Water Div.  
Srinagar

Contd....3<sup>rd</sup>. page.