

Office of the Executive Engineer P.H.E Division Awantipora

Tabid Ahmad Bhat
S/O: Abdul Rehman Bhat
R/O: Batgund Tral
Reg. No.: SE(R&B)SB-D-196 of 2018-19
GST No.: 01DVPPB9987J1ZY
PAN No.: DVPPB9987J

No.PHE/AWP/ 7122-30
Dated: 1-3-23

Subject:- Construction of Pump House cum Operator Quarter for WSS Khangund Gujrabasti under JJM

- Reference:- 1) Your tender in response to this office E-NIT No. 58/PHA of 2022-23 (e-tendering) issued under endorsement no: PHA/AWP/5727-37 Dated: 13.12.2022, Tender ID :2022_PHE_199514_8 and date extension notice no: PHA/AWP/5709-19 Dated: 24.12.2022.
2) Administrative Approval accorded by Superintending Engineer Hydraulic Circle Pulwama/Shopian vide order no: SE/HYD/SPN/25 of 06/2021-22 Dated: 15.06.2021.
3) Tech. Sanction No. CE/PHE/DB/623 of 09/2022 dated:- 15/09/2022.
4) Minutes of Meeting DJJM Pulwama held on 01/02/2023 endorsed vide No: SE/HYD/SPN/DB/7219-31 Dated: 01.02.2023.

For and on behalf of lieutenant Governor of Union Territory of Jammu & Kashmir, contract for above mentioned work is hereby fixed with you at the following quoted rates, terms conditions .

Advertised Cost:- Rs 13.44 lacs

Allotted Cost:-Rs 13.846 lacs
(Rupees Thirteen Lac Eighty Four Thousand and Six Hundred) only

S.No	Particulars of Items	Units	Quantity	Allotted Rate	Amount	
					In figures	In words
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All kinds of soil	Cum	45.58	449.08	20469.07	Rupees Twenty Thousand Four Hundred SixtyNine Paise Seven Only
2	Providing and laying of dry stone soling tightly hand packed on horizontal levels.	Cum	24.58	634.89	15605.65	Rupees Fifteen Thousand Six Hundred Five Paise SixtyFive Only

8
W

Handwritten signatures and initials, including a date stamp 9/1/23 and the initials 'EN' and 'CH'.

Construction of Pump House cum Operator Quarter for WSS Khangund Gujarbasti under JJM

3	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	12.48	4552.45	56814.52	Rupees FiftySix Thousand Eight Hundred Fourteen Paise FiftyTwo Only
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	Cum	31.37	5091.70	159726.69	Rupees One Lakh FiftyNine Thousand Seven Hundred TwentySix Paise SixtyNine Only
5	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	7.85	7304.35	57339.13	Rupees FiftySeven Thousand Three Hundred ThirtyNine Paise Thirteen Only
6	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	8.75	9222.57	80697.47	Rupees Eighty Thousand Six Hundred NinetySeven Paise FortySeven Only
7	Brick work with common burnt clay (non-modular) bricks of class designation 7.5 in foundation and plinth including curing in :Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	25.16	6369.26	160250.64	Rupees One Lakh Sixty Thousand Two Hundred Fifty Paise SixtyFour Only
8	Extra for brick work with common burnt clay bricks/cement concrete bricks in superstructure above plinth level upto floor five level	Cum	25.16	1363.36	34302.13	Rupees ThirtyFour Thousand Three Hundred Two Paise Thirteen Only

Handwritten signature and date: 21/11/21

Construction of Pump House cum Operator Quarter for WSS Khangund Gujarbasti under JJM

9	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	Sqm	75.46	270.17	20386.95	Rupees Twenty Thousand Three Hundred EightySix Paise NinetyFive Only
9.01	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	74.12	591.07	43809.77	Rupees FortyThree Thousand Eight Hundred Nine Paise SeventySeven Only
10	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs or with dash fasteners shall be paid for separately):Second class kail wood	Cum	0.94	94827.31	89137.67	Rupees EightyNine Thousand One Hundred ThirtySeven Paise SixtySeven Only
11	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note: - Butt hinges and necessary screws shall be paid separately).Second kail wood	Sqm	18.34	2828.33	51871.54	Rupees FiftyOne Thousand Eight Hundred SeventyOne Paise FiftyFour Only
12	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick. Decorative ply wood both side decorative veneer (type 1) conforming to IS 1328 BWR type	Sqm	3.74	2431.78	9094.85	Rupees Nine Thousand NinetyFour Paise EightyFive Only
13	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Welded	Kg	1355.75	95.64	129657.83	Rupees One Lakh TwentyNine Thousand Six Hundred FiftySeven Paise EightyThree Only

it No.PHE/A

e of
ning

.2022

ation
Bl

led
up

[Handwritten signature and initials]

Construction of Pump House cum Operator Quarter for WSS Khangund Gujrabasti under JJM

14	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	175	137.30	24027.33	Rupees TwentyFour Thousand TwentySeven Paise ThirtyThree Only
15	Providing corrugated G. S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface)excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.0.63 mm thick with zinc coating not less than 275 gram/m ²	Sqm	59.56	980.35	58389.88	Rupees FiftyEight Thousand Three Hundred EightyNine Paise EightyEight Only
16	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gram/m	Mtr	30.48	712.09	21704.52	Rupees TwentyOne Thousand Seven Hundred Four Paise FiftyTwo Only
17	15mm Cement plaster on the rough side of single or half brick wall of mix: 1 : 6 (1 cement : 6 fine sand)	Sqm	117.75	286.96	33789.30	Rupees ThirtyThree Thousand Seven Hundred EightyNine Paise Thirty Only
18	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on New work (two or more coats) over and including priming coat with water thinnable cement primer	Sqm	117.75	153.52	18077.16	Rupees Eighteen Thousand SeventySeven Paise Sixteen Only
19	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats	Sqm	298.2	125.61	37456.45	Rupees ThirtySeven Thousand Four Hundred FiftySix Paise FourtyFive Only
20	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm	Sqm	70.62	94.55	6677.40	Rupees Six Thousand Six Hundred SeventySeven Paise Fourty Only

Handwritten signature and initials

Construction of Pump House cum Operator Quarter for WSS Khangund Gujrabasti under JJM

21	Providing and fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : 4.0mm thick glass panes	Sqm	13.86	966.86	13400.69	Rupees Thirteen Thousand Four Hundred Paise SixtyNine Only
22	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 50 mm thick with 20mm nominal size stone aggregate	Sqm	37.91	520.15	19718.89	Rupees Nineteen Thousand Seven Hundred Eighteen Paise EightyNine Only
23	Providing and fixing Glass strips in joints of cement concrete floors.	Mtr	69.51	70.30	4886.38	Rupees Four Thousand Eight Hundred EightySix Paise ThirtyEight Only
24	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	743.75	81.63	60710.45	Rupees Sixty Thousand Seven Hundred Ten Paise FortyFive Only
25	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15 cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	No	32	167.94	5374.13	Rupees Five Thousand Three Hundred SeventyFour Paise Thirteen Only
26	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth and curing complete.	Sqm	4.52	511.55	2312.20	Rupees Two Thousand Three Hundred Twelve Paise Twenty Only
27	Providing and fixing Hardware items Complete . 150mm Handles	No	35	103.00	3605.00	Rupees Three Thousand Six Hundred Five Only
28	Tower Bolts 150mm	No	45	103.00	4635.00	Rupees Four Thousand Six Hundred ThirtyFive Only
29	L-Drop	No	4	515.00	2060.00	Rupees Two Thousand Sixty Only
30	Dry random rubble masonry with hard stone in foundation and plinth: With bond stone.	Cum	15.99	2572.43	41133.08	Rupees FortyOne Thousand One Hundred ThirtyThree Paise Eight Only
31	Providing and fixing soil waste pipes (10 feet long).	RM	10	360.50	3605.00	Rupees Three Thousand Six Hundred Five Only
32	Providing and fixing Vent pipes 100mm dia PVC B class	No	1	412.00	412.00	Rupees Four Hundred Twelve Only
33	PVC Collar 100 mm	No	3	154.50	463.50	Rupees Four Hundred SixtyThree Paise Fifty Only

[Handwritten signatures and initials]

st No.PH

e of
ning

!.2022

ation

led

Construction of Pump House cum Operator Quarter for WSS Khangund Gujarbasti under JJM

34	P/F of PVC Flow trap with Jalli	No	2	206.00	412.00	Rupees Four Hundred Twelve Only
35	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc.: 15 mm dia. nominal bore	Mtr	30	287.27	8618.01	Rupees Eight Thousand Six Hundred Eighteen Paise One Only
36	Providing & fixing White vitreous china water closet squatting pan(Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material i/c malba, all complete as per the direction of Engineer-in charge.Orissa pattern W.C Pan of size 580x440 mm	Each	1	3800.96	3800.96	Rupees Three Thousand Eight Hundred Paise NinetySix Only
37	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	Ltr	500	11.59	5793.75	Rupees Five Thousand Seven Hundred NinetyThree Paise SeventyFive Only
38	Providing and fixing Stain less steel heavy duty BiB cock Long Nose	No	5	1030.00	5150.00	Rupees Five Thousand One Hundred Fifty Only
39	Providing and fixing Stain less steel heavy duty Angle Valve	No	1	978.50	978.50	Rupees Nine Hundred SeventyEight Paise Fifty Only
40	Providing and fixing of PVC connections	No	4	206.00	824.00	Rupees Eight Hundred TwentyFour Only
41	Providing and fixing manhole Cover with frame.	No	2	1030.00	2060.00	Rupees Two Thousand Sixty Only
42	Providing and fixing of Stainless steel Sink of Reputed make including all fittings.	No	1	2060.00	2060.00	Rupees Two Thousand Sixty Only
43	Providing and fixing of Lighting points	No	8	978.50	7828.00	Rupees Seven Thousand Eight Hundred TwentyEight Only
44	Providing and fixing of Heating points	No	4	1184.50	4738.00	Rupees Four Thousand Seven Hundred ThirtyEight Only
45	Providing and fixing of main Electrical Pannel with necessary D.P switch Etc.	C.Job	1	3605.00	3605.00	Rupees Three Thousand Six Hundred Five Only
46	Providing and fixing of Geyser of 25 ltr.capacity of reputed make Havells, Jaguar.	C.Job	1	6180.00	6180.00	Rupees Six Thousand One Hundred Eighty Only
47	Carriage of materials by mechanical transport from source upto site of work including loading unloading and stacking complete Stone Agg.(below 40mm) Avg lead of 20 KM	Cum	48.14	360.31	17345.54	Rupees Seventeen Thousand Three Hundred FourtyFive Paise FiftyFour Only

Handwritten signature and initials, including "KEN" and "CHP".

ent No.PHE/A

ate of
ening

12.2022

Affi
Blac

ration
ded

upl

Construction of Pump House cum Operator Quarter for WSS Khangund Gujarbasti under JIM

47.01	Sand Avg. lead of 20 KM	Cum	33.89	360.31	12211.06	Rupees Twelve Thousand Two Hundred Eleven Paise Six Only
47.02	Bricks Avg. lead of 20 KM	No	11951	0.96	11447.86	Rupees Eleven Thousand Four Hundred FourtySeven Paise EightySix Only
Total					Rs 13.846 lacs	

Rates & quantity checked

Head Draftsman

Terms Conditions:-

- 1 The cost of work shall in no case exceed beyond **Rs 13.846 lacs (Rupees Thirteen Lac Eighty Four Thousand and Six Hundred only)**
- 2 Bid security declaration @ 2% vide CDR No. 147866 Dated:- 28.12.2022 for an amount of Rs 26900/- is being retained as security deposit shall be released only after successful completion of the work expiry of defective period.
- 3 Time of completion is essence of the contract.
- 4 The work shall have to be started by you at site immediately and ensure its successful completion within a period of **01 Month** from the date of issuance of LOI/Allotment from this office strictly in accordance with the approved proposals falling which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be recommended for forfeiting.
- 5 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 6 The allotted works shall be subject to check by the third party monitoring agency appointed by the department.
- 7 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis
- 8 Performance security equivalent to 3% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/bank Guarantee within one week of issuance of allotment order and valid for a period of 3 months beyond the expiry of warranty period of the contract.
- 9 The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works . If during warranty period any malfunctioning / defects arise, you shall have to rectify same within a period of 10 days of receipt of intimation . In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The quantity allotted shall have to be executed on ground strictly as per the estimates that have been framed in the DPR.
- 12 All other terms and conditions shall be applicable as laid down in standard bid document and PWD from No. 25/33.
- 13 Any rules / terms and conditions if not stipulated in the bidding documents , shall be strictly dealt in accordance with the relevant rules / guidelines stipulated in General Financial Rules (GFR-2017) and manual for procurement of works 2019 G.O.I.

Head Draftsman

Executive Engineer

(USD) PHE Division Awantipora