

OFFICE OF THE EXECUTIVE ENGINEER PHE DIVISION BARAMULLA

Email: kmrphebla@gmail.com (FAX) 01952234575 (Tel) 01952234244


Allotment Order No. 03 of 2023 dated 3-3-2023

Name of the agency/ contractor	Abdul Rashid Waja
Address	Soura Srinagar
Registration No.	SE/R&B/Gbl/Bandi/CEE/13/Civil/2020-21
Contact/ Email	abrashidwaja@gmail.com
Name of work	Laying fitting of pipes, constt of 0.05 lac glns SR with sluice chamber, replacement/P/L of filter media to SSFP and chain link fencing for WSS Kandi Nowgam under JJM
References	This office ENIT 62 of 2022 (S.No. 03)
Accord of administrative approval No. & date	169/SE/Hyd/DB/JJM of 2022-23 dated 31.01.2023
Advertised Cost	Rs. 24.60 lacs
Allotted Cost	Rs. 2274117/- (Rupees Twenty Two Lacs Seventy Four Thousand One Hundred Seventeen Only)
Time of completion	45 days

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" t this allotment, on the terms and conditions given here under :

Conditions:


01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of **45** days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.



09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
13. Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I).

(Encl: Annexure "A")

No. 11307-19
Dt. 2-3-2023


Executive Engineer
Jal Shakti Department
PHE Division Baramulla

Copy to the :-

- 1/- Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 12742-54 Dated: 07.01.2023.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- Asstt. Ex. Engineer PHE Sub Division Watergam, for information.
- 13/- File Concerned.

Comp. by: ShahidFarooq (Correspondence)

Annexure "A"

of work:

fitting of pipes, constt of 0.05 lac glns SR with sluice chmaber, replacement/P/L of filter media to SSFP and chain link fencing
VSS Kandi Nowgam under JJM

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Total Amount
1.00	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed				
1.10	All Kinds of soil.	1071.290	Cum	436.000	467082.440
2.00	Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads lifts and all carriages complete.	16.140	cum	1320.000	21304.800
3.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	1.840	cum	4861.835	8945.776
4.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	44.400	cum	5437.740	241435.656
5.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	3.6100	cum	7800.760	28160.744
6.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	5.810	cum	9408.135	54661.264
7.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	2.260	cum	9849.345	22259.520
8.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	723.0000	Kg	87.175	63027.525
9.00	Centering and shuttering including strutting, propping etc. and removal of form work for:				0.000
9.10	Foundations, footings, bases for columns	224.900	sqm	262.300	58991.270
9.20	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	71.060	sqm	573.850	40777.781
9.30	Arches, domes, vaults upto 6 m span	11.850	sqm	2086.800	24728.580
10.00	Extra for shuttering in circular work:				0.000
10.10	Foundations, footings, bases of columns etc.	4.520	sqm	52.460	237.119
10.20	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	66.520	sqm	114.770	7634.500

12.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade (two or more coats on new work).	198.100	sqm	121.950	24158.295
12.00	12mm Cement plaster finished with a floating coat of neat cement of mix: 1 : 4 (1 cement : 4 fine sand)	41.430	sqm	325.450	13483.394
13.00	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	25.200	kg	133.300	3359.160
14.00	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.4300	cum	7542.400	3243.232
15.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3597.000	kg	91.025	327416.925
16.00	Applying priming coat: With ready mixed red oxide Zinc Chromate primer of approved brand and manufacture on steel galvanized iron/steel works	198.1000	sqm	52.750	10449.775
17.00	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket.				0.000
17.10	100 mm dia D.I	80.000	Joint	89.700	7176.000
18.00	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work.				0.000
18.10	15 mm dia. nominal bore	1500.000	Mtr	20.250	30375.000
18.20	20 mm dia. nominal bore	762.000	Mtr	20.250	15430.500
18.30	25 mm dia. nominal bore	1372.0000	Mtr	30.650	42051.800
18.40	40 mm dia. nominal bore	825.000	Mtr	40.800	33660.000
19.00	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe)	74.300	Qtl	245.550	18244.365
20.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	894.3200	cum	198.700	177701.384
21.00	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				0.000
21.10	25 to 40 mm nominal bore	60.000	No	666.250	39975.000
22.00	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest amendments.				0.000
22.10	100 mm dia. Class 1	3.000	No	13164.000	39492.000
23.00	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end)				0.000
23.10	25 mm nominal bore	10.000	No	543.850	5438.500
23.20	40 mm nominal bore	5.000	No	704.700	3523.500
23.30	50 mm nominal bore	2.0000	No	942.750	1885.500


[Handwritten signature]
[Handwritten initials]

4.00	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc. if required will be paid separately).				0.000
24.10	50 mm dia.	1.000	No	5147.150	5147.150
25.00	Providing fixing of MS lid cover of 0.60x0.60m with angle iron frame including locking arrangement and all carriages complete.	1.000	No	4500.000	4500.000
26.00	P/ F 50mm GI bends with flange	10.000	No	800.000	8000.000
27.00	Providing and fixing of chain link fencing of 50mm x 50mm mesh with nuts bolts incl. straightening	266.400	Sqm	360.000	95904.000
28.00	Fixing of gate available at site including upto site work	1.000	Job	2000.000	2000.000
29.00	Removal of servicable filter and servicable for filter bends incl. washing and slary servicable	1.000	job	23000.000	23000.000
30.00	Providing / laying of filtered media incl. all carriages for Ganderbal to site of work incl. slacking as per the diretions of Engineer Incharge	40.0000	Cum	9000.000	360000.000
31.00	Providing / fixing of pipe line for delivering washout	18.0000	Mtr	1135.350	20436.300
32.00	carriage of material from source to site of work by Mechanical Transport including loading unloading and stacking etc.				0.000
32.10	Pipes (below 100mm dia) max lead 20 Km	8.020	M.ton	357.639	2868.265
32.20	Pipes 100mm dia D.I max lead 20 Km	420.0000	Mtr	8.763	3680.460
32.30	Cement /Steel max lead 22 Km	16.2000	M.ton	375.360	6080.832
32.40	Sand max lead 26 Km	26.940	cum	461.955	12445.068
32.50	Stone aggregate 20mm nominal size max lead 22 Km	50.810	cum	517.270	26282.489
32.60	Stone aggregate 40mm nominal size max lead 20 Km	1.620	cum	402.270	651.677
32.70	Soling Stone max lead 10 Km	16.130	cum	330.395	5329.271
33.00	carriage of material from dumping/ road side to site of work by Manual Means including loading unloading and stacking etc. max lead 300 Mtrs.				0.000
33.10	Cement	14.830	M.ton	265.765	3941.295
33.20	Steel	1.060	M.ton	452.640	479.798
33.30	Sand/ Aggregates	78.6000	cum	438.380	34456.668
33.40	Soling Stone	16.130	cum	515.775	8319.451
Total					2459834
Quoted Rate @ Below 7.55%					185717
Total Allotted Amount					2274117
(Rupees Twenty Two Lacs Seventy Four Thousand One Hundred Seventeen Only)					

Rates & Qty checked by:


Head Draftsman

Technical Officer


Executive Engineer
PHE Division Baramulla