

(16)

OFFICE OF THE EXECUTIVE ENGINEER (JSD) PHE DIVISION BARAMULLA

Email: kmrphebla@gmail.com (FAX) 01952234575 (Tel) 01952234244

Page no: (67)



No. 6617-28

dt. 15-9-2022

M/s. Farooq Ahmad Buhroo,
R/o. Azad Gunj Baramulla.
Regd No.

Sub: Retrofitting of W.S. Scheme Panzalla Gundbal by way of :- Laying and fitting of Main /Submain /Distribution System at various spots and Constt. of ChainLink Fencing (for providing 100% FHTC) under JJM.

Ref: 1/- Constitution of District JalJeevan Mission, Administrative Council DecisionNo: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

2/- UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

3/- Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

4/- Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

5/- District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No. SE/Hyd/DB/4538-50 dated 22.07.2022.

6/- Your tender received in response to this office ENIT No: 24 of 05/2022 S.No. 08.

7/- This office LOI No. 4514-28 dated 29.07.2022

1/- Amount of work advertised: 1525000.00

2/- Allotted cost of work: 1509480.00

(Rupees Fifteen Lacs Nine Thousand Four Hundred Eighty only)

3/- Time of completion: (45 days)

oh

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" t this allotment, on the terms and conditions given here under :

Conditions:

01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of 45 days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning /

Q

7

- (10)
- defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing
08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
 09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
 10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
 11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
 12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
 13. Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

(Encl: Annexure "A")


Technical Officer to
Executive Engineer
PHE Division Baramulla


Executive Engineer
Jal Shakti Department
PHE Division Baramulla

Copy to the :-

- 1/- Mission Director, Mission Directorate JaJeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 2105-14 Dated: 04-06-2022.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- File Concerned.

Comp. by: ShahidFarooq (Correspondence)

-1% (16)

eProcurement System Government of Jammu And Kashmir

Annexure "A"

Scheme Panzalla Gundbal by way of :- Laying and fitting of Main /Submain /Distribution System at various spots in Link Fencing (for providing 100% FHTC) under JJM.

Description of Work / Item(s)	No.of Qty	Units	Rate	Total Amount
Work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
All kinds of soil.	981.720	Cum	431.640	423749.621
Ordinary Rock	22.680	Cum	958.172	21731.330
Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads lifts and all carriages complete.	8.100	cum	1306.800	10585.080
Providing & Laying in position cement concrete of 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) excluding the cost of centring and shuttering all work upto plinth level incl. dewatering.	4.500	cum	4813.217	21659.475
4 Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	42.860	Cum	5383.363	230730.921
5 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1569.000	kg	90.115	141390.043
6 Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-incharge. Made of G.I. wire of dia 4 mm	109.200	sqm	726.165	79297.218
7 12mm Cement plaster of mix: 1 : 4 (1 cement : 4 coarse sand)	73.200	sqm	257.450	18845.303
8 Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	174.700	sqm	259.677	45365.572
9 Centering and shuttering including strutting, propping etc. and removal of form for:- Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	18.700	sqm	568.112	10623.685
10 Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work.	0.0000		0.000	0.000
10.1 15 mm dia. nominal bore	2012.000	Mtr	20.048	40335.570
10.2 20 mm dia. nominal bore	1800.000	Mtr	20.048	36085.500
10.3 25 mm dia. nominal bore	1800.000	Mtr	30.344	54618.300
10.4 40 mm dia. nominal bore	1600.000	Mtr	40.392	64627.200
10.5 50 mm dia. nominal bore	2000.000	Mtr	40.392	80784.000
11 Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	874.800	cum	196.713	172084.532

[Handwritten signature]

[Handwritten signature]

ing connection of G.I. distribution branch with G.I. main following sizes by providing and fixing Tee, including ing and threading the pipe etc. complete	0.0000		0.000	0.000
to 40 mm nominal bore	2.000	No	659.588	1319.175
to 80 mm nominal bore	3.000	No	1256.063	3768.188
roviding and fixing of MS surface boxes (0.75x0.75x0.75) of 6mm nick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	1.000	Job	6930.000	6930.000
Carraige of material from source to actual site of work by Mechanical Transport incl. loading unloading and stacking etc.	0.0000		0.000	0.000
Pipes (below 100mm dia) for 20 Km	16.680	M.Ton	354.063	5905.764
Cement/ Steel avg lead 12 Kms	10.310	M.Ton	268.538	2768.632
Sand/ Stone Aggregate avg lead 30 Kms	65.400	Cum	496.636	32480.025
Stone Soling for 20Km	8.100	Cum	468.516	3794.976
Total				1509480.11
Rupees Fifteen Lacs Nine Thousand Four Hundred Eighty Only				


Qty checked by:

Head Draftsman

 2



 Technical Officer 2


 Executive Engineer
 PHE Division Baramulla