

OFFICE OF THE EXECUTIVE ENGINEER (JSD) PHE DIVISION BARAMULLA

Email: kmrphebla@gmail.com (FAX) 01952234575 (Tel) 01952234244



No. 9589-9601

dt. 28-12-2022

M/s. Abdul Ahad Bhat  
S/o. Gh Ahmad Bhat  
R/o. Monagam Kreeri  
Regd No. 605/BK-SE/PWD/DEE/2012-13

**Sub:** Retrofitting of W.S.Scheme Bandi Bala by way of :- Laying and fitting of Main /Submain /Distribution System at various spots and Constt. of intake chamber (for providing 100% FHTC) under JJM.

**Ref:** 1/- Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

2/- UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

3/- Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

4/- Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

5/- District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No. SE/Hyd/DB/11748-60 dated 16.12.2022.

6/- Your tender received in response to this office ENIT No: 53 of 2022 (S.No 03).

1/- Amount of work advertised: 855000.00

2/- Allotted cost of work: 838296.00

(Rupees Eight Lacs Thirty Eight Thousand Two Hundred Ninety Six Only)

3/- Time of completion: ( 30 days)

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" t this allotment, on the terms and conditions given here under :


**Conditions:**

01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of **30** days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning /




defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
13. Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

  
Technical Officer to  
Executive Engineer  
PHE Division Baramulla

**(Encl: Annexure "A")**

  
Executive Engineer  
Jal Shakti Department  
PHE Division Baramulla

**Copy to the :-**

- 1/- Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 2105-14 Dated: 04-06-2022.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- Asstt. Ex. Engineer PHE Sub Division Kreeri, for information.
- 13/- File Concerned.


Comp. by: ShahidFaroq (Correspondence)



of work:  
fitting of W.S. Scheme Bandl Bala by way of :- Laying and fitting of Main /Submain /Distribution System at various spots and  
constt. of intake chamber (for providing 100% FHTC) under JJM

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Total Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1.1	All kinds of soil	337.020	Cum	436.000	146940.720
1.2	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres: All kinds of soil :	75.000	Cum	252.050	18903.750
2	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work.				0.000
2.1	15 mm dia. nominal bore	600.000	Mtr	20.250	12150.000
2.2	20 mm dia. nominal bore	750.0000	Mtr	20.250	15187.500
3	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe)	420.000	Qtl	245.550	103131.000
4	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket.				0.000
4.1	100 mm dia pipes	281.0000	No	89.700	25205.700
4.2	150 mm dia pipes	91.000	No	144.700	13167.700
5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	365.170	cum	198.700	72559.279
6	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				0.000
6.1	25 to 40 mm nominal bore	14.000	No	666.250	9327.500
6.2	50 to 80 mm nominal bore	5.0000	No	1268.750	6343.750
7	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest amendments.				0.000
7.1	100mm dia	2.000	No	13164.000	26328.000
7.2	150mm dia	1.000	No	20243.000	20243.000
8	Providing and fixing gun metal gate valve with C.I. wheel of approved quality incl. all accessories and all carriage complete.				0.000
8.1	25 mm nominal bore	2.000	No	543.850	1087.700
8.2	40 mm nominal bore	1.0000	No	704.700	704.700

  
To

  
Xen



9	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions and other accessories complete.				0.000
9.1	50 mm dia.	1.0000	No	5147.150	5147.150
10	Providing and fixing of MS surface boxes (0.75x0.75x0.75) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	1.000	Job	7000.000	7000.000
11	Manufacturing providing fixing of MS Bends/ Tees including carriage of welding machine upto site of work incl. cost of nuts, bolts, rubber washers etc., complete job.	30.000	Kg	210.000	6300.000
12	Providing and laying D.I. standard specials such as tees, bends, collars, tapers, caps etc. suitable for flanged jointing as per IS : 9523 (as per site requirement) upto 300mm dia	1.0000	Qtl	7823.700	7823.700
13	Providing fixing of 10 to 12mm thick flanges to G.I pipes incl. cost of rubber washers, nuts, bolts and including carriage of welding machine & gen set involving welding at site as per the ground profile complete job.				0.000
13.1	80mm dia G.I	5.000	Pair	1000.000	5000.000
13.2	100mm dia G.I	2.0000	Pair	1200.000	2400.000
13.3	100mm dia D.I	3.000	Pair	1300.000	3900.000
14	Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads lifts and all carriages complete.	1.170	cum	1320.000	1544.400
15	Providing & Laying in position cement concrete of 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) excluding the cost of centring and shuttering all work upto plinth level incl. dewatering.	0.8000	cum	4861.835	3889.468
16	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.560	cum	7800.100	12168.156
17	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	5.940	Cum	9408.335	55884.322
18	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.5700	Cum	9849.345	5614.127
19	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	566.490	Kg	87.175	49383.766

90


Handwritten signature/initials




20	Centering and shuttering including strutting, propping etc. and removal of form for:- Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	77.440	sqm	573.850	44438.944
21	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platforms.	4.000	sqm	635.600	2542.400
22	Centering and shuttering including strutting, propping etc. and removal of form for: 5.9.1 Foundations, footings, bases of columns etc. for mass concrete.	3.360	sqm	262.300	881.328
23	Manufacturing /Fabrication and installation of MS drum made out of 6mm thick MS sheet incl. fixing of flanged nipples as per site requirement incl. fixing of supply main and including installation of MS stand with all carriages upto site of work complete.	1.0000	C.Job	20000.000	20000.000
24	Providing and fixing of MS lid cover of size 0.60x0.60m with angle iron frame 45x45x5mm and 25x25x5mm and 4mm thick lid cover with priming coat and all carriages upto site of work.	1.000	C.Job	4500.000	4500.000
25	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5 Km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc., complete.	225.000	cum	272.450	61301.250
26	carriage of material from source to dumping site of work by Mechanical Transport including loading unloading and stacking etc.				0.000
26.1	100mm dia D.I pipes for 30 KMs	1550.000	Mtr	10.833	16791.150
26.2	150mm dia D.I pipes for 30 Kms	500.000	Mtr	30.510	15255.000
26.3	Pipes below 100mm dia for 30 KMs	1.450	M.ton	446.085	646.823
26.4	Cement /steel avg. lead 40 KMs	3.790	M.ton	534.279	2024.917
26.5	Sand / Stone aggregate for 40 Kms	11.9500	Cum	601.613	7182.105
27	carriage of material from road / dumping site to the actual site of work by Manual means including loading unloading and stacking for avg. lead 800 Mtrs.				0.000
27.1	100mm dia D.I pipes	1550.000	Mtr	13.110	20320.500
27.2	150mm dia D.I pipes	500.000	Mtr	18.596	9298.000
27.3	Pipes below 100mm dia	1.4500	M.ton	490.659	711.456
27.4	Cement /steel	3.790	M.ton	389.114	1474.742
27.5	Sand / Stone aggregate	11.950	Cum	895.413	10700.185
<b>Total</b>					<b>855404</b>
Quoted Rate @ below 2%					<b>17108</b>
<b>Total Allotted Amount</b>					<b>838296</b>
(Rupees Eight Lacs Thirty Eight Thousand Two Hundred Ninety Six Only)					

Rates & Qty checked by:

  
Head Draftsman

  
Technical Officer

  
Executive Engineer  
PHE Division Baramulla