

13
OFFICE OF THE EXECUTIVE ENGINEER (JSD) PHE DIVISION BARAMULLA

Email: kmrphebla@gmail.com (FAX) 01952234575 (Tel) 01952234244



No. 7606-18

dt. 25-10-22

M/s. Nissar Ahmad Bhat
S/o. Ab Rehman Bhat
R/o. Qazipora Patti Ferozpora
Regd No. 711/BK-SE/PWD/CEE/2005-06

Sub: Retrofitting of W.S.Scheme Drangpati Check Dudbugh by way of :- Laying and fitting of Main /Submain /Distribution System at various spots (for providing 100% FHTC) under JJM..

Ref: 1/- Constitution of District Jal Jeevan Mission, Administrative Council DecisionNo: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

2/- UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

3/- Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

4/- Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

5/- District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No. SE/Hyd/DB/7859-71 dated 19.09.2022.

6/- Your tender received in response to this office ENIT No: 42 of 08/2022 (S.No 04).

1/- Amount of work advertised: 1220000.00

2/- Allotted cost of work: 1196001.00
(Rupees Eleven Lacs Ninety Six Thousand & One Only)

3/- Time of completion: (30 days)

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" to this allotment, on the terms and conditions given here under :

Conditions:

01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of 30 days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring & by appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of

Annexure "A"


Name of work:


Retrofitting of W.S.Scheme Drangpati Check Durbugh by way of :- Laying and fitting of Main /Submain /Distribution System at various spots (for providing 100% FHTC) under JJM.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Allotted Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1.1	All Kinds of Soil	788.400	Cum	427.280	336867.552
1.2	Ordinary Rock	197.100	Cum	948.493	186947.9703
2	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work.			0.000	0
2.1	15 mm dia. nominal bore	2200.000	Mtr	21.15	43659
2.2	20 mm dia. nominal bore	2000.000	Mtr	19.845	39690
2.3	25 mm dia. nominal bore	2000.000	Mtr	30.037	60074
2.4	40 mm dia. nominal bore	1800.000	Mtr	39.984	71971.2
2.5	50 mm dia. nominal bore	2200.000	Mtr	39.984	87964.8
2.6	80 mm dia. nominal bore	500.0000	Mtr	71.589	35794.5
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto.50 m and lift upto 1.5 m.	886.950	cum	194.726	172712.2257
4	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete			0.000	0
4.1	25 to 40 mm nominal bore	21.000	No	653.825	13711.425
4.2	50 to 80 mm nominal bore	12.000	No	1243.875	14920.5
5	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest amendments.			0.000	0
5.1	100 mm dia.	2.0000	No	12900.720	25801.44
6	Providing and fixing gun metal gate valve with C.I. wheel of approved quality incl. all accessories and all carriage complete.			0.000	0
6.1	25 mm nominal bore	3.000	No	532.973	1598.919
6.2	40 mm nominal bore	4.000	No	690.606	2762.424
6.3	50 mm nominal bore	3.000	No	923.895	2771.685
6.4	65 mm nominal bore	2.000	No	1537.473	3074.946
7	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions and other accessories complete.			0.000	0
7.1	50 mm dia.	2.000	No	5044.207	10088.414
7.2	80 mm dia.	2.0000	No	6106.233	12212.466

- recommended for further punitive action as governed under the relevant clause of the contract including black listing.
08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
 09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
 10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
 11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
 12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No., 25/33.
 13. Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

(Encl: Annexure "A")


Technical Officer to
Executive Engineer
PHE Division Baramulla


Executive Engineer
Jal Shakti Department
PHE Division Baramulla

Copy to the :-

- 1/- Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 2105-14 Dated: 04-06-2022.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- Asstt. Ex. Engineer PHE Sub Division Kreeri, for information.
- 13/- File Concerned.

Comp. by: ShahidFarooq (Correspondence)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Allotted Rate	Amount
8	Providing and fixing of MS surface boxes (0.75x0.75x0.75) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	2.000	Job	6860.000	13720
9	Manufacturing providing fixing of MS Bends/ Tees including carriage of welding machine upto site of work incl. cost of nuts, bolts, rubber washers etc., complete job.	60,000	Kg	205.800	12348
10	Providing fixing of 10 to 12mm thick flanges to G.I pipes incl. cost of rubber washers, nuts, bolts and including carriage of welding machine & gen set involving welding at site as per the ground profile complete job.			0.000	0
10.1	80mm dia G.I	16.000	Pair	980.000	15680
10.2	100mm dia G.I	18.0000	Pair	1176.000	21168
11	Carriage of pipes (below 100mm dia) from divisional store upto site of work by mechanical transport incl. loading unloading and stacking etc., for 25 Kms	26.570	M.ton	393.763	10462.28344
Total					1196001.75
(Rupees Eleven Lacs Ninety Six Thousand & One Only)					

Rates & Qty checked by:

Head Draftsman

Technical Officer

Executive Engineer
PHE Division Baramulla

