

# OFFICE OF THE EXECUTIVE ENGINEER (JSD) PHE DIVISION

## BARAMULLA

Email: kmrpheb1a@gmail.com (FAX) 01952234575 (Tel) 01952234244

Page No. (106)



No. 6216-20

dt. 12-9-2022

M/s. Manzoor Ahmad Mir  
R/o. Kreeri Baramulla  
Regd No.

**Sub:** Retrofitting of W.S.Scheme Maqdampora by way of :- Laying and fitting of Main /Submain /Distribution System at various spots (for providing 100% FHTC) under JJM.

**Ref:** 1/- Constitution of District JalJeevan Mission, Administrative Council DecisionNo: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

2/- UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

3/- Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

4/- Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

5/- District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No. SE/Hyd/DB/7137-49 dated 07.09.2022.

6/- Your tender received in response to this office ENIT No: 38 of 2022 (S.No 24).

1/- Amount of work advertised: 998000.00

2/- Allotted cost of work: 987593.00

(Rupees Nine Lacs Eighty Seven Thousand Five Hundred Ninety Three Only)

3/- Time of completion: (30 days) (fifty)

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" t this allotment, on the terms and conditions given here under :

### Conditions:

01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of 30 days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful completion of the works. If during warranty period any malfunctioning /

*[Handwritten signature]*


*[Handwritten signature]*



defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any delay on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
13. Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

**(Encl: Annexure "A")**

  
Technical Officer to  
Executive Engineer  
PHE Division Baramulla

  
Executive Engineer  
Jal Shakti Department  
PHE Division Baramulla

**Copy to the :-**

- 1/- Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 2105-14 Dated: 04-06-2022.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- File Concerned.

Comp. by: ShahidFarooq (Correspondence)

name of work:

retrofitting of W.S.Scheme Maqdampora by way of :- Laying and fitting of Main /Submain /Distribution System at various spots (for providing 100% FHTC) under JJM.

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Allotted Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1.1	All Kinds of Soil	1022.220	Cum	431.640	441231.0408
2	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work.			0.000	0
2.1	15 mm dia. nominal bore	1458.000	Mtr	20.048	29229.255
2.2	20 mm dia. nominal bore	1900.000	Mtr	20.048	38090.25
2.3	25 mm dia. nominal bore	1300.000	Mtr	30.344	39446.55
2.4	40 mm dia. nominal bore	1500.000	Mtr	40.392	60588
2.5	50 mm dia. nominal bore	1200.000	Mtr	40.392	48470.4
2.6	80 mm dia. nominal bore	700.000	Mtr	72.320	50623.65
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	920.0000	cum	196.713	180975.96
4	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete			0.000	0
4.1	25 to 40 mm nominal bore	15.000	No	659.588	9893.8125
4.2	50 to 80 mm nominal bore	10.000	No	1256.063	12560.625
5	Providing and fixing gun metal gate valve with C.I. wheel of approved quality incl. all accessories and all carriages complete.			0.000	0
5.1	25 mm nominal bore	4.000	No	538.412	2153.646
5.2	40 mm nominal bore	3.0000	No	697.653	2092.959
5.3	50 mm nominal bore	3.000	No	933.323	2799.9675
6	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions and other accessories complete.			0.000	0
6.1	80 mm dia.	3.000	No	6168.542	18505.6245
7	Providing and fixing of MS surface boxes (0.75x0.75x0.75) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	2.000	Job	6930.000	13860
8	Providing fixing of 10 to 12mm thick flanges to G.I pipes Incl. cost of rubber washers, nuts, bolts and including carriage of welding machine & gen set involving welding at site as per the ground profile complete job.			0.000	0
8.1	80mm dia G.I	30.000	Palr	990.000	29700

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Allotted Rate	Amount
9	Carraige of pipes (below 100mm dia) from divisional store upto site of work incl. loading unloading and stacking etc., for 20 Kms	20.8200	M.ton	354.063	7371.58354
<b>Total</b>					<b>987593.32</b>
(Rupees Nine Lacs Eighty Seven Thousand Five Hundred Ninety Three Only)					

Rates & Qty checked by:

*[Signature]*  
Head Draftsman

*[Signature]*  
Technical Officer

*[Signature]*  
Executive Engineer  
PHE Division Baramulla