

Office of the Executive Engineer (JSD)P.H.E Division Awantipora

E-Mail ID: phedivisionawantipora@gmail.com

Nisar Ahmad Bhat
S/O: Ab Ahad Bhat
R/O: Hurdmir Tral
Reg. No. : 28/CEE/SE/hyd/Shopian/2003-04
PAN No. AKYPB1710A
GST No. 01AKYPB1710A2ZZ

No.PHE/AWP/ 2844-49
Dated:- 01/08/2022

Subject:- Allotment for Retrofitting of WSS Zantrag by way of laying and fitting under JJM

Reference:- 1. Your tender in response to this office E-NIT No. 03/PHA of 2022-23 (e-tendering) S.No.(7) issued under endorsement No. PHA/Awp/192-203 Dated:-16-04-2022 Tender Id No. 2022_PHE_166872_7

2. Minuts of meeting DJJM Pulwama held on 14-06-2022

3. Technical sanction No. 39/JJM/2022-23 of 08/2022

4. CE Kms PHE Dept. Sgs No: 13745-83 Dated: 26/07/2022

For on behalf of lieutenant Governor of Union Territory of Jammu & Kashmir, contract for above mentioned work is hereby fixed with you at the following quoted rates, terms conditions.


Advertised Cost:-Rs 12.34 lacs

Allotted Cost:- Rs 12.83 lacs

(Rupees twelve lacs and eighty three thousand) only

S.No.	Particulars of items	Unit	Qty	Alloted Rate	Amount	
					in figures	in Words
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All kinds of soil (1 meter from cutting edge).	cum	424.84	453.44	192639.4496	Rupees One Lakh NinetyTwo Thousand Six Hundred ThirtyNine Paise FourtyFive Only
2	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work. 80 mm dia GI Pipes	mtr	20	75.97	1519.44	Rupees One Thousand Five Hundred Nineteen Paise FourtyFour Only
3	50 mm dia GI Pipes	mtr	500	42.43	21216	Rupees TwentyOne Thousand Two Hundred Sixteen Only
4	40 mm dia GI Pipes	mtr	500	42.43	21216	Rupees TwentyOne Thousand Two Hundred Sixteen Only
5	20 mm dia GI Pipes	mtr	900	21.06	18954	Rupees Eighteen Thousand Nine Hundred FiftyFour Only

Allotment Rates Accepted



Subject:- Allotment for Retrofitting of WSS Zantrag by way of laying and fitting under JJM

6	15 mm dia GI Pipes	mtr	730	21.06	15373.8	Rupees Fifteen Thousand Three Hundred SeventyThree Paise Eighty Only
7	Providing & fixing of MS Flanges to GI pipe including cutting of threaded portion, welding, cost of nuts, bolts and washers with testing after completion of work including all carriages complete for; 40 mm dia	joint	20	520.00	10400	Rupees Ten Thousand Four Hundred Only
8	50mm	Joint	20	780.00	15600	Rupees Fifteen Thousand Six Hundred Only
9	80mm	joint	6	1144.00	6864	Rupees Six Thousand Eight Hundred SixtyFour Only
10	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete 25 to 40 mm nominal bore	each	25	692.90	17322.5	Rupees Seventeen Thousand Three Hundred TwentyTwo Paise Fifty Only
11	50 to 80 mm nominal bore	each	12	1319.50	15834	Rupees Fifteen Thousand Eight Hundred ThirtyFour Only
12	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	cum	378.567	206.65	78230.11342	Rupees SeventyEight Thousand Two Hundred Thirty Paise Eleven Only
13	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil.	cum	4.21	453.44	1908.9824	Rupees One Thousand Nine Hundred Eight Paise NinetyEight Only
14	Providing and laying of stone soling (dully hand packed) on horizontal level.	cum	1.05	641.06	673.1088	Rupees Six Hundred SeventyThree Paise Eleven Only
15	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	0.7	5056.31	3539.41952	Rupees Three Thousand Five Hundred ThirtyNine Paise FourtyTwo Only
16	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	26.36	6691.37	176384.5237	Rupees One Lakh SeventySix Thousand Three Hundred EightyFour Paise FiftyTwo Only

[Handwritten signature and date]

Subject:- Allotment for Retrofitting of WSS Zantrag by way of laying and fitting under
JJM

17	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate -10mm nominal size).	cum	0.96	7257.83	6967.514112	Rupees Six Thousand Nine Hundred SixtySeven Paise FiftyOne Only
18	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	sqm	4.88	126.83	618.92064	Rupees Six Hundred Eighteen Paise NinetyTwo Only
19	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level: Thermo Mechanically Treated bars of grade Fe-500D or more.	kg	91	90.67	8250.7152	Rupees Eight Thousand Two Hundred Fifty Paise SeventyTwo Only
20	Providing and laying 50 mm thick cement concrete flooring with floating coat of neat cement	sqm	2.25	577.72	1299.87	Rupees One Thousand Two Hundred NinetyNine Paise EightySeven Only
21	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	sqm	1.73	522.96	904.72772	Rupees Nine Hundred Four Paise SeventyThree Only
22	Suspended floors, roofs, landings, balconies, and access platform.	sqm	3.78	661.02	2498.67072	Rupees Two Thousand Four Hundred NinetyEight Paise SixtySeven Only
23	Edges of slabs and breaks in floors and walls. Under 20cms wide	Mtr	7.8	251.99	1965.5376	Rupees One Thousand Nine Hundred SixtyFive Paise FiftyFour Only
24	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs or with dash fasteners shall be paid for separately): 9.1.1 First classkail wood	cum	0.08	111169.76	8893.5808	Rupees Eight Thousand Eight Hundred NinetyThree Paise FiftyEight Only
25	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4mm thick float glass panes including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. First class kail wood 35mm	sqm	0.54	3217.55	1737.47808	Rupees One Thousand Seven Hundred ThirtySeven Paise FourtyEight Only
26	Brick work with common burnt clay (non-modular) bricks of class designation 7.5 in foundation and plinth including curing in: Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	3.43	6431.15	22058.85136	Rupees TwentyTwo Thousand FiftyEight Paise EightyFive Only
27	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note: -Butt hinges and necessary screws shall be paid separately). First class kail wood 35mm	sqm	1.61	3217.55	5180.25872	Rupees Five Thousand One Hundred Eighty Paise TwentySix Only

Handwritten signature and initials

**Subject:- Allotment for Retrofitting of WSS Zantrag by way of laying and fitting under
JJM**

28	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick. First class kail wood	sqm	0.54	2601.87	1665.19808	Rupees One Thousand Six Hundred SixtyFive Paise Twenty Only
29	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	kg	2895.83	106.22	307581.1626	Rupees Three Lakh Seven Thousand Five Hundred EightyOne Paise Sixteen Only
30	Providing and fixing plained eaves boarding. 12.69.1 2nd class Deodar wood 250x32 mm (nominal size)	sqm	30	721.66	21649.68	Rupees TwentyOne Thousand Six Hundred FourtyNine Paise SixtyEight Only
31	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	sqm	41.4	95.47	3952.5408	Rupees Three Thousand Nine Hundred FiftyTwo Paise FiftyFour Only
32	12mm Cement plaster finished with a floating coat of neat cement of mix: 1 : 4 (1 cement : 4 fine sand)	sqm	14.42	297.50	4289.984608	Rupees Four Thousand Two Hundred EightyNine Paise NinetyEight Only
33	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	7.88	1160.43	9144.20416	Rupees Nine Thousand One Hundred FourtyFour Paise Twenty Only
34	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or Strap, 10 litre low level P.V. C. flushing cistern including flush pipe (of approved make) manually controlled device (handle lever) conforming to IS:7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required. White vitreous china W.C. pan of size 580x440 mm with integral type foot rests.	each	1	5756.24	5756.244	Rupees Five Thousand Seven Hundred FiftySix Paise TwentyFour Only

Handwritten signature and initials

Subject:- Allotment for Retrofitting of WSS Zantrag by way of laying and fitting under

JJM

35	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1: 4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete. In all colours, shades, except White, Ivory, Fume Red Brown	sqm	1.99	1207.54	2403.01256	Rupees Two Thousand Four Hundred Three Paise One Only
36	Distemping with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ liter, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	sqm	14.42	81.80	1179.49832	Rupees One Thousand One Hundred SeventyNine Paise Fifty Only
37	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gram/m ²	mtr	30	719.00	21570.12	Rupees TwentyOne Thousand Five Hundred Seventy Paise Twelve Only
38	Providing corrugated G. S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface)excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gram/m ²	sqm	174.92	989.88	173150.2294	Rupees One Lakh SeventyThree Thousand One Hundred Fifty Paise TwentyThree Only
39	Providing plain coloured CGS Sheets for soffits or reputed make of 0.50 mm thick with all accessories complete	sqm	20	884.00	17680	Rupees Seventeen Thousand Six Hundred Eighty Only
40	PVC pipe 100mm	m	6	312.00	1872	Rupees One Thousand Eight Hundred SeventyTwo Only
41	PVC pipe 75mm	m	6	260.00	1560	Rupees One Thousand Five Hundred Sixty Only
42	Angle Valve	No	2	520.00	1040	Rupees One Thousand Fourty Only
43	Bib Cock CP	No	2	1040.00	2080	Rupees Two Thousand Eighty Only

Handwritten signature and initials in blue ink.

Subject:- Allotment for Retrofitting of WSS Zantrag by way of laying and fitting under JJM

44	Basin Mixer CP	No	1	2600.00	2600	Rupees Two Thousand Six Hundred Only
45	PVC Flow trap	No	1	312.00	312	Rupees Three Hundred Twelve Only
46	Door bend/Tee 100mm/75mm	No	1	260.00	260	Rupees Two Hundred Sixty Only
47	PVC bends 100/75mm	No	1	208.00	208	Rupees Two Hundred Eight Only
48	15mm dia internal pipe	M	5	290.06	1450.28	Rupees One Thousand Four Hundred Fifty Paise TwentyEight Only
49	P/F of plumbing & electrician items of reputed make with ISI mark complete job (To be paid as per actual)	Job	1	10400.00	10400	Rupees Ten Thousand Four Hundred Only
50	Lighting points 1.5mm sq wire	No	1	1040.00	1040	Rupees One Thousand Forty Only
51	P/F of exhaust fan 300mm	No	1	2080.00	2080	Rupees Two Thousand Eighty Only
52	P/F of 15 liter Gysar inclding all fitting/fixures complete	No	1	6240.00	6240	Rupees Six Thousand Two Hundred Forty Only
53	Providing and laying in position 1000mm dia of 300mm in depth precast cement concrete rings for sludge/waste water includinf, earthwork, disposal, carriage, loading, unloading etc	No.	21	520.00	10920	Rupees Ten Thousand Nine Hundred Twenty Only
54	Carriage by Mechanical Transport Steel	Ton	2.14	417.87	894.24608	Rupees Eight Hundred NinetyFour Paise TwentyFive Only
55	Sand	cum	3.68	470.05	1729.779584	Rupees One Thousand Seven Hundred TwentyNine Paise SeventyEight Only
56	Aggregates 20mm	cum	4.42	470.05	2077.615696	Rupees Two Thousand SeventySeven Paise SixtyTwo Only
57	Aggregates 40mm	cum	0.63	510.94	321.895208	Rupees Three Hundred TwentyOne Paise EightyNine Only
58	Bricks	No	1627	1.26	2047.4168	Rupees Two Thousand FourtySeven Paise FourtyTwo Only
59	Stone rolling	cum	1	552.99	552.9888	Rupees Five Hundred FiftyTwo Paise NinetyNine Only
60	Pipes @ 25 Km lead	MT	6.65	417.86	2778.77964	Rupees Two Thousand Seven Hundred SeventyEight Paise SeventyEight Only
61	Carriage by Manual Transport pipes @ 500 m	MT	6.65	369.92	2459.95204	Rupees Two Thousand Four Hundred FiftyNine Paise NinetyFive Only
Total:-					Rs 12.83 lacs	

Rates and quantity checked


Head Draftsman

Xen
C/S

Terms Conditions:-

- 1 The cost of work in no case exceed beyond Rs 12.83 lacs (Rupees twelve lacs and eighty three thousand) only
- 2 Bid declaration security @ 2% vide CDR No.3249230 Dated:-25/4/2022 for an amount of Rs 10000/-, CDR No. 3249231 dated:- 25-4-2022 for an amount of Rs 10000/- and CDR No. 3249238 dated:- 9-5-2022 for an amount of Rs 5000/-are being retained as security deposit shall be released only after successful completion of the work expiry of defective period.
- 3 Time of completion is essence of the contract.
- 4 The work shall have to be started by you at site immediately and ensure its successful completion within a period of **03 months** from the date of issuance of allotment from this office strictly in accordance with the approved proposals falling which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited. However date of start for laying and fitting of pipes will start within 07 days from the date of issuance of pipe material by the deptt.
- 5 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 6 The allotted works shall be subject to check by the third party monitoring agency appointed by the department.
- 7 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis
- 8 Performance security equivalent to 3% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/bank Guarantee within one week of issuance of allotment order and valid for a period of 3 months beyond the expiry of warranty period of the contract.
- 9 The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works . If during warranty period any malfunctioning / defects arise, you shall have to rectify same within a period of 10 days of receipt of intimation . In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The quantity allotted shall have to be executed on ground strictly as per the estimates that have been framed in the DPR for the item of "laying and fitting".
- 12 All other terms and conditions shall be applicable as laid down in standard bid document and PWD from No. 25/33.
- 13 Any rules / terms and conditions if not stipulated in the bidding documents , shall be strictly dealt in accordance with the relevant rules / guidelines stipulated in General Financial Rules (GFR-2017) and manual for procurement of works 2019 G.O.I.

Head Draftsman



Tech. Officer

Executive Engineer

JSD (PHE) Division Awantipora

