

Office of the Executive Engineer Spl Sub Div Tangdar

Email Address: xenssdt@gmail.com

Mr. Zahid Ahmad Magray
 S/o. Gh Ahmad Magray
 R/o Hayatpora Berwah
 Reg No: 90/AAY/CE/CID/PDC/2010-11
 GSTIN: 01BINPM2673RIZO
 Mob No: 8825078828

No: 918-27
 Dated: 15-6-2023

- Subject:** Laying fitting of Pipe network WSS Seemari Chamkote incld. Anchor and saddle blocks at spots
- Ref:**
1. Revised DAP approved and issued under No: DDCK/Plg/JJM/4465-85 dtd: 14.07.2022
 2. DPR appraisal committee meeting held on 8th Feb 2022 issued under CE/PHE/DB/44620-41 Dtd: 12.03.2022
 3. Accord of Administrative approval accorded by Chief Engineer PHE DEppt. Kmr Order No. CE/PHE/DB/249 of 8/2022 dtd: 31.08.2022.
 4. Technical Sanction issued by Chief Engineer PHE Deptt Kmr Order No CE/PHE/DB/255 of 8/2022 dtd: 31.08.2022.
 5. This office 1st Fresh E-NIT No. 11 of 2022-23, Dated: 17.05.2023, issued under endstt. No: 420-28 Dated: 17.05.2023.
 6. Your tender received in response to this office E-NIT No. 11 of 2022-23
 7. District Development Commissioner Kupwara's Authorization No: DDCK/PLG/JJM/1572-95 Dated: 12.06.2023.

Adv. Cost 116.11Lacs
 Alloted Cost: 118.42 lacs

For and on behalf of Lt. Governor of Union Territory of Jammu & Kashmir, the above noted work is hereby allotted to you on following negotiated rates which are 2% above on advertise rates

S.No	Particulars of Items	Unit	Qty	Estimate d Rate	Alloted Rate 2%	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed in:-All kinds of Soil	Cum	6273.50	436.00	444.72 ✓	2789951 ✓
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed in:-Ordinary Rock	Cum	1144.50	841.60	858.43 ✓	982475
3	Providing and laying dry stone soling hand packed tightly including cost of 50-200mm nallah boulders	Cum	18.00	678.04	691.60 ✓	12449
4	Providing and laying in position cement concrete of specified grade including curing butxcluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 mix (1 Cement: 4 Course Sand : 8 graded crushed stone agg 40mm nominal size)	Cum	12.00	4861.84	4959.08 ✓	59509

5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 mix (1 Cement: 3 Course Sand : 6 graded crushed stone agg 20mm nominal size)	Cum	216.00	5399.02	5507.00 ✓	1189512
6	Walls	Sqm	261.00	660.00	673.70 ✓	175705
7	Laying and fitting of G.I. pipes (all classes) pipes, fittings and Earth work complete excluding cost of pipes and earth work. 100mm Dia	Mtr	12.00	124.00	126.48 ✓	1518
8	80 mm Dia G.I. Pipes	Mtr	3600.00	84.00	85.68 ✓	308448
9	65mm Dia G.I. Pipes	Mtr	700.00	84.00	85.68 ✓	59976
10	50mm Dia G.I. Pipes	Mtr	16700.00	47.00	47.94 ✓	800598
11	40mm Dia G.I. Pipes	Mtr	15600.00	47.00	47.94 ✓	747864
12	25mm Dia G.I. Pipe	Mtr	11700.00	35.00	35.70 ✓	417690
13	20mm Dia G.I. Pipe	Mtr	12500.00	23.00	23.46 ✓	293250
14	15mm Dia G.I. Pipes	Mtr	3400.00	23.00	23.46 ✓	79764
15	Laying in position 125mm dia D.I. Pipes in trenches excluding cost of pipes and earth work.	Qtl	720.00	282.00	287.64 ✓	207101
16	Providing push on Joints to 125mm dia D.I. Pipes including cost of rubber insertion complete.	jnts	727.00	100.00	102.00 ✓	74154
17	Providing and fixing GI Union in GI Pipe Including cutting and threading the pipe and making long screws complete. (New Work) a) 20mm nominal bore	no	150.00	363.06	370.32 ✓	55548
18	25 mm nominal bore G.I Unions	No	150.00	409.23	417.41 ✓	62612
19	40 mm nominal bore G.I Unions	No	150.00	566.15	577.47 ✓	86621
20	50 mm nominal bore G.I Unions	No	200.00	745.32	760.23 ✓	152045
21	65 mm nominal bore G.I Unions	No	50.00	1019.19	1039.57 ✓	51979
22	80 mm nominal bore G.I Unions	No	100.00	1133.04	1155.70 ✓	115570
23	Providing and fixing gun metal gate valve with CI wheel of approved quality. 20 mm nominal bore	No	50.00	533.20	543.86 ✓	27193
24	25 mm nominal bore	No	50.00	625.43	637.94 ✓	31897
25	40 mm nominal bore	No	30.00	810.41	826.62 ✓	24799
26	50 mm nominal bore	No	25.00	1084.16	1105.84 ✓	27646
27	65 mm nominal bore	No	25.00	1804.18	1840.26 ✓	46007
28	80 mm nominal bore	No	15.00	2767.65	2823.00 ✓	42345
29	Supply of GI Pipe Specials conforming to IS 1239 (Part-2) (subject to non availability in Stores) 20 mm dia G.I elbows	No	200.00	39.00	39.78 ✓	7956
30	25 mm dia G.I elbows	No	200.00	54.00	55.08 ✓	11016
31	40 mm dia G.I elbows	No	250.00	115.00	117.30 ✓	29325
32	50 mm dia G.I elbows	No	150.00	206.00	210.12 ✓	31518
33	65 mm dia G.I elbows	No	100.00	322.00	328.44 ✓	32844
34	80 mm dia G.I elbows	No	60.00	432.00	440.64 ✓	26438
35	20 mm to 15 mm G.I. sockets (reducing)	No	250.00	24.00	24.48 ✓	6120
36	25 mm to any smaller size G.I. sockets (reducing)	No	250.00	30.00	30.60 ✓	7650
37	40 mm to any smaller size G.I. sockets (reducing)	No	200.00	55.00	56.10 ✓	11220
38	50 mm to any smaller size G.I. sockets (reducing)	No	150.00	91.00	92.82 ✓	13923
39	80-65 Reducing Socket	No	20.00	150.00	153.00 ✓	3060
40	15 mm G.I. Tee (equal)	No	300.00	32.00	32.64 ✓	9792
41	20 mm G.I. Tee (equal/reducing)	No	200.00	54.00	55.08 ✓	11016
42	25 mm G.I. Tee (equal/reducing)	No	200.00	72.00	73.44 ✓	14688
43	40 mm G.I. Tee (equal/reducing)	No	150.00	145.00	147.90 ✓	22185
44	50 mm G.I. Tee (equal/reducing)	No	100.00	230.00	234.60 ✓	23460
45	50 mm G.I. Tee (equal/reducing)	No	50.00	300.00	306.00 ✓	15300
46	80 mm G.I. Tee (equal/reducing)	No	20.00	572.00	583.44 ✓	11669

[Handwritten signature]

[Handwritten signature]
Ken

47	15 mm G.I Nipple of length 3", 4" and 6"	No	50.00	35.00	35.70	✓	1785
48	20 mm G.I Nipple of length 3", 4" and 6"	No	80.00	46.00	46.92	✓	3754
49	25 mm G.I Nipple of length 3", 4" and 6"	No	80.00	69.00	70.88	✓	5690
50	40 mm G.I Nipple of length 3", 4" and 6"	No	60.00	104.00	106.08	✓	6365
51	50 mm G.I Nipple of length 3", 4" and 6"	No	20.00	144.00	146.88	✓	2938
52	Providing and fixing CI double acting Air Values of approved quality with nuts, bolts etc Complete (Tail pieces, tappers if required will be paid seperately 50mm dia	No	10.00	5661.86	5775.10	✓	57751
53	Laying and fitting of G.I. Pipes in trenches with flanged joints including cost of MS Flanges, nuts, bolts etc but excluding cost of earth work and pipes. 100mm dia	Joints	18.00	1800.00	1836.00	✓	33048
54	Laying in position 125mm dia D.I. Pipes in trenches excluding cost of pipes and earth work.	Qtl	720.00	245.55	250.46	✓	180332
55	Providing push on Joints to 125mm dia D.I. Pipes including cost of rubber insertion complete.	Joints	727.00	144.70	147.59	✓	107301
56	Providing, fabricating /fixing of GI/ MS bends of required degree /size complete job 125 mm dia	No	4.00	2000.00	2040.00	✓	8160
57	Providing, fabricating /fixing of GI/ MS Tee of required degree /size complete job 125 mmx80mm.	No	1.00	2000.00	2040.00	✓	2040
58	Providing and fixing 125mm dia Sluice Value with Wheel type handle including cost of flanges, nuts, bolts, rubber insertion all carriages complete.	No	2.00	25000.00	25500.00	✓	51000
59	Providing and fixing 100mm dia Sluice Value with Wheel type handle including cost of flanges, nuts, bolts, rubber insertion all carriages complete.	No	2.00	18000.00	18360.00	✓	36720
60	Providing and fixing 80mm dia Sluice Value with Wheel type handle including cost of flanges, nuts, bolts, rubber insertion all carriages complete.	No	2.00	15000.00	15300.00	✓	30600
61	Providing and fixing Gun Matel Gate Value with C.I Wheel of approved quality (Screwed end) 50mm dia Gate values	No	20.00	1037.00	1057.74	✓	21155
62	Providing and fixing Gun Matel Gate Value with C.I Wheel of approved quality (Screwed end) 40mm dia Gate values	No	30.00	775.17	790.67	✓	23720
63	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc, in layers no exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5m	Cum	6400.00	229.00	233.58	✓	1494912
64	Carriage of materials from source to road site of work by Mechanical Transport including loading unloading and stacking complete. Cement and Steel 15 Km's	MT	49.56	304.00	310.08	✓	15368
65	Stones/ Soling Stones 7 Km's	Cum	18.00	278.00	283.56	✓	5104
66	Sand 7 km's and 20mm crushed aggregate	Cum	297.00	236.00	240.72	✓	71494
67	Crushed Aggregate 40mm nominal Size 7 Kms	Cum	10.80	257.00	262.14	✓	2831
68	G.I Pipes below 100mm dia from divisional store avg 15Kms	MT	192.64	306.18	312.30	✓	60162
69	125/100mm Dia D.I./G.I Pipes	HMtr	40.00	459.35	468.54	✓	18741

Handwritten signature in blue ink.

Handwritten signature in black ink with 'See Xerox' written below it.

70	Carriage of materials from road site upto actual site of work by manual means (Head Load) avg 500 mtrs including loading unloading and stacking complete. Cement	MT	49.56	282.00	287.64	14255
71	Stones / Soling	Cum	18.00	731.00	745.62	13421
72	Sand and 20mm Crushed agg	Cum	279.00	621.00	633.42	176724
73	40mm crushed aggregate	Cum	10.80	671.55	684.98	7398
74	Carriage of materials from road site upto actual site of work by manual means (Head Load) avg 1500 mtrs GI pipes below 100mm dia	MT	192.64	770.01	785.41	151301
75	125/100mm Dia D.I/G.I Pipes avg 500mtr	HMtr	40.00	626.64	649.12	25567
Total						11842983

Rupees one crore eighteen lacs forty two thousand nine hundred and eighty three only

TERMS & CONDITIONS:

- 1 The contractor shall draw agreement with the Executive Engineer Spl Sub Div Tangdar within a period of 07 days from the date of issue of allotment order and failing to execute such an agreement in time shall not however prevent this contract being enforced against the contractor and the conditions laid down in the SBD shall hold good even before drawal of formal agreement .
- 2 The work shall have to be executed strictly in accordance with the approved proposals and specifications of the sanctioned estimates
- 3 The date of start of work shall be reckoned from the date of issuance of allotment order subject to the working weather conditions
- 4 It shall be mandatory for the executing agency / contractor to ensure safe and adequate supply of electricity required for all the workmen skilled /unskilled deployed at site of work.
- 5 Suitable arrangement for supply of potable water at site of work for all the workmen skilled/unskilled be made by
- 6 Arrangement for sufficient sanitation facility at site be ensured by the executing agency / contractor for all the workmen to be mobilized at site besides , saperate toilet facilities be provided for female workers at the site of work
- 7 Performance security equivalent to 03% of the value of the contract i.e Rs. 351000 valid in accordance with bid condition shall have to be furnishd by you in shape of CDR/FDR/Bank Gurantee within one week of the date of issuance of allotment order or at the time of signing of agreement whichever is earlier.
- 8 Insurance cover as admissible under rules shall be provided to all workers / skilled / unskilled deployed at site and the necessary premiums shall be borne by the executing agency / contractor itself.
- 9 Payment are subject to the recommendations of the third party verification agency (M/S WARCOS Ltd) or any other agency engaging by the Govt for the purpose.

TIME OF COMPLETION

The work shall be completed within a period of (90 working Days) after the date of issue of allotment. In the event of the contractor failing / declining /neglecting /causing delay in the execution of the work, penalty to the extent of 10% of the allotted amount shall be imposed on the contractor and the work shall be got executed departmentally or through any other agency at the risk and extra cost of the contractor besides action under rules for black listing of the contractor shall be taken up by the department.

EARNEST MONEY :

The BG for Rs. 3.51 lacs dttd: 23.05.2023 from State Co op Ban Ltd Branch Budgam pledged to Executive Engineer Spl Sub Division Tangdar shall be retained in this office till successful completion of the above mentioned work after the expiry of the Defective Liability Period (D.L.P)

ADVANCE PAYMENT :

No mobilization advance or advance payment shall be made to the allottee (Contractor)

GENERAL :


All other terms and conditions as laid down in the E-NIT No. 11 of 2023-24, dt 17.05.2023, issued under order No. 420-28 Dt. 17.05.2023, from this office shall be binding on the contractor.

No: 917-27


Date: 15-6-2023



Head Drafts man



T.O



15/6/23.

Executive Engineer
Spl Sub Div Tangdar

Copy to the:-

1. Chief Engineer Kmr PHE Department Srinagar for information.
2. District Development Commissioner Kupwara (Chairman DJJM Kupwara) for favour of information.
3. District Superintending Engineer Hydraulic Circle Kupwara HQ- Kupwara (Secretary DJJM Kupwara) for favour of information
4. Technical officer to Chief Engineer JSD (PHE) Kashmir for favour of information to Chief Engineer.
5. Team Leader WAPCOS Kupwara for information & necessary action.
6. AEE PHE Sub-Division Tangdar for information. He is directed to get the work executed as per approved drawings /Specifications within allotted cost.
7. HD/AAO / Divisional office for information & record.
8. File Concern.