

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 10 of 06/2023

M/S : Showkath Ahmad Malik
S/O : Mohammad Shafi Malik
R/O : Bandipore Kashmir
Registration No. : SB/123-SE(R&B) A-Class/1998-99
TIN No./GST No:- : 01GMBPM9821C1ZE

Name of work : Construction of Water Supply Scheme Lower Nambla by way of Construction of Intake Chambers/Service Reservoirs Protection works, , laying and fitting of GI Pipes and other allied works (for providing 100% FHTC)

eNIT No. : 01 /Hyd/Uri of 2023-24 TENDER ID 2023_IFC_209185_38
Your Tender Received in response to : eNIT No:01/Hyd/Uri_of_2023-24 Dated: 03/04/2023 issued under endorsement No:- HDU/CC-02/11-21 Dated: 03/04/2023 (S. No: 38) Tender ID : 2023_IFC_209185_38

Reference :
(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/2022/1214-44 Dated: 24-05-2022.
(viii) This Office Letter No: HDU/CC-02/404-05 Dated:- 26/04/2023 and No:- 509-10 Dated:- 01/05/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/971-83 Dated:- 01/05/2023

Ref: to AAA : Accorded vide Order No. 36/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.
Ref: to Tech. Sanction : Accorded vide Order No. CE/PHE/DB/558 of 09/2022 Dated:- 10/09/2022.
LOI Issued under No:- : NIT NO. 01/533-34 Dated:- 03/05/2023
Advertisement cost : Rs: 48.03Lacs
Allotted cost : ₹ 4995352.33 Rupees Forty Nine Lakh(s) Ninety Five Thousand Three Hundred Fifty Two And Paise Thirty Three Only

Time of completion : 120-days
M.H. of Account : (JJM)
Ref. To CDR/FDR No. : FDR NO: 593845 Dated: 06/05/2023 Amount: ₹ 150,000.00
Name of the Bank : J&K Bank Ltd. Branch Office Bandipore

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

- 1 Time of completion is essence of the contract.

- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depoition of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by

Head Craftsman

NO: HD/CC-04/

DATED:

Copy to the:

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/971-83 Dated:- 03/05/2023.
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla(Member DJJM) for information.
- 9 Chief Medical Officer Baramulla(Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.

Executive Engineer
Hydraulic Division Uri

Annexure "A" to the Allotment Order No. 10 of 06/2023

Construction of Water Supply Scheme Lower Nambla by way of Construction of Intake Chambers/Service Reservoirs Protection works, laying and fitting of GI Pipes and other allied works (for providing 100% FHTC)

S#	Particulars	Qty	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
1.1	In all kinds of soils	3028.620	Cum	539.350	1633486.20
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	2613.210	Cum	198.700	519244.83
3	Providing and laying stone soling 2nd class	14.010	Cum	616.400	8635.76
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	9.110	Cum	4861.840	44291.36
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	7.200	Cum	6465.195	46549.40
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	15.280	Cum	7800.760	119195.61
7	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand; 3 graded stone aggregate 20mm nominal size.	17.990	Cum	9408.135	169252.35
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	2.200	Cum	9849.345	21668.56
9	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement	3.390	Cum	10404.515	35271.31
10	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
10.1	Foundations, footings, bases of columns	26.980	Sqm	262.300	7076.85
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	263.990	Sqm	573.850	151490.66
10.3	Suspended floors, roofs, landings, balconies and access platform.	19.020	Sqm	635.600	12089.11
10.4	Arches, Domes, walls upto 60 mtr span	33.890	Sqm	2086.800	70721.65

S#	Particulars	Qty	Unit	Rate	
11	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	269.530	Sqm	358.00	
12	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	400.000	Kg	67.650	
13	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	4132.710	Kg	87.175	
14	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	267.390	Kg	102.140	
15	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
15.1	65mm dia	4.000	Nos	5000.000	20000.00
16	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality				0.00
16.1	50mm dia	12.000	Nos	500.000	6000.00
17	Providing and fixing of (8mm-thick) MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carriages upto site of work complete job.				0.00
17.1	65mm dia				
17.2	50mm dia	100.000	Joints	1100.000	110000.00
17.3	40mm dia	309.000	Joints	1000.000	309000.00
18	Laying and fitting of GI Pipes excluding trenching and refilling etc.(Including providing and fixing of Pipe Specials/fittings	145.000	Joints	900.000	130500.00
18.1	65 mm dia GI pipes				0.00
18.2	50 mm dia GI pipes	1200.000	Mtr	73.050	87660.00
18.3	40 mm dia GI pipes	4500.000	Mtr	40.800	183600.00
18.4	25 mm dia GI pipes	1700.000	Mtr	40.800	69360.00
18.5	20 mm dia GI pipes	2000.000	Mtr	30.650	61300.00
18.6	15mm dia GI pipes	2500.000	Mtr	20.250	50625.00
19	Making connection of GI distribution branch with GI main of following sizes, by P/F of tees, incld. cutting and threading the pipe etc. complete	1500.000	Mtr	20.250	30375.00
19.1	25 to 40 mm dia nominal bore				0.00
20	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer	20.000	No	666.250	13325.00
20.1	Cement and Steel (55Kms)				0.00
20.2	Pipes (60 kms)				
20.3	Sand. (60 kms)	40.920	Mton	666.760	27283.82
20.4	Agg. 20mm (80Kms)	52.190	Mton	666.760	34798.20
20.5	Agg. 40mm (80Kms)	46.970	Cum	799.730	37563.32
20.6	Stone Soling (07-Kms)	70.860	Cum	998.450	70750.17
		8.210	Cum	1083.200	8893.07
		14.010	Cum	277.700	3890.58

(Signature) MMX


7.650
100
360268
7311.21

Particulars		Qty	Unit	Rate	Amount
Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer					0.00
21.1	Cement (1000 mtrs)	36.790	Mton	460.460	16940.32
21.2	Pipes (1000 mtrs)	52.190	Mton	580.640	30303.60
21.3	Steel (1000 mtrs)	4.140	Mton	989.140	4095.04
21.4	Sand. (1000 mtrs)	46.970	Cum	1078.220	50643.99
21.5	Agg. 20mm (1000 mtrs)	70.860	Cum	1078.220	76402.67
21.6	Agg. 40mm (1000 mtrs)	8.210	Cum	1165.590	9569.49
21.7	Stone Soling (500 mtrs)	14.010	Cum	730.800	10238.51
				Total	4803223.40
					4995352.332

Excess (+)	4.00%
------------	-------

Checked by

Head D/Man



Executive Engineer
Hydraulic Division Uri

