

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: uri.hydraulic@gmail.com

Allotment Order No. 12 of 07/2023

M/S : **Mohammad Ahyas Khan**
S/O : **Habibullah Khan**
R/O : **Niloosa Uri**
Registration No. : **CE/R&B/K/01/A-Class/Civil/1999-2000**
Class : **A**
TIN No./GST : **01AHMPK0673L1ZB**

Name of work : **Construction of Water Supply Scheme Braripora Mayan Bijhama by way of Construction/Commissioning and Testing of PSTs/SRS/SSFPs/ (for providing 100% FHTC) under JJM**

e/NIT No. : **14 /Hyd/Uri of 2022-23** TENDER ID : **2022_IFC_1171267_6**
Your Tender Received in response to : **ENIT 14/Hyd/Uri of 2022-23 Dated: 28/05/2022 issued under endorsement No:- HDU/CC-02/851-67 Dated: 28/05/2022 (S.No: 08) Tender ID : 2022_IFC_171267_8**

Reference

(i) **Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.**
(ii) **Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K meeting convened on 04-09-2021.**
(iii) **Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.**
(iv) **Chief Engineer Kashmir-PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Enclt. No. CE/PHE/DB/41981-42033 Dated: 21-02-2022.**
(v) **UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).**
(vi) **Chief Engineer Kashmir-PHE Jal Shakti Department Srinagar's office letter No: CEPHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.**
(vii) **Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM R/a) authorization issued vide No: DDC/BM/Meeting/ 2022/1214-44 Dated: 24-05-2022.**
(viii) **District Superintending Engineer Hyd. Circle Bta/Bpr HO Sopore authorization No: SE/Hyd/DB/4551-63 Dated:- 22/07/2022.**

Ref: to AAA

Ref: to TS

: **Accorded vide Order No. CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022 issued under Endorsement No:- CE/PHE/DB/18266-74 Dated:- 31/08/2022**

: **Accorded vide Order No. CE/PHE/DB/190 of 08/2022 Dated:- 31/08/2022 issued under Endorsement No:- CE/PHE/DB/18836-40 Dated:- 01/09/2022.**

LOI issued under NO:- HDU/CC-02/eNIT-14/1703-16 Dated:- 28/07/2022.

Advertisement cost : **Rs:117,52Lacs**

Allotted cost

: **₹ 12222059.79**

Rupees One Twenty Two Lakhs(s) Twenty Two Thousand Fifty Nine And Paise Seventy Eight Only

Time of completion : **120-days**

M.H. of Account : **(JJM)**

Ref. To CDR No. : **3136440**

Name of the Bank : **J&K Bank Ltd.**

Dated: **23/05/2022**

Amount: **₹ 244,440.00**

Branch Office **Chandanwari**

For and on behalf of L.T. Governor of J&K UT the contract for above noted work is fixed with you

on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the



Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

- 1 Time of completion is essence of the contract.
- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depositions of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by

Head Drafter
NO: HDU/CC-0A/

DATED:

1806-18
12-07-2023.

Copy to the:

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: SE/Hyd/DB/4551-62 Dated:- 23/07/2022.
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
Assistant Executive Engineer PHE Sub Division Uri for information. This is in continuation to this office LOI issued under No: HDU/CC-02/eNIT-14/1703-16 Dated:- 28/07/2022.
- 12 File.

Executive Engineer
Hydraulic Division Uri

(Syed Shafiq)

Annexure "A" to the Allotment Order No. 12 of 07/203

Construction of Water Supply Scheme Braripora Mayan Bijhama by way of Construction/Commissioning and Testing of PSTs/ SRs/SSFPs/ (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1.00	E/W in bulk excavation by manual means over areas (exceeding 30cm in depth, 1.5Mtr in width as well as 10 sqm on plan)including disposal of excavated earth lead upto 50Mtrs and lift upto 1.5Mtr as directed by the Engineer Incharge				
1.10	In all kinds of soils	1816.472	Cum	539.350	979714.17
2.00	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	225.198	Cum	198.700	44746.84
3.00	Providing and laying stone soling 2nd class incl. cost of stones	80.566	Cum	616.400	49660.88
4.00	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	53.437	Cum	4861.835	259801.88
5.00	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	31.650	Cum	6465.195	204623.42
6.00	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	142.517	Cum	7800.760	1111740.91
7.00	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	180.002	Cum	9408.135	1693483.12
8.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	14.504	Cum	9849.345	142854.90
9.00	Providing and fixing upto floor five level precast cement concrete string or lacing, courses copings bed plates anchor blocks plain window sills, shelves, louvers, steps stair cases etc including hoisting and setting fr psition with cement mortar 1:3 (1 cement: 3 coarse sand) cost of required centring shuttering and curing complete l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	0.954	Cum	8679.000	8279.77

(Handwritten signatures and initials)

S#	Particulars	Qty	Unit	Rate	Amount
10.00	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement	35.123	Cum	10404.515	365437.78
11.00	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
11.10	Foundations, footings, bases of columns	70.066	Sqm	262.300	18378.31
11.20	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	1492.297	Sqm	573.850	856354.63
11.30	Suspended floors, roofs, landings, balconies and access platform.	97.412	Sqm	635.600	61915.07
11.40	Arches, Domes, walls upto 60 mtr span	258.951	Sqm	2086.800	540378.95
12.00	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	1766.440	Sqm	357.995	632376.69
13.00	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	1495.000	Kg	61.500	91942.50
14.00	Providing and fixing of MS surface boxes (1mx1mx1m) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	6.000	Kg	102.140	612.84
15.00	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	785.350	Kg	102.140	80215.65
16.00	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	28808.665	Kg	87.175	2511395.37
17.00	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	7.300	Kg	102.140	745.62
18.00	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case raklling and similar works and applying primer coat	129.740	Kg	174.250	22607.20
19.00	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				
19.10	150mm dia	9.000	Nos	9000.000	81000.00
19.20	100mm dia	6.000	Nos	7500.000	45000.00
19.30	80mm dia	2.000	Nos	6000.000	12000.00
19.40	50mm dia	2.000	Nos	5000.000	10000.00
19.50	40mm dia	6.000	Nos	4000.000	24000.00
20.00	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality				
20.10	80mm dia	22.000	Nos	600.000	13200.00
20.20	50mm dia	18.000	Nos	500.000	9000.00
21.00	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia ength	65.000	No	200.000	13000.00
22.00	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	88.560	Cum	8500.000	752760.00





S#	Particulars	Qty	Unit	Rate	Amount
23.00	Providing and fixing of (8mm-Thick) MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers, gaskets including all carriages upto site of work complete job.				
23.10	100mm dia	154.000	Joints	1300.000	200200.00
23.20	80mm dia	32.000	Joints	1000.000	32000.00
24.00	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				
24.10	Cement and Steel (46 Kms)	192.465	Mton	587.271	113029.11
24.20	Sand. (51Kms)	215.042	Cum	710.309	152746.27
24.30	Agg. 20mm (91Kms)	303.909	Cum	1107.749	336654.89
24.40	Agg. 40mm (91Kms)	48.104	Cum	1203.993	57916.86
24.50	Stone Soling (07-Kms)	73.396	Cum	276.345	20282.62
25.00	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				
25.10	Cement (100Mtrs)	161.615	Mton	139.400	22529.13
25.20	Steel (100Mtrs)	30.830	Mton	299.410	9230.81
25.30	Sand.(100Mtrs)	215.042	Cum	255.600	54964.74
25.40	Agg. 20mm (100Mtrs)	303.909	Cum	255.600	77679.14
25.50	Agg. 40mm (100Mtrs)	48.112	Cum	276.320	13294.31
25.60	Stone Soling (100Mtrs)	80.566	Cum	300.700	24226.20
				Total	11751980.56
Excess (+)		4.00%		12222059.79	

Rupees One Crore Twenty Two Lakh(s) Twenty Two Thousand Fifty Nine And Paise Seventy Eight Only

Checked by

Head Division

Executive Engineer
Hydraulic Division Uri