

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI  
email: urihydraulic@gmail.com

Allotment Order No. 32 of 07/2023

M/S : AIJAZ AHMAD AWAN  
S/O : Abdul Latief Awan  
R/O : Sultan Dhaki Uri  
Registration No. : SE-R&B-SB/BEE 189 of 2019-20  
TIN No./GST No:- : 01AKCPA1123A1ZO

Name of work : Construction of Water Supply Scheme Jhulla Chidi Maidanan by way of Construction/SRs Chain Link Fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-A)

eNIT No. : 49 /Hyd/Uri of 2022-23 TENDER ID 2023\_IFC\_204393\_72  
Your Tender Received in response to : eNIT No:49/Hyd/Uri\_of\_2022-23 Dated: 11/01/2023 issued under endorsement No:- HDU/CC-02/5279-89 Dated: 07/02/2023 (S. No: 72) Tender ID : 2023\_IFC\_204393\_72

Reference :

- (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.
- (ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.
- (iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.
- (iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.
- (v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).
- (vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.
- (vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.
- (viii) This Office Letter No: HDU/CC-02/5845-46 Dated:- 02/03/2023
- (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/15662-74 Dated:- 07/03/2023

LOI issued under No:- : NIT NO. 49/6041-42 Dated:- 08/03/2023  
Ref: to AAA : Accorded vide Order No. 27/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.  
Ref: to Tech. Sanction : Accorded vide Order No.CE/PHE/DB/538 of 09/2022 Dated:- 10/09/2022  
Advertisement cost : Rs:38.81Lacs  
Allotted cost : ₹ 3931157.93 Rupees Thirty Nine Lakh(s) Thirty One Thousand One Hundred Fifty Seven And Paise Ninety Three Only

Time of completion : 120-days  
M.H. of Account : (JJM)  
Ref. To CDR No. :  
Name of the Bank :

Bid Security Declaration Format

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

**Terms and Conditions:-**

1 Time of completion is essence of the contract.

- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week after issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 13 Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

  
Head Assistant

NO: HDU/CC-04/ 2212-24

DATED: 10-7-2023

Copy to the:

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/15662-74 Dated:- 07/03/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla(Member DJJM) for information.
- 9 Chief Medical Officer Baramulla(Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.


  
Executive Engineer  
Hydraulic Division Uri

(Syed Shafiq)

**Annexure "A" to the Allotment Order No. 32 of 07/2023**

**Construction of Water Supply Scheme Jhulla Chidi Maidanan by way of Construction/ SRs Chain Link Fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-A)**

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5 in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils(Bulk)	300.830	Cum	560.924	168742.77
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	59.910	Cum	206.648	12380.28
3	Providing and laying stone soling 2nd class including cost of stones	23.240	Cum	641.056	14898.14
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	15.600	Cum	5056.308	78878.41
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	52.170	Cum	6723.803	350780.79
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	27.050	Cum	8112.790	219450.98
7	Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	42.440	Cum	9784.460	415252.50
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	2.400	Cum	10243.319	24583.97
9	Providing hoisting and fixing upto floor five level pre cast reinforced cement concrete work in string courses, bends, coopings, bedplates, anchor block, piain window silis, and the like including setting in position in cement mortar 1:5:3 including cost of centering shuttering and curring but excluding cost of reinforcement 1:1.5:3 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	0.841	Cum	9397.846	7903.59
10	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 15° floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement	0.860	Cum	10820.696	9305.80



#	Particulars	Qty	Unit	Rate	Amount
11	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
11.1	Foundations, footings, bases of columns	12.810	Sqm	272.792	3494.47
11.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	585.200	Sqm	596.804	349249.70
11.3	Suspended floors, roofs, landings, balconies and access platform.	17.140	Sqm	661.024	11329.95
11.4	Arches, Domes, walls upto 60 mtr span	8.600	Sqm	2170.272	18664.34
11.5	Columns, Pilers, abutment, posts and struts.	12.600	Sqm	707.356	8912.69
12	12mm thick cement plaster of mix 1:4 (1-cement: 4-sand)	478.600	Sqm	372.315	178189.86
13	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	85.000	Kg	70.356	5980.26
14	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	545.000	Kg	106.226	57892.95
15	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1741.610	Kg	106.226	185003.57
16	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	6669.700	Kg	90.636	604514.93
17	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	89.130	Kg	106.226	9467.89
18	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat	19.210	Kg	197.798	3799.69
19	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
19.1	50mm dia	7.000	Nos	4160.000	29120.00
20	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality			0.000	0.00
20.1	50mm dia	6.000	Nos	624.000	3744.00
21	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engh	20.000	No	208.000	4160.00
22	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	70.080	Cum	8840.000	619507.20
23	Providing and Fixing of 4mm thick GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	156.000	Sqm	762.840	119003.04
24	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
24.1	Cement and Steel (55 Kms)	73.520	Mton	693.429	50980.93

21/11/20  
S. H. AMZ

S#	Particulars	Qty	Unit	Rate	Amount
24.2	Sand. (60Kms)	72.180	Cum	831.722	60033.72
24.3	Agg. 20mm (85Kms)	108.150	Cum	1090.058	117889.81
24.4	Agg. 40mm (85Kms)	14.040	Cum	1184.770	16634.17
24.5	Stone Soling (07-Kms)	23.240	Cum	288.808	6711.90
25	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
25.1	Cement (500Mtrs)	52.470	Mton	293.374	15393.31
25.2	Steel (500Mtrs)	8.300	Mton	630.188	5230.56
25.3	Sand.(500Mtrs)	72.260	Cum	646.048	46683.43
25.4	Agg. 20mm (500Mtrs)	108.140	Cum	646.048	69863.63
25.5	Agg. 40mm (500Mtrs)	14.120	Cum	698.412	9861.58
25.6	Stone Soling (500Mtrs)	23.240	Cum	760.032	17663.14
				<b>Total</b>	<b>3931157.93</b>

Rupees Thirty Nine Lakh(s) Thirty One Thousand One Hundred Fifty Seven And Paise Ninety Three Only

Checked by

Head of

*[Handwritten signature]*  
21/10/21

**Executive Engineer**  
**Hydraulic Division Uri**