

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 48 of 07/2023

M/S : BALOTE CONSTRUCTION COMPANY
Prop. : Mohd Ashraf Balote
S/O : Qammar-ud-Din Balote
R/O : Garkote Uri
Registration No. : 117/AAY/CE/CID/PDC/2010-11
TIN No./GST No:- : 01ANAPA7383B1ZS

Name of work : Construction of Water Supply Scheme Bandi Machikrand by way of Construction/ Commissioning and Testing of SSFPs/ (for providing 100% FHTC) under JJM

eNIT No. : 01 /Hyd/Uri of 2023-24 TENDER ID 2023_IFC_209185_13
Your Tender Received : eNIT No:01/Hyd/Uri_of_2023-24 Dated: 03/04/2023 issued under endorsement No:-
in response to : HDU/CC-02/11-21 Dated: 03/04/2023 (S. No: 13) Tender ID : 2023_IFC_209185_13

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.
(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/3005-3018 Dated: 15/06/2023

Ref: to AAA : Accorded vide Order No. CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.
Ref: to Tech. Sanction : Accorded vide Order No. CE/PHE/DB/189 of 08/2022 Dated:- 31/08/2022.
LOI Issued under No:- : NIT NO. 01/1319-20 Dated:- 17/06/2023
Advertisement cost : Rs: 60.23 Laes
Allotted cost : ₹ 6264467.53 Rupees Sixty Two Lakh(s) Sixty Four Thousand Four Hundred Sixty Seven And Paise Fifty Three Only

Time of completion : 120-days
M.H. of Account : (JJM)
Ref. To CDR/TDR No. : BSDF:
Name of the Bank :

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the

expiry of warranty period of the contract.

- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after deposition of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.


Head Assistant

NO: HDU/CC-04/ 2578-89

DATED: 19-7-2023.

Copy to the:


Executive Engineer
Hydraulic Division Uri
(Syed Shafiq)

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 5 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 6 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 7 Chief Planning Officer Baramulla(Member DJJM) for information.
- 8 Chief Medical Officer Baramulla(Member DJJM) for information.
- 9 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.
- 10 District Information Officer Baramulla (Member DJJM) for information.
- 11 Assistant Executive Engineer PHE Sub Division Uri for information.
- 12 File.

Annexure "A" to the Allotment Order No. 48 of 07/2023

Execution of Water Supply Scheme Bandi Machikrand by way of Construction/ Commissioning and Testing of SSFPs/ (for providing 100% FHTC) under JJM

	Particulars	Qty	Unit	Rate	Amount
	Earth work in bulk excavation by manual means over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on an area including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
	Excavation in all kinds of soils (Bulk)	499.420	Cum	539.350	269362.18
	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	90.430	Cum	198.700	17968.44
	Providing and laying stone soling 2nd class	33.180	Cum	616.400	20452.15
	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	22.900	Cum	4861.835	111336.02
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centering, and shuttering (all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	31.990	Cum	6465.195	206821.59
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	66.080	Cum	7800.760	515474.22
7	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing and reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	75.990	Cum	9408.135	714924.18
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	4.470	Cum	9849.345	44026.57
9	Providing and fixing upto floor five level precast cement concrete string or lacing, courses copings bed plates anchor blocks plain window sills, shelves, louvers, steps stair cases etc including hoisting and setting in position with cement mortar 1:3 (1 cement: 3 coarse sand) cost of required centering shuttering and curing complete 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	1.154	Cum	8679.000	10015.57
10	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
10.1	Foundations, footings, bases of columns	34.260	Sqm	262.300	8986.40

24/10/23


[Handwritten Signature]

Particulars		Qty	Unit	Rate	Amount
	ing walls, return walls, walls (any thickness) including shed pilasters, buttresses, plinth and string courses fillets	761.650	Sqm	573.850	437072.85
	ended floors, roofs, landings, balconies and access form.	37.480	Sqm	635.600	23822.29
	mm cement plaster of mix 1:4 (1-cement: 4-sand)	915.220	Sqm	357.995	327644.18
	roviding and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	170.000	Kg	67.600	11492.00
	roviding and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1090.000	Kg	102.140	111332.60
	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	923.880	Kg	102.140	94365.10
5	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	12080.230	Kg	87.175	1053094.05
16	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	153.480	Kg	102.140	15676.45
17	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat	83.750	Kg	190.190	15928.41
18	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
18.1	65mm dia	2.000	Nos	5000.000	10000.00
18.2	50mm dia	2.000	Nos	4000.000	8000.00
19	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia ength	40.000	No	200.000	8000.00
20	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	150.960	Cum	8500.000	1283160.00
21	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
21.1	Cement and Steel (50Kms)	82.320	Mton	578.439	47617.10
21.2	Sand. (60 kms)	110.340	Cum	711.873	78548.07
21.3	Agg. 20mm (100Kms)	154.830	Cum	1068.005	165359.21
21.4	Agg. 40mm (100Kms)	20.610	Cum	1160.799	23924.07
21.5	Stone Soling 7km	33.180	Cum	276.322	9168.36
22	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer 1000mtr				0.00
22.1	Cement	68.050	Mton	460.460	31334.30

Particulars	Qty	Unit	Rate	Amount
	14.270	Mton	989.138	14115.00
d.	110.640	Cum	1078.217	119293.93
j. 20mm	154.830	Cum	1078.217	166940.34
g. 40mm	20.610	Cum	1165.594	24022.89
one Soling (500-Mtrs)	33.180	Cum	730.800	24247.94
			Total	6023526.47
Excess (+)	4.00%			6264467.53

Rupees Sixty Two Lakh(s) Sixty Four Thousand Four Hundred Sixty Seven And Paise Fifty Three Only

Checked by

Head D/Man



Executive Engineer
Hydraulic Division Uri