

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI  
email: urihydraulic@gmail.com

Allotment Order No. 57 of 07/2023

M/S : Naveed & Co.  
Prop : Naveed Anjum  
S/O : Ghulam Qadir Ganai  
R/O : Chandanwari  
Registration No. : CE/UEED/AAAY/30/2005-06  
TIN No./GST No:- : 01AIXPG9710G1Z8

Name of work : Construction of Water Supply Scheme Zamhoor Pattan by way of Construction/Commissioning and Testing of PSTs, Intake Chambers, Chain Link Fencing and other allied works (for providing 100% FHTC) under JJM

eNIT No. : 53 /Hyd/Uri of 2022-23 TENDER ID 2022\_IFC\_207248\_26  
Your Tender Received in response to : eNIT No:53/Hyd/Uri\_of 2022-23 Dated: 06/03/2023 issued under endorsement No:- HDU/CC-02/5930-40 Dated: 06/03/2023 (S. No: 26) Tender ID : 2022\_IFC\_202344\_26

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.  
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.  
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.  
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.  
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).  
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.  
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.  
(viii) This Office Letter No: HDU/CC-02/6399-6400 dated:- 31/03/2023  
(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/189-201 Dated:- 05/04/2023

Ref: to AAA : Accorded vide Order No. 31/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.  
Ref: to Tech. Sanction : Accorded vide Order No.CE/PHE/DB/537of 09/2022 Dated:- 10/09/2022.  
LOI issued under No: : NIT No./53/47-48 Dated:- 05/04/2023  
Advertisement cost : Rs:28.37Lacs  
Allotted cost : ₹ 2950511.15 Rupees Twenty Nine Lakh(s) Fifty Thousand Five Hundred Eleven And Paise Fifteen Only

Time of completion : 120-days  
M.H. of Account : (JJM)  
Ref. To CDR No. :  
Name of the Bank :

BID Declaration Format Submitted

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates quoted by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"  
Terms and Conditions:-

1 Time of completion is essence of the contract.

- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 13 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.



Head Assistant

NO: HDU/CC-04/

DATED: 19-7-2023

Copy to the:

2663-75

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/218-301 Dated:- 05/04/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.


Executive Engineer  
Hydraulic Division Uri

**Annexure "A" to the Allotment Order No. 57 of 07/2022**

**Construction of Water Supply Scheme Zamboor Pattan by way of Construction/Commissioning and Testing of PSTs, Intake Chambers, Chain Link Fencing and other allied works (for providing 100% FHCT) under JJM**

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5 in width, as well as 10Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils (Bulk)	327.670	Cum	560.924	183797.97
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	31.468	Cum	206.648	6502.80
3	Providing and laying stone soling 2nd class including cost of stones	21.510	Cum	641.056	13789.11
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	12.970	Cum	5056.308	65580.32
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	68.950	Cum	6723.803	463606.20
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	9.680	Cum	8112.790	78531.81
7	Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size)	17.500	Cum	9784.460	171228.06
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	1.440	Cum	10243.319	14750.38
9	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	34.840	Cum	2600.000	90584.00
10	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
10.1	Foundations, footings, bases of columns	120.580	Sqm	272.792	32893.26
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	351.660	Sqm	596.804	209872.09
10.3	Suspended floors, roofs, landings, balconies and access platform.	6.680	Sqm	661.024	4415.64
10.4	Columns, Pilers, abutment, posts and struts.	12.600	Sqm	707.356	8912.69
11	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	256.260	Sqm	372.315	95409.39
12	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	50.000	Kg	70.356	3517.80
13	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm . Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	545.000	Kg	106.226	57892.95
14	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	2200.850	Kg	106.226	233786.61
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	4343.680	Kg	90.662	393806.72
16	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case rakling and similar works and applying primer coat	37.940	Kg	197.798	7504.44



	Particulars	Qty	Unit	Rate	Amount
17	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
17.1	50mm dia	2.000	Nos	4160.000	8320.00
18	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engh	20.000	No	208.000	4160.00
19	Providing and Fixing of 4mm-thick GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	156.090	Sqm	762.840	119071.70
20	Providing and fixing of bolts of 16mm Dia 25Cm Long fully threaded to be embed in cement concrete with bolts including all sorts of carriages Complete Job	68.000	No	208.000	14144.00
21	Providing and fixing of MS Plates for anchoring of pipe over saddle/anchor blocks with nuts and bolts already fitted in concrete 4mm thick 200 wide and average length 50cms MS Plate complete job in all respect	106.760	Kg	106.226	11340.65
22	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
22.1	Cement and Steel (45Kms)	50.410	Mton	601.578	30325.53
22.2	Sand. (50Kms)	54.930	Cum	728.385	40010.18
22.3	Agg. 20mm (95Kms)	115.760	Cum	1193.390	138146.78
22.4	Agg. 40mm (95Kms)	13.280	Cum	1297.390	17229.33
22.5	Stone Soling (07Kms)	63.780	Cum	288.808	18420.17
22.6	Chainlink fencing (45Kms)	0.170	Mton	601.578	102.27
23	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
23.1	Cement (2100Mtrs)	38.060	Mton	886.974	33758.25
23.2	Steel (2100Mtrs)	5.910	Mton	1905.415	11261.00
23.3	Sand.(2100Mtrs)	54.930	Cum	720.834	39595.43
23.4	Agg. (2100Mtrs)	115.760	Cum	2166.954	250846.64
23.5	Agg. 40mm (2100Mtrs)	13.280	Cum	2166.954	28777.15
23.6	Stone Soling (500Mtrs)	63.780	Cum	760.032	48474.84
23.7	Chainlink fencing (2100Mtrs)	0.170	Mton	886.974	144.99
	<b>Total</b>				<b>2950511.15</b>

Rupees Twenty Nine Lakh(s) Fifty Thousand Five Hundred Eleven And Paise Fifteen Only

Checked by

Head D/Man

2A

Executive Engineer  
Hydraulic Division Uri