

(Allotment)

GOVT. OF JAMMU AND KASHMIR

OFFICE OF THE DISTRICT SUPERINTENDING ENGINEER, SAVE THE WATER

HYDRAULIC CIRCLE KUPWARA -- HEADQUARTER HANDWARA

Fax/Phone: 01955262005 *****00***** email: sehydkupwara@gmail.com

M/S Riyaz Ahmad Bhat.

S/O: Ab Khaliq Bhat.

R/O: Sulkoot Kupwara.

Registration No: CE/UEED/AA/CIVIL/39/2018-19.

GSTIN NO: 01AQCPB1253G2ZR

ALLOTMENT ORDER NO: 22.....-DSE/HH/DB OF 2022-24 DT: 01/04/2023

Sub: - Construction of 0.65 lac galling, 0.60 lac gallons, 0.40 lac gallons, 0.25 lac gallons capacity RCC service Reservoirs with Sluice Chambers and Chain Link Fencing around Structures for 100% FHTC Under jjm for WSS Augmentation MEELYAL.

Ref: - 1. Minutes of the 8th meeting of Technical Appraisal Committee held on 08.02.2022, minutes issued thereof vide CE/PHE/44620-41 dated. 12-03-2022.

2. Accord of Administrative Approval vide Chief Engineer Kashmir PHE Deptt. Srinagar's Order No. CE/PHE/DB/JJM/267 of 09/2022 dated. 26/09/2022.

3. District Action Plan of District Kupwara by DJJM vide No. DDCK/Plg/JJM/4465-85 dated. 14-07-2022.

4. Govt. Order No. 19-JK (JSD) of 2022 dated. 04.02.2022

5. Technical Sanction Order No. CE/PHE/DB/717 of 10/2022 dated. 19/10/2022

6. District Development Commissioner Kupwara' Authorization No. DDCK/Plg/JJM/MOM/5861-66 Dated. 06-08-2022.

Advertised cost: - Rs : 146.11 LACS.

Allotted cost: - Rs : 15195798.00/.

(Rupees ONE Crore Fifty one Lacs Ninety Five Thousand Seven Hundred and Ninety Eight Rupees Only) For and on behalf of the Lt. Governor of Jammu and Kashmir UT, contract for Construction of 0.65 lac galling, 0.60 lac gallons, 0.40 lac gallons, 0.25 lac gallons capacity RCC service Reservoirs with Sluice Chambers and Chain Link Fencing around Structures for 100% FHTC Under jjm for WSS Augmentation MEELYAL. is hereby fixed with you on the accepted rates by you as shown in the enclosed Annexure of this allotment. The total cost of the work will be of the order of Rs 15195798.00/ (Rupees ONE Crore Fifty one Lacs Ninety Five Thousand Seven Hundred and Ninety Eight Rupees Only) on the terms and conditions as laid down in E- NIT No: No:-12 of 05/2022 Dated :- 16/11/2022 issued under endorsement No :- PHEDK/608-19 Dated 30/05/2022 . from the Executive Engineer PHE Division Kupwara shall be binding on the contractor.

Sl. No.	Item Description	Quantity	Units	Rate	AMOUNT
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge				
2	All sorts of soil	630.80	CUM	539.35	340221.980
3	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 min width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: (1 Mtr from cutting edge)				
4	All sorts of soil	208.35	CUM	436.00	90840.600

DSE

HD



5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	✓ 157.67	Cum	✓ 198.70	31329.029
6	Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads lifts and all carriages complete.	✓ 94.42	Cum	✓ 1320.00	124634.400
7	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	✓ 12.65	Cum	✓ 5437.74	68787.411
8	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	✓ 248.63	Cum	✓ 6465.20	1607442.676
9	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	✓ 74.65	Cum	✓ 4861.84	362936.356
10	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level				0
11	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	✓ 122.15	Cum	✓ 7800.76	952862.834
12	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	✓ 19.04	Cum	✓ 7676.55	146161.512
13	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement.				0
14	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	✓ 127.97	Cum	✓ 9408.14	1203959.676
15	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with:				0
16	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	✓ 13.18	Cum	✓ 9849.35	129814.433
17	Reinforced cement concrete work in arches, arch ribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level level including curing but excluding the cost of centering, shuttering finishing and reinforcement with:				0
18	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	✓ 46.67	Cum	✓ 10404.52	485578.948
19	Centering and shuttering including strutting, propping etc. and removal of form for:				0
20	Foundations, footings, bases of columns etc. for mass concrete.	✓ 85.39	sqm	✓ 262.30	22397.797

HD

TO

DSE

Attachment No. 22/DSE/HH/DB of 2022-23



21	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	1808.98 ✓	sqm	573.85 ✓	1038083.173
22	Suspended floors, roofs, landings, balconies and access platforms.	20.52 ✓	sqm	635.60 ✓	13042.512
23	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	70.52 ✓	sqm	502.85 ✓	35460.982
24	Arches, domes, vaults upto 6 m span	311.14 ✓	sqm	2086.80 ✓	649286.952
25	Extra for arches, domes, vaults exceeding 6 m span	311.14 ✓	sqm	1008.45 ✓	313769.133
26	Extra for shuttering in circular work (20% of respective centering and Shuttering items)	✓		✓	0
27	Foundation	85.39 ✓	sqm	52.46 ✓	4479.559
28	Walls	958.48 ✓	sqm	114.77 ✓	110004.750
29	Beams	58.63 ✓	sqm	100.57 ✓	5896.419
30	Domes	311.14 ✓	sqm	417.36 ✓	129857.390
31	Suspended floors	20.52 ✓	sqm	127.12 ✓	2608.502
32	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	682.00	kgs	57.90	39487.800
33	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete approved make from factory/workshop to construction site including placing in position and binding all complete upto plinth level.				0
34	Thermo-Mechanically Treated bars of grade Fe-500D or more.	28503.36	Kg	95.10	2710669.536
35	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	550.00	Kg	99.30	54615.000
36	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.welded	8613.54	Kg	111.42	959720.627
37	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works..	777.60	Kg	159.96	124384.896
38	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. (Made of G.I. wire of dia 4 mm)	695.40	sqm	733.50	510075.900
39	12mm Cement plaster				0
40	1 : 4 (1 cement : 4 fine sand	1189.94	sqm	286.06	340394.236
41	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	617.16	sqm	91.80	56655.288

HD

TO

DSE

Attachment no. 22/2024

42	Providing & fixing of MS pipes / fittings viz bends of suitable degree, tees, collars etc to be fabricated from 6mm Nominal Size MS plate as per the requirement of site including cost of welding. The work should be leakproof and should be painted with anti corrosive red oxide primer. Complete Job.	625.00	Kg	147.82	92387.500
43	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	1368.00	sqm	121.95	166827.600
44	Providing and fixing D.I. sluice valves Class 1 (with cap) complete with rubber insertions, bolts, nuts, extention rod, joint connector, supporting pedestal with base plate, top plate and necessary anchoring bolts etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest amendments. (if not available in Diviisonal Stores)				0
45	100 mm dia.	4.00	Each	19791.50	79166.000
46	150 mm dia.	4.00	Each	30728.00	122912.000
47	Providing & fixing of 0.63mm thick PGI shëets at construction joints including all leads and lifts complete job as directed by Engineer-in-charge	318.00	m	920.00	292560.000
48	Carriage of materials by mechanical transport including loading, unloading, stacking of materials				0
49	Soling by 10 km	94.42	Cum	330.42	31198.256
50	Stone Aggregate 40 mm size by 30 km	66.44	Cum	545.28	36228.403
51	Stone Aggregate 20 mm size by 30 km	525.36	Cum	501.65	263546.844
52	Sand by 50 km	333.94	Cum	501.65	167521.001
53	Cement by 30 km	156.11	MT	448.03	69941.963
54	TMT Steel by 30 km	28.50	MT	627.05	17870.925
55	Carriage of materials by manual means including loading, unloading, stacking of materials- (Subjected to Actual)				0
56	Soling by 400 m	94.42	Cum	623.28	58850.098
57	Stone Aggregate 40 mm size by 400 m	66.44	Cum	572.75	38053.510
58	Stone Aggregate 20 mm size by 400 m	525.36	Cum	529.81	278340.982
59	Sand by 400 m	333.94	Cum	529.81	176924.751
60	Cement by 400 m	156.11	MT	246.42	38468.626
61	TMT Steel by 400 m	28.50	MT	529.32	15085.620
	Total				14611344.00
	Add above 4% on all items				584454.00
	Total				Rs. 15195798.00

Draftsman

Technical Officer

District Superintending Engineer,
Hyd. Circle Kupwara
H.Q Handwara

HD

TTC



A Terms and Conditions: -

1. The contractor shall draw agreement with the Superintending Engineer Hyd. Circle Kupwara H.Q Handwara within 07 days from the date of issue of allotment order and failing to execute such an agreement in time shall not however prevent this contract being enforced against the contractor and the conditions laid down in the NIT shall hold good even before drawl of formal agreement.
2. The work shall have to be executed strictly in accordance with the approved proposals and specifications of the sanctioned estimates.
3. The date of start of work shall be reckoned from 07 days after issuance of allotment.
4. It shall be mandatory for the executing agency/ contractor to ensure safe and adequate supply of electricity required for all the workmen skilled/ unskilled deployed at site of work.
5. Suitable arrangements for supply of portable water at site of work for all the workmen skilled/ unskilled be made by the agency/ contractor just before the virtual start of execution at site.
6. Arrangements for sufficient sanitation facility at site be ensured by the executing agency / contractor for all the workmen to be mobilized at site besides, separate toilet facilities be provided for Female workers at the site of work.
7. **Performance security equivalent 03% of the value of the contract Rs. 438330/- valid in accordance with bid condition shall have to be furnished by you in shape of CDR/FDR/BG within one week of the date of issuance of allotment order or at the time of signing of agreement whichever is earlier**
8. Insurance cover as admissible under rules shall be provided to all workers/ skilled/unskilled deployed at site and the necessary premiums shall be borne by the executing agency/ contractor itself.
9. Payments are subject to the recommendation of the third party verification agency (M/s. WAPCOS Ltd)

B. Time of completion

The works shall be completed within a period of (150 Working Days) after the date of issue of allotment. In the event of the contractor failing / declining / neglecting / delay in the execution of the work, penalty to the extent of 10% of the allotted amount shall be imposed on the contractor and the work shall be got executed departmentally or through any other agency at the risk and extra cost of the above contractor. Besides action under rules for black listing of the contractor shall be taken up by the Department.

C. Earnest Money

The Bank Gurantory Bid Security BG No. 0135PBG2205003 Dt: 11/05/2022 for Rs. 2.93 lacs J&K Bank Branch Qasba Hyhama (Rupees Two lacs and Ninety three thousands Only) Pledged to the {District Superintending Engineer Hydraulic Circle Kupwara H/Q: Handwara} shall be retained in this Office till successful completion of the above work after the expiry of the defect liability period.

D. Advance payment

No mobilization advance or advance payment shall be made to the allottee (contractor).


E General

All other conditions as laid down in E-NIT 09 of 2022-23 dated. 10.05.2022 issued under endorsement No: PHEDK/608-19 Dt: 30/05/2022 from Executive Engineer PHE Division Kupwara shall be binding on the contractor.

No: DSE/HH/DB/

Dated: - 01/07/2023


22-27


District Superintending Engineer,
Hydraulic Circle Kupwara
HQ Handwara

Copy to the: -

1. Chief Engineer Kashmir PHE Department Srinagar for favour of information.
2. District Development Commissioner (Chairman DJJM) Kupwara for favour of information.
3. District Nodal Officer WAPCOS Ltd. (Distt. Kupwara) for information.
4. Executive Engineer PHE Division Kupwara for information and necessary action.
5. Head Draftsman Circle Office Handwara.
6. Office Copy.

Allotment No:- 22/DSE/HH/DB of 2022-23




HD

TO

DSE

