



# OFFICE OF THE DISTRICT SUPERINTENDING ENGINEER,



## HYDRAULIC CIRCLE KUPWARA -- HEADQUARTER HANDWARA

Fax/Phone: 01955262005 \*\*\*\*\*00\*\*\*\*\* email: sehydkupwara@gmail.com

NAME: M/S NEW WANI & BROTHERS

PROP: Nazir Ahmad Wani

S/O: Ab.Waheed Wani.

R/O: Shumanag Kupwara .

Registration No: 929/AAAY(civil/sanitary)/CE/KCC/PDC/2009-10.

GSTIN NO: 01ACBPW3482F2ZR.

ALLOTMENT ORDER NO: .....40.....-DSE/HH/DB OF 2023-24 DT: 19/07/2023

Sub: Construction of 4 No. Service Reservoirs having Capacity 0.70 Lac, 0.45 Lac, 0.10 Lac Gallons, Sump at Nagbal, 2 No. Pre Settling Tanks, 6 No. Sluice Chambers, Chain Link fencing for WSS Sogam Chandigam (JJM).

Ref: -

- Minutes of the 8th meeting of Technical Appraisal Committee held on 08-02.2022, minutes issued thereof Vide CE/PHE/DB/44620-41 dated. 12-03.2022.
- Accord of Administrative Approval vide Chief Engineer Kashmir PHE Deptt. Srinagar's Order No. CE/PHE/DB/JJM/346 of 02/2023 dated. 21-02-2023
- Revised District Action Plan of District Kupwara by DJJM vide No. DDCK/Plg/JJM/12709-20 dated. 03.02.2023
- Govt. Order No. 19-JK (JSD) of 2022 dated. 04.02.2022.
- Technical Sanction Order No. CE/PHE/DB/845 of 02/2023 dated. 23/02/2023.
- District Development Commissioner Kupwara's Authorization No. DDCK/Plg/JJM/7152-72 Dated: 07/09/2022 .
- Executive Engineer PHE Division Kupwara Letter(Recommendation) No:-PHE/KUP/997-98. Dated 10/06/2023

Advertised cost: - Rs : 219.10 Lacs (original cost of project=Rs.1168.93 Lacs)

Cost as per revised BOQ 183.40 Lacs (Revised Cost of Project=Rs.951 Lacs)

Allotted cost: - Rs : 184.89 Lacs

(Rupees One Crore Eighty Four Lacs & Eighty Nine thousand Rupees Only)

For and on behalf of the Lt. Governor of Jammu and Kashmir UT, contract for Construction of 4 No. Service Reservoirs having Capacity 0.70 Lac, 0.45 Lac, 0.10 Lac Gallons, Sump at Nagbal, 2 No. Pre Settling Tanks, 6 No. Sluice Chambers, Chain Link fencing for WSS Sogam Chandigam (JJM). is hereby fixed with you on the accepted rates by you as shown in the enclosed Annexure of this allotment. The total cost of the work will be of the order of Rs : 184.87 Lacs (Rupees One Crore Eighty Four Lacs & Eighty Nine thousand Rupees Only) on the terms and conditions as laid down in E- NIT No: 22 Of 2022-23. issued under endorsement No. PHEDK/1525-36 Dt: 16/07/2022 from Executive Engineer PHE Division Kupwara shall be binding on the contractor.

Sl. No.	Item Description	Quantity	Units	Estimated Rate	AMOUNT
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: (1 Mtr from cutting edge)				
i	All sorts of soil	263.27	CUM	436	114786.00



TO

DSE

2	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m <sup>2</sup> on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge				0.00
i	All sorts of soil	1773.73	CUM	539.4	956750.00
ii	Ordinary rock	720.60	CUM	855.7	616617.00
3	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material				
i	a) All sorts of soil	443.93	CUM	81.7	36269.00
ii	b) Ordinary Rock	190.26	CUM	146.5	27873.00
4	Providing of Laying of dry stone soling hand packed on level	104.83	CUM	816.4	85583.00
5	Centering and shuttering including strutting, propping etc, and removal of form for.				0.00
i	Foundations, footings, bases of columns etc for mass concrete.	826.19	SQM	262.3	216710.00
ii	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	1708.32	SQM	573.9	980405.00
iii	Suspended floors, roofs, landings, balconies and access platform.	43.88	SQM	635.6	27890.00
6	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	63.75	SQM	502.9	32060.00
i	Edges	17.00	RM	242.3	4119.00
ii	Arches, domes, vaults upto 6 m span	200.66	SQM	2086.8	418737.00
iii	Extra for arches, domes, vaults exceeding 6 m span	233.72	SQM	1007.5	235473.00
7	Extra for shuttering in Circular work 20% of basic respective centering and shuttering items.				0.00
i	Foundation	54.48	SQM	52.5	2860.00
ii	Walls	963.18	SQM	114.8	110573.00
ii	Beams	75.41	SQM	100.6	7586.00
8	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with				
i	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	95.91	CUM	4861.8	466295.00
ii	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	182.25	CUM	5437.7	991021.00
iii	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	11.39	CUM	6465.2	73639.00
9	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level				0.00

HD

TO

DSE



i	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	146.75	CUM	7798.8	1144474.00
ii	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	11.25	CUM	6978.7	78510.00
10	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement.				0.00
i	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	180.91	CUM	9408.1	1702019.00
11	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with				0.00
i	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	24.18	CUM	9849.4	238158.00
12	Reinforced cement concrete work in arches, archribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level level including curing but excluding the cost of centering, shuttering finishing and reinforcement with:				0.00
ii	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	35.44	CUM	10404.5	347926.00
13	Reinforcement for R.C.C work including straightening cutting, bending, placing in position and binding all complete, Thermo-Mechanically treated bars.	38293.42	KG	95.1	3641664.00
14	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1500.00	KG	99.3	148950.00
15	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete Welded	8812.39	KG	111.4	981700.00
16	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using MS angles 40 x 40 x 6 mm for diagonal braces	14.46	SQM	5899	85300.00
17	12mm Cement plaster of mix:				0.00
i	1 : 4 ( 1 cement : 4 fine sand)	1695.78	SQM	286.1	485163.00

TO

DSE

HD

18	12mm Cement plaster finished with a floating coat of neat cement of mix:				0.00
i	1 : 3 ( 1 cement : 3 fine sand)	1700.11	SQM	378.1	642812.00
19	Providing and incorporating PGI Sheet strip, 0.63mm thick, 200mm wide at construction joints for providing water seal.	484.00	RM	90	43560.00
21	Demolishing stone rubble masonry manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge: In cement mortar	55.98	CUM	1583.1	88622.00
22	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and lift upto 1.5m.	2202.62	CUM	198.7	437661.00
23	P/F of double flanges CI sluice valves conforming to IS 14846 of 1984 read with upto date amendments, PN-16 rating lift incld. cost of nuts, bolts, RI cloth incld. all sorts of carriages upto site of work complete job incld. cost of pedestals, extension rods upto working platform and handles of approved manufacture like Zoloto, Kirloskar or like				0.00
i	150mm dia	2.00	No.	26720	53440.00
ii	125mm dia	5.00	No.	21000	105000.00
iii	100mm dia	6.00	No.	17210	103260.00
iv	80mm dia	3.00	No.	14058	42174.00
v	65mm dia	1.00	No.	9500	9500.00
24	P/F of MS fabricated boxes for safeguard of sluice valves size 0.50x0.50x0.60 using 40x40x5 angle iron & 3mm thick MS sheet complete job incl, embedding in cement concrete work	9.00	No.	12000	108000.00
25	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-incharge. (Made of G.I. wire of dia 4 mm)	734.25	SQM	733.5	538572.00
26	Carriage of materials from source upto nearest dumping site incl, loading, unloading and stacking (subject to actual)				0.00
i	Soling by an avg lead of 10 Kms	104.83	CUM	330.4	34635.00
ii	40mm course aggregate for av lead of 30kms	86.81	CUM	545.3	47337.00
iii	20mm course aggregate for avg lead of 30kms	531.15	CUM	501.7	266478.00
iv	Sand for avg lead of 50 km	411.76	CUM	700.4	288397.00
v	Cement by an average lead of 20 km	271.9	MT	357.6	97231.00
vi	TMT Steel by an average lead of 20 km	38.29	MT	357.6	13693.00

ly HD

TO

DSE



27	Carriage of materials by Manual Labours from Dumping Site Upto working site incl, loading, unloading and stacking for an average lead of 750 meters ( Subject to Actual at site)				0.00
i	Soling				
ii	40mm course aggregate	104.83	CUM	999.6	104788.00
iii	20mm course aggregate	86.81	CUM	918.6	79743.00
iv	sand	531.15	CUM	849.7	451318.00
v	Cement	411.76	CUM	849.7	349873.00
vi	TMT Steel	271.9	MT	468.2	127304.00
		38.29	MT	371.3	14217.00
<b>Total</b>					<b>18306725.00</b>
ADD (+1.00%) on all above items					Rs. 183067.00 Lacs
<b>Grand Total</b>					<b>Rs.18489792.00Lacs</b>

Head  
Draftsman

*[Signature]*

Technical Officer

*[Signature]*

District Superintending Engineer

*[Signature]*

**A Terms and Conditions: -**

1. The contractor shall draw agreement with the Superintending Engineer Hyd. Circle Kupwara H.Q Handwara within 07 days from the date of issue of allotment order and failing to execute such an agreement in time shall not however prevent this contract being enforced against the contractor and the conditions laid down in the NIT shall hold good even before drawl of formal agreement.
2. The work shall have to be executed strictly in accordance with the approved proposals and specifications of the sanctioned estimates.
3. The date of start of work shall be reckoned from 07 days after issuance of allotment.
4. It shall be mandatory for the executing agency/ contractor to ensure safe and adequate supply of electricity required for all the workmen skilled/ unskilled deployed at site of work.
5. Suitable arrangements for supply of portable water at site of work for all the workmen skilled/ unskilled be made by the agency/ contractor just before the virtual start of execution at site.
6. Arrangements for sufficient sanitation facility at site be ensured by the executing agency / contractor for all the workmen to be mobilized at site besides, separate toilet facilities be provided for Female workers at the site of work.
7. Insurance cover as admissible under rules shall be provided to all workers/ skilled/unskilled deployed at site and the necessary premiums shall be borne by the executing agency/ contractor itself.
8. Payments are subject to the recommendation of the third party verification agency (M/s. WAPCOS Ltd).

HD

TO

DSE



**B. Time of completion**

The works shall be completed within a period of (150 Working Days) after the date of issue of allotment. In the event of the contractor failing / declining / neglecting / delay in the execution of the work, penalty to the extent of 10% of the allotted amount shall be imposed on the contractor and the work shall be got executed departmentally or through any other agency at the risk and extra cost of the above contractor. Besides action under rules for black listing of the contractor shall be taken up by the Department.

**C. Earnest Money**

The CDR bearing No.: 3137417 for Rs.443000 (Four lacs Forty Three Hundred only) of JK Bank Branch Hyhama pledged to Executive Engineer PHE Division Kupwara has been submitted.

**D. Performance security.** Performance security equivalent 03% of the value of the contract Rs.657700/- valid in accordance with bid condition have been furnished by you in shape of BG bearing No.:01171FBG2209001 OF JK Bank Branch Kralpora shall be retained in this office till the successful completion of the defect liability as period laid in NIT.



**E. Advance payment**

No mobilization advance or advance payment shall be made to the allottee (contractor).

**F. General**

All other conditions as laid down in E- NIT No: 07 of 2022-2023 issued under endorsement No. PHEDK/294-304 Dt: 28/04/2022 from Executive Engineer PHE Division Kupwara shall be binding on the contractor.

No: DSE/HH/DB/ 1463-67  
Dated: - 10 / 07 / 2023

  
**District Superintending Engineer,**  
Hydraulic Circle Kupwara  
HQ Handwara 

**Copy to the: -**

1. Chief Engineer Kashmir PHE Department Srinagar for favour of information.
2. District Development Commissioner (Chairman DJJM) Handwara for favour of information.
3. District Nodal Officer WAPCOS Ltd. (Distt. Kupwara) for information.
4. Executive Engineer PHE Division Kupwara for information and necessary action.
5. Office Copy.

TO

DSE

