

Government of Jammu and Kashmir
16
OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 631-34
 Dated. 01-05-2021

Contractor,
Ahmad Naik,
S/o. Ghulam Ahmad Naik,
R/o Zagigam, Pulwama
Regd. No. 24/AAAY/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Armulla Gadbugh by way of Providing & laying of GI pipes, construction of head works/intake sump, including revamping of SSFP including installation of 119 No. FHTC's for Armulla Gadbugh including maintenance for a period of three years which includes DLP of 12 months.(JJM).

Ref:- E-NIT S.No. 118/PHEP of 2020-21, job No. (1), Circulated vide this office No. PHEP/ 6345 - 55
Dated:- 13-02-2021

.....
Advertised Amount of work: ₹ 85,88,000.00
Alloted Amount of work: ₹ 81,08,000.00
Rupees Eighty One Lakh(s) Eight Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earth work in excavation by manual means in trenches for foundations ,drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts ,wells ,cesspits, and the like not exceeding 10sqm on plan ,including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	1822.14	Cum	436.00	300.00	Rupees Three Hundred Only
2.00	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil	39.69	Cum	81.65	65.00	Rupees Sixty Five Only
3.00	Providing and banking excavated or stacked material : All kinds of soil dressing and ramming all complete	23.21	Cum	612.50	600.00	Rupees Six Hundred Only
4.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 mix (1 cement :4 coarse sand :8 graded stone aggregate 40 mm nominal size)	16.32	Cum	4419.85	4100.00	Rupees Four Thousand One Hundred Only
5.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	15.87	Cum	7091.60	6800.00	Rupees Six Thousand Eight Hundred Only
6.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	25.21	Cum	8552.85	8200.00	Rupees Eight Thousand Two Hundred Only
7.00	Centring shuttering including strutting , propping etc. and removal of form work for					
7.10	Foundation footings , bases for columns	17.97	Sqm	262.30	250.00	Rupees Two Hundred Fifty Only
7.20	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	252.20	Sqm	573.85	500.00	Rupees Five Hundred Only
8.00	Steel reinforcement for RCC work including straightening, cutting , bending , placing in position and binding all complete upto plinth level thermo -Mechanically -Treated bars of grade Fe-500D or more	3286.40	Kg	79.25	80.00	Rupees Eighty Only
9.00	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	252.20	Sqm	260.05	190.00	Rupees One Hundred Ninety Only
10.00	Pumping out water caused by springs, tidal or river seepage, broken water mains or drains and the like.	244.24	KL	155.55	120.00	Rupees One Hundred Twenty Only
11.00	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	310.00	Kg	57.90	40.00	Rupees Forty Only
12.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)					
12.10	50 mm dia G.I pipes	3000.00	Mtr		477.50	Rupees Four Hundred Seventy Seven And Paise Fifty Only
12.20	40 mm dia G.I pipes	600.00	Mtr		386.06	Rupees Three Hundred Eighty Six And Paise Five Only
12.30	25 mm dia G.I pipes	1500.00	Mtr		249.00	Rupees Two Hundred Forty Nine Only
12.40	20 mm dia G.I pipes	1500.00	Mtr		182.55	Rupees One Hundred Eighty Two And Paise Sixty Five Only
12.50	15 mm dia G.I pipes	1428.00	Mtr		144.40	Rupees One Hundred Forty Four And Paise Forty Only

(Handwritten signature)

Retrofitting of Water Supply Scheme Armulla Gadbugh by way of Providing & laying of GI pipes, construction of head works/intake sump, including revamping of SSFP including installation of 119 No. FHTC's for Armulla Gadbugh including maintenance for a period of three years which includes DLP of 12 months.(JJM).

Providing and laying S&S Centrifugally Cast (Spun)/ Ductile Iron Pipes conforming to IS : 8329						
13.10	150 mm dia Ductile Iron Class K - 7 Pipes	500.00	Mtr		1581.25	Rupees One Thousand Five Hundred Eighty One And Paise Twenty Five Only
13.20	100 mm dia Ductile Iron Class K - 7 Pipes	2000.00	Mtr		1108.15	Rupees One Thousand One Hundred Eight And Paise Fifteen Only
14.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete					
14.10	(a) 25 to 40 mm nominal bore	20.00	No	666.25	500.00	Rupees Five Hundred Only
14.20	(b) Above 40 mm nominal bore	10.00	No	1268.75	800.00	Rupees Eight Hundred Only
15.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	1409.40	Cum	198.70	170.00	Rupees One Hundred Seventy Only
16.00	Providing fixing double flanges C.I sluice valves of standard quality Kirlosker /vage make conforming to IS 780 of 1984 read with upto date amendments standard mark ISI make PN-1 including cost of nuts bolts IR cloth including all sorts of carriage upto site of work complete job including cost of pedestals and handles (to be paid as per actual details with supporting vouchers duly verified by AEE concern)					
16.10	(a) 100 mm dia sluice valve	2.00	No		16000.00	Rupees Sixteen Thousand Only
16.20	(b) 80 mm dia sluice valve	2.00	No		12000.00	Rupees Twelve Thousand Only
16.30	(c) 65 mm dia sluice valve	3.00	No		9000.00	Rupees Nine Thousand Only
17.00	Providing ,fixing supplying 150mm dia NRV of kirlosker /vage make including supplying of spun yarn , wooden plugs , nuts , bolts , washers , flanges , welding , earthwork and refilling if required at site including all sorts of carriages (to be paid as per actual details with supporting vouchers duly verified by AEE concern)	4.00	No		8000.00	Rupees Eight Thousand Only
18.00	Clearance of silt from RSFP/PST / clear water sump including disposal of silt outside the premises all leads lifts complete (to be paid as per details/ measurements)	5537.50	Cft		10.00	Rupees Ten Only
19.00	Removing of filter media mixed with silt including disposal of silt outside the premises all leads lifts complete (to be paid as per details/ measurements)	4000.00	Cft		6.00	Rupees Five Only
20.00	Washing of filter media after taking out from plant including removing of unserviceable material outside the premises complete (to be paid as per details/ measurements)	2800.00	Cft		6.00	Rupees Six Only
21.00	Relaying of filter media after washing into plant in layers all complete (to be paid as per details/ measurements)	2800.00	Cft		7.00	Rupees Seven Only
22.00	Providing , laying of filter media from Gandarbal of various grades including all carriages leads lifts and placing in layers into plant complete job (to be paid as per details/ measurements)	33.96	Cum		7000.00	Rupees Seven Thousand Only
23.00	Applying priming coats with primer of approved brand and manufacture having low VOC (Volatile Organic Compound) content. With ready mixed red oxide zinc chromatic on steel / iron works having VOC content less than 250 grams/ liter	384.30	Sqm	59.50	62.00	Rupees Sixty Two Only
24.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	384.30	Sqm	121.95	120.00	Rupees One Hundred Twenty Only
25.00	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth, Lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge. All kinds of soil :	3600.00	Sqm	83.45	75.00	Rupees Seventy Five Only
26.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	9.00	Cum	5877.45	5500.00	Rupees Five Thousand Five Hundred Only
27.00	Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete					
27.10	Sand and Bajri avg lead 15km	101.78	Cum	297.02	300.00	Rupees Three Hundred Only
27.20	Cement and steel avg lead 15km	29.63	M.T.	264.04	265.00	Rupees Two Hundred Sixty Five Only
27.30	Stone solling avg lead 15km	23.21	Cum	349.39	250.00	Rupees Two Hundred Fifty Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (06) months and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- All other terms and conditions will remain same as per the original agreement form No. 25-double, Form FC – 33 and detailed E-NIT.

Checked
Head Draftsman

Tech. Officer

Executive Engineer,
ISD (PHE) Div. Pulwama