

No. PHEP/.....623-26
Dated. 01-05-2021

Mr. Washir Ahmad Naik, ✓
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zagigam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Bon Koil by way of providing, laying & fitting of GI pipes, construction of chain link fencing including electrical and mechanical works including installation of 132 No. FHTC's for Bon Koil including maintenance for a period of three years which includes DLP of 12 months.(JMM). ✓

Ref:- E-NIT S.No. 113/PHEP/Fresh of 2020-21, job No. (1), Circulated vide this office No. PHEP/6172-82 Dated:- 09-02-2021 followed by Ex. Engineer, PHE (Mech) Divn, South Awantipora's No. MDSA/4092-93 dated. 30-03-2021.

Advertised Amount of work: ₹ 25,23,000.00 ✓
Alloted Amount of work: ₹ 23,29,600.00 ✓

Rupees Twenty Three Lakh(s) Twenty Nine Thousand Six Hundred Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	455.70 ✓	Cum	240.45	280.00 ✓	Rupees Two Hundred Eighty Only
2.00	Providing laying stone soling hand packed including cost of stone.	5.40 ✓	Cum	327.05	300.00 ✓	Rupees Five Hundred Only
3.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work upto plinth level mix 1:3:6(1 cement : 3coarse sand 6 graded stone aggregate 40mm nominal size crushed)	21.60 ✓	Cum	3565.75	4100.00 ✓	Rupees Four Thousand One Hundred Only
4.00	Structural steel work welded in built up sections, trusses and framed work, including cutting, hosting, fixing, in position and applying a priming coat of approved steel primer all complete .	1630.06 ✓	Kg	80.80	92.00 ✓	Rupees Ninety Two Only
5.00	Providing and fixing GI chain-link fencing (fabric fencing) of required width in mesh size 50x50mm including strengthening with 2mm dia wire or nuts bolts washer are required complete as per direction of engineer-in-charge (made of GI Wire of dia 4mm) .	292.80 ✓	Sqm	571.00	700.00 ✓	Rupees Seven Hundred Only
6.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.					
6.10	65mm dia	480.00 ✓	Mtr	RQC	625.00 ✓	Rupees Six Hundred Twenty Five Only
6.20	50mm dia	500.00 ✓	Mtr	RQC	475.00 ✓	Rupees Four Hundred Seventy Five Only
6.30	40mm dia	450.00 ✓	Mtr	RQC	385.00 ✓	Rupees Three Hundred Eighty Five Only
6.40	25mm dia	490.00 ✓	Mtr	RQC	249.00 ✓	Rupees Two Hundred Forty Nine Only
6.50	20mm dia	365.00 ✓	Mtr	RQC	180.00 ✓	Rupees One Hundred Eighty Only
6.60	15mm dia	1000.00 ✓	Mtr	RQC	143.00 ✓	Rupees One Hundred Forty Three Only
7.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.					
7.10	25mm to 40mm nominal bore	16.00 ✓	No	403.65	600.00 ✓	Rupees Six Hundred Only
7.20	above 40mm nominal bore	3.00 ✓	No	1022.15	1000.00 ✓	Rupees One Thousand Only
8.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	380.97 ✓	Cum	102.20	120.00 ✓	Rupees One Hundred Twenty Only
9.00	Carriage of different material from source up to dumping site of work by Mech. Transport incl. loading, unloading and stacking complete					
9.10	Stone soling avg lead 10 km	5.40 ✓	Cum	202.11	250.00 ✓	Rupees Two Hundred Fifty Only
9.20	Sand Bajri avg lead 20 km	29.16 ✓	Cum	265.13	300.00 ✓	Rupees Three Hundred Only
9.30	Cement and steel avg lead 05 km	6.38 ✓	M.T.	112.96	120.00 ✓	Rupees One Hundred Twenty Only
10.00	Providing and installation of electrical and mechanical works complete job					
10.01	Supply, Installation, Testing & Commissioning of Submersible Pumping Equipment (for full specifications refer S. No. (1) of Annexure A in Tender Document)	3.00 ✓	Job	RQC	60000.00 ✓	Rupees Sixty Thousand Only
10.02	Fabrication, Providing and fitting of Modular control panel with appropriate size fabricated out of 16SWG sheet having required openings / vents and protection Class: 1P 55 & fitted (for full specifications refer S. No. (2) of Annexure A in Tender Document)	1.00 ✓	Job	RQC	100000.00 ✓	Rupees One Lakh(s) Only

Retrofitting of Water Supply Scheme Bon Koil by way of providing, laying & fitting of GI pipes, construction of chain link fencing including electrical and mechanical works including installation of 132 No. FHTC's for Bon Koil including maintenance for a period of three years which includes DLP of 12 months.(JJM).

10.03	Control Valves(Sluice Valves) Providing, Fitting of 100 mm, PN 1.6/16, Ductile Iron double flanged, soft seated glandless gate/ sluice valve. Body and bonnet of ductile cast iron, wedge with fully vulcanized EPDM rubber(Approved for drinking water) and NBR seal. Gate /Sluice valve shall be compatible for buried application and shall be safe to install in both horizontal and vertical positions It shall have electrostatic epoxy coating inside and outside approved for drinking water the valve shall be supplied along with hand wheel.The job includes providing and fitting of 02 No. M.S Flanges perfectly adaptable to the inbuilt flanges of the valve, which shall be fitted with delivery mains of the pumping unit. Cost on account of Nuts, bolts, gaskets, etc required for the job is included in the scope of work. Make VAG/AVK/SIGMAFLOW/ TALIS	1.00	Job	RQC	18000.00	Rupees Eighteen Thousand Only
10.04	Providing, fitting, testing and commissioning of 50 KVA voltage controllers for above WSS (for full specifications refer S. No. (4) of Annexure A in Tender Document)	2.00	Job	RQC	90000.00	Rupees Ninety Thousand Only
10.05	P/F of 16mm Sq. Submersible cable conforming to IS: 694 (part 1st) – 1964 & IS: 694 (Part 2nd) – 1964 of L&T make for inter connections of electrical gadgets.	50.00	Mtr	RQC	300.00	Rupees Three Hundred Only
10.06	Supply, Installation of 3-ton capacity chain pulley blocks (for full specifications refer S. No. (6) of Annexure A in Tender Document)	1.00	Job	RQC	30000.00	Rupees Thirty Thousand Only
10.07	Providing, fitting, testing and commissioning of (L.T) XLPE 70 mm ² Armored Al. Cable of 1.1 KV grade conforming to IS: 7089 part 1st (for full specifications refer S. No. (7) of Annexure A in Tender Document)	30.00	Mtr	RQC	270.00	Rupees Two Hundred Seventy Only
10.08	Providing, fitting of MS clamps capable of holding 80 mm dia. GI-B-class Pipe. The clamp shall be fabricated out of 12mm thick MS plate with adequate flange length and flanges bored with 5/8" holes and provided with suitable size nuts and bolts	2.00	Job	RQC	1500.00	Rupees One Thousand Five Hundred Only
10.09	Supply, Providing of nuts, bolts-10 Kgs & Washers 3",4" -2 Dozen Each.	1.00	Job	RQC	1000.00	Rupees One Thousand Only
10.10	Providing, erection of 9 m long M S Tubular poles of designation 410 SP-33-2 nos. and fitted with (450x450) mm size M.S plate at the bottom. The job also includes spiral earthing, painting of poles in silver colour, grouting of poles in CC blocks of (M-20 mix). The job is also inclusive of providing and fitting of pin insulators as per site requirement.	2.00	Job	RQC	12000.00	Rupees Twelve Thousand Only
10.11	Providing, Fitting of 9' long ,75x40 x5mm size ISMC channels for holding safety devices.	6.00	Job	RQC	1900.00	Rupees One Thousand Nine Hundred Only
10.12	Providing, laying, testing and commissioning of 0.05 ACSR conductor to serve as HT line from HT tapping source to substation.	30.00	Mtr	RQC	55.00	Rupees Fifty Five Only
10.13	P/F of lightning arrestor set station Type for 11 KV line job.	1.00	Job	RQC	6000.00	Rupees Six Thousand Only
10.14	P/F of heavy duty Go link set.	1.00	Job	RQC	7000.00	Rupees Seven Thousand Only
10.15	P/F of drop out set for 11 KV line job.	1.00	Job	RQC	4500.00	Rupees Four Thousand Five Hundred Only
10.16	P/F of 200 ampere capacity AI – thimbles including crimping to intake and outtake connections.	4.00	No	RQC	80.00	Rupees Eighty Only
10.17	Providing, Fitting of Transformer belt fabricated out of ISA 40x40x5mm thick two pieces to be fitted with nuts & bolts	1.00	Job	RQC	1200.00	Rupees One Thousand Two Hundred Only
10.18	Providing/Fitting of lighting and fan points in 1.5 mm multi strand single core cable (Havells) make carried through 1 dia. PVC pipe junction box, bends, clips and fitted with 5-Amp plano type SSK switch on Hylum plate (8 nos.) etc. (for full specifications refer S. No. (18) of Annexure A in Tender Document)	6.00	Job	RQC	1500.00	Rupees One Thousand Five Hundred Only
10.19	Providing of tool kit comprising of Flat Spanner 14-27 No (07 Pieces), Ring spanner set 14-27 No (07 pieces), 10" screw Driver, the tools shall be of Tap aria /Ambika make Provided in canvas bag. The Job also Includes Providing of Chargeable lantern of Andsite make 01no, 15 ltrs.	1.00	Job	RQC	15000.00	Rupees Fifteen Thousand Only
10.20	Supply & installation of 0.850 Kva Microtek /Luminous make inverter along with 12 volts 150 AH Exide/Luminous make battery complete with leads terminals & thimbles. The job also includes all the charges on account of carriage, wiring and arrangement of skilled labour for installation of inverter.	1.00	Job	RQC	30000.00	Rupees Thirty Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (30) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked
Head Draftsman

Tech. Officer
Executive Engineer,
JSD (PHE) Div. Pulwama

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Tahab for information and necessary action.
- 4- File Concerned.