

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 134 of 02/2023

M/S : Mohammad Maqbool Mir
S/O : Mohammad Dilawar Mir
R/O : Gantamulla Bala Tehsil Narvaw Distt. Baramulla
Registration No. : 259-BK/SE-PWD/BEE/2005-06
TIN No./GST No:- : 01ANCPM4687Q1ZI

Name of work : Construction of Water Supply Scheme Gantamulla Payeen by way of Construction of Intake Chambers/protection bunds, laying and fitting of GI Pipes and other allied works (for providing 100% FHTC) under JJM

eNIT No. : 45 /Hyd/Uri of 2022-23 TENDER ID 2022_IFC_202344_34
Your Tender Received in response to : eNIT No:45/Hyd/Uri_of_2022-23 Dated: 11/01/2023 issued under endorsement No:- HDU/CC-02/4813-23 Dated: 11/01/2023 (S. No: 34) Tender ID : 2022_IFC_202344_34

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/2022/1214-44 Dated: 24-05-2022.
(viii) This Office Letter No: HDU/CC-02/5293-94 dated:- 07/02/2023
(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HO Sopore authorization No: SE/Hyd/DB/14646-58 Dated:- 09/02/2023

Ref: to AAA : Accorded vide Order No. 50/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022. issued under Endorsement No:- SE/HYD/DB/6462-67 Dated:- 26/08/2022.

Ref: to Tech. Sanction : Accorded vide Order No.CE/PHE/DB/548 of 09/2022 Dated:- 10/09/2022. issued under Endorsement No:- CE/PHE/DB/21476-80 Dated:- 10/09/2022.

Advertisement cost : Rs:45.29Lacs
Allotted cost : **₹ 4710213.49** Rupees Forty Seven Lakh(s) Ten Thousand Two Hundred Thirteen And Paise Forty Nine Only

Time of completion : 120-days
M.H. of Account : (JJM)
Ref. To CDR No. : CDR NO: 3434124 Dated: 19/01/2023 Amount: ₹ 90,580.00
Name of the Bank : J&K Bank Ltd. Branch Office KB Adda Baramulla

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Conditions:-

- Completion is essence of the contract.
 Work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall not to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
 Performance security equivalent to 05% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after deposition of 03% performance security of the value of the contract
 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
 Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.


Checked by

Head Division
 NO: HDR/CC-01/5744-56

DATED: 27-2-2023

Copy to the:

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/14646-58 Dated:- 09/02/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.



 Technical Officer to
 Executive Engineer
 Hydraulic Division Uri


 Executive Engineer
 Hydraulic Division Uri

Annexure "A" to the Allotment Order No. 134 of 02/2023

Construction of Water Supply Scheme Gantamulla Payeen by way of Construction of Intake
 Bunds/protection bunds, laying and fitting of GI Pipes and other allied works (for providing 100%
 FHTC) under JJM


	Particulars	Qty	Unit	Rate	Amount
1	E/W in excavation by manual means in trenches for foundations, drains, pipes, cables etc (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth within 1km from cutting edge, disposed earth to be leveled and neatly dressed :				
1.1	In all kinds of soils (Trenches)	3783.500	Cum	436.000	1649606.00
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	3376.890	Cum	198.700	670988.04
3	Providing and laying stone soling 2nd class	3.110	Cum	616.400	1917.00
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	1.960	Cum	4861.835	9529.20
5	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	2.806	Cum	7800.760	21888.93
6	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	3.723	Cum	9408.135	35026.49
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	0.599	Cum	9849.345	5899.76
8	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	34.840	Cum	2500.000	87100.00
9	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
9.1	Foundations, footings, bases of columns	4.740	Sqm	262.300	1243.30
9.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	43.240	Sqm	573.850	24813.27
9.3	Suspended floors, roofs, landings, balconies and access platform.	3.813	Sqm	635.600	2423.54
10	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	35.190	Sqm	357.995	12597.84
11	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	200.000	Kg	67.650	13530.00



 HD.



Particulars		Qty	Unit	Rate	Amount
	Structural steel work welded in built up sections, trusses and other steel work, including cutting, hoisting, fixing in position and painting a priming coat of approved steel primer all complete.	1050.660	Kg	102.140	107314.41
	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	872.720	Kg	87.175	76079.37
14	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	76.740	Kg	102.140	7838.22
15	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
15.1	100mm dia	2.000	Nos	7500.000	15000.00
16	Providing and fixing of (8mm-thick) MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carriages upto site of work complete job.				0.00
16.1	100mm dia	91.000	Joints	1300.000	118300.00
16.2	80mm dia	191.000	Joints	1200.000	229200.00
16.3	65mm dia	109.000	Joints	1100.000	119900.00
16.4	50mm dia	109.000	Joints	1000.000	109000.00
16.5	40mm dia	127.000	Joints	900.000	114300.00
17	Laying and fitting of GI Pipes excluding trenching and refilling etc.(Including providing and fixing of Pipe Specials/fittings				0.00
17.1	100 mm dia GI pipes	800.000	Mtr	107.700	86160.00
17.2	80 mm dia GI pipes	4000.000	Mtr	73.050	292200.00
17.3	65 mm dia GI pipes	2000.000	Mtr	73.050	146100.00
17.4	50 mm dia GI pipes	1600.000	Mtr	40.800	65280.00
17.5	40 mm dia GI pipes	2200.000	Mtr	40.800	89760.00
17.6	25 mm dia GI pipes	2000.000	Mtr	30.650	61300.00
17.7	20 mm dia GI pipes	3000.000	Mtr	20.250	60750.00
17.8	15mm dia GI pipes	1000.000	Mtr	20.250	20250.00
18	Making connection of GI distribution branch with GI main of following sizes, by P/F of tees, incld. cutting and threading the pipe etc. complete				0.00
18.1	25 to 40 mm dia nominal bore	131.000	No	666.250	87278.75
18.2	Above 40 mm nominal bore	5.000	No	1268.750	6343.75
19	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
19.1	Cement and Steel (15Kms)	11.130	Mton	303.646	3379.58
19.2	Pipes (15-Kms)	89.990	Mton	303.646	27325.10
19.3	Sand. 20Kms)	4.523	Cum	402.293	1819.57
19.4	Agg. 20mm (60Kms)	6.410	Cum	799.733	5126.29
19.5	Agg. 40mm (60Kms)	36.600	Cum	869.239	31814.15
19.6	Stone Soling (07-Kms)	45.380	Cum	277.770	12605.20


 H.D. T.O.



Particulars	Qty	Unit	Rate	Amount
Wage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and site stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
20.1 Cement (500Mtrs)	3.520	Mton	282.095	992.97
20.2 Steel (500Mtrs)	0.871	Mton	605.958	527.79
20.3 Pipes (500Mtrs)	89.990	Mton	355.690	32008.54
20.4 Sand. 500Mtrs)	4.523	Cum	621.207	2809.72
20.5 Agg. 20mm (500Mtrs)	6.410	Cum	621.210	3981.96
20.6 Agg. 40mm (500Mtrs)	36.600	Cum	671.554	24578.88
20.7 Stone Soling (500Mtrs)	45.380	Cum	730.802	33163.79

Total	4529051.43
--------------	-------------------

Excess (+)	4.00%
-------------------	--------------

4710213.489

Rupees Forty Seven Lakh(s) Ten Thousand Two Hundred Thirteen And Paise Forty Nine Only

Checked by

Head of Man

21/11/20
Jey

Executive Engineer
Hydraulic Division Uri