

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI  
email: urihydraulic@gmail.com

Allotment Order No. 80 of 07/2023

M/S : Mohammad Sultan Najar  
S/O : Abdul Rehman Najar  
R/O : Limber Uri  
Registration No. : 62-BK/SE-PWD/BEE/1997-98  
TIN No./GST No:- : 01ASKPN5156A1Z6

Name of work : Construction of Water Supply Scheme Limber A and B by way of Providing of Chain Link fencing, Construction of Intake Chambers, Protection Bunds, and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM

eNIT No. : 49 /Hyd/Uri of 2022-23 TENDER ID 2023\_IFC\_204393\_19  
Your Tender Received in response to : eNIT No:49/Hyd/Uri\_of\_2022-23 Dated: 11/01/2023 issued under endorsement No:- HDU/CC-02/5279-89 Dated: 07/02/2023 (S. No: 19) Tender ID : 2023\_IFC\_204393\_19

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.  
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.  
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.  
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.  
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).  
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.  
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/2022/1214-44 Dated: 24-05-2022.  
(viii) This Office Letter No: HDU/CC-02/5858-59 Dated:- 02/03/2023  
(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/15662-74 Dated:- 07/03/2023

LOI issued under No:- : NIT NO. 49/6043-44 Dated:- 08/03/2023  
Ref: to AAA : Accorded vide Order No.CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022  
Ref: to Tech. Sanction : Accorded vide Order No.CE/PHE/DB/182 of 08/2022 Dated:- 31/08/2022  
Advertisement cost : Rs:46.13Lacs  
Allotted cost : ₹ 4804492.54 Rupees Forty Eight Lakh(s) Four Thousand Four Hundred Ninety Two And Paise Fifty Four Only

Time of completion : 120-days  
M.H. of Account : (JJM)  
Ref. To CDR No. : CDR NO: 3397141 Dated: 16/02/2023 Amount: ₹ 92,300.00  
Name of the Bank : J&K Bank Ltd. Branch Office Chandanwari


For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Request Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

- 1 Time of completion is essence of the contract.

- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 05% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week after issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depositions of 03% performance security of the value of the contract within 07-days after issuance of allotment
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

  
Head Assistant

NO: HDU/CC-04/ 2859-71  
DATED: 19-7-2023  
Copy to the:

  
Executive Engineer  
Hydraulic Division Uri  
(Byed Shafiq)


- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/15662-74 Dated:- 07/03/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla(Member DJJM) for information.
- 9 Chief Medical Officer Baramulla(Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.



**Annexure "A" to the Allotment Order No. 80 of 07/2023**

**Construction of Water Supply Scheme Limber A and B by way of Providing of Chain Link fencing, Construction of Intake Chambers, Protection Bunds, and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM**

#	Particulars	Qty	Unit	Rate	Amount
1	E/W in excavation by manual means in trenches for foundations, drains, pipes, cables etc (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth within 50-Mtr from cutting edge, disposed earth to be leveled and neatly dressed :				
1.1	in all kinds of soils (Trenches)	303.990	Cum	453.440	137841.23
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	60.180	Cum	206.648	12436.08
3	Providing and laying stone soling 2nd class incl. cost of stones.	42.060	Cum	641.056	26962.82
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	26.550	Cum	5056.308	134244.99
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	133.670	Cum	6723.803	898770.72
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	11.850	Cum	8112.790	96136.57
7	Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	17.726	Cum	9784.460	173439.35
8	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
8.1	Foundations, footings, bases of columns	34.680	Sqm	272.792	9460.43
8.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	624.980	Sqm	596.804	372990.56
8.3	Columns	37.800	Sqm	707.356	26738.06
9	12mm thick cement plaster of mix 1:4 (1-cement: 4-sand)	170.260	Sqm	372.320	63391.20
10	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	2725.000	Kg	106.226	289464.76



	Particulars	Qty	Unit	Rate	Amount
	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	10134.130	Kg	106.226	1076504.04
12	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	1236.420	Kg	90.667	112102.74
13	Providing and Fixing of 4mm thick GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	468.300	Sqm	762.840	357237.97
14	Hand-packing stones in wire-crates; including cost of crates and stones inclusive of all carriages upto site of work	146.630	Kg	2600.000	381238.00
15	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
15.1	Cement and Steel (30Kms)	69.310	Mton	454.612	31509.16
15.2	Sand. (35Kms)	88.060	Cum	563.053	49582.44
15.3	Agg. 20mm (60Kms)	141.630	Cum	831.722	117796.83
15.4	Agg. 40mm (60 Kms)	34.170	Cum	904.009	30889.97
15.5	Chainlink Fencing (30km)	0.910	Cum	454.612	413.70
16	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer (1200 mtrs)			0.000	0.00
16.1	Cement	60.340	Mton	553.082	33372.99
16.2	Steel	8.950	Mton	1188.106	10633.55
16.3	Sand.	88.060	Cum	1311.461	115487.24
16.4	Agg. 20mm	141.630	Cum	1311.461	185742.19
16.5	Agg. 40mm	34.170	Cum	1417.738	48444.12
16.6	Stone Soling (100mtr)	35.680	Cum	312.728	11158.14
16.7	Chainlink Fencing	0.910	Cum	552.427	502.71
				<b>Total</b>	<b>4804492.54</b>

Rupees Forty Eight Lakh(s) Four Thousand Four Hundred Ninety Two And Paise Fifty Four Only

Checked by

Head D/Man



  
Executive Engineer  
Hydraulic Division Uri