

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI  
email: urihydraulic@gmail.com

Allotment Order No. 80 of 07/2023

M/S : MOHAMMAD HUSSAIN AKHOON  
S/O : Mohammad Amin Akhoon  
R/O : Khanpora Baramulla  
Registration No. : SE (R&B) SB-B-107 of 2017-18  
TIN No./GST No:- : 01BNNPA6349D1ZE

Name of work : Construction of Water Supply Salasan by way of Construction/Commissioning and Testing of/SSFPS/ Chain Link fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-B)

eNIT No. : 12 /Hyd/Uri of 2023-24 TENDER ID 2023\_IFC\_215240\_21  
Your Tender Received in response to : eNIT No:12/Hyd/Uri\_of\_2023-24 Dated: 17/05/2023 issued under endorsement No:- HDU/CC-02/1178-89 Dated: 05/06/2023 (S. No: 21) Tender ID : 2023\_IFC\_212582\_21

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.  
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.  
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.  
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.  
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).  
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.  
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.  
(viii) This Office Letter No: HDU/eNIT-11/1039-40 Dated:- 30/05/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/3317-29 Dated:- 22/06/2023

Ref: to AAA : Accorded vide Order No. 32/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.  
Ref: to Tech. Sanction : Accorded vide Order No. CE/PHE/DB/541 of 09/2022 Dated:- 10/09/2022.  
LOI Issued under No:- : NIT NO. 12/1545-46 Dated:- 27/06/2023  
Advertisement cost : Rs: 37.29 Lacs  
Allotted cost : ₹ 3827808.83 Rupees Thirty Eight Lakh(s) Twenty Seven Thousand Eight Hundred Eight And Paise Eighty Three Only

Time of completion : 120-days  
M.H. of Account : (JJM)

Ref. To CDR/TDR No. :  
Name of the Bank :

BID SECURITY DECLARATION FORMAT

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

- 1 Time of completion is essence of the contract.
- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week after issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.
- 13 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.



Head Assistant

NO: HDU/CC-04/2487-99

DATED: 18-7-2023

Copy to the:



Executive Engineer  
Hydraulic Division Uri

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/3317-29 Dated:- 22/06/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla(Member DJJM) for information.
- 9 Chief Medical Officer Baramulla(Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.



**Annexure "A" to the Allotment Order No. 88 of 07/20**

**Construction of Water Supply Salasan by way of Construction/Commissioning and Testing of /SSFPs/ Chain Link fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-B)**



| S#   | Particulars                                                                                                                                                                                                                                                                                                                                                           | Qty     | Unit | Rate      | Amount    |
|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|-----------|-----------|
| 1    | E/W in excavation by manual means in trenches for foundations, drains, pipes, cables etc (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth within 50-Mtr from cutting edge, disposed earth to be leveled and neatly dressed :                      |         |      |           |           |
| 1.1  | In all kinds of soils                                                                                                                                                                                                                                                                                                                                                 | 395.290 | Cum  | 436.000   | 172346.44 |
| 2    | Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.                                                                                                                                   | 23.840  | Cum  | 198.700   | 4737.01   |
| 3    | Providing and laying stone soling 2nd class incl. cost of stones                                                                                                                                                                                                                                                                                                      | 23.630  | Cum  | 616.400   | 14565.53  |
| 4    | Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.                                                                                                     | 15.720  | Cum  | 4861.835  | 76428.05  |
| 5    | Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 3 : 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40-mm nominal size) crushed.                                                                                                     | 28.900  | Cum  | 5437.740  | 157150.69 |
| 6    | Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)                                                                                                              | 17.080  | Cum  | 6465.195  | 110425.53 |
| 7    | Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed                                                                       | 16.060  | Cum  | 7800.760  | 125280.21 |
| 8    | Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size. | 20.990  | Cum  | 9408.135  | 197476.75 |
| 9    | Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15 <sup>0</sup> landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)                            | 1.920   | Cum  | 9849.345  | 18910.74  |
| 10   | Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 15 <sup>0</sup> upto floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement                                                                                                                 | 1.791   | Cum  | 10404.515 | 18634.49  |
| 11   | Centering and shuttering including strutting propping etc. and removal of Form work for.                                                                                                                                                                                                                                                                              |         |      |           | 0.00      |
| 11.1 | Foundations, footings, bases of columns                                                                                                                                                                                                                                                                                                                               | 27.590  | Sqm  | 262.300   | 7236.86   |
| 11.2 | Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.                                                                                                                                                                                                                                 | 369.530 | Sqm  | 573.850   | 212054.79 |



| S#   | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                                          | Qty      | Unit | Rate      | Amount    |
|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------|-----------|
| 11.3 | Suspended floors, roofs, landings, balconies and access platform.                                                                                                                                                                                                                                                                                                                                                                                    | 67.990   | Sqm  | 635.600   | 43214.44  |
| 11.4 | Lintel Beams                                                                                                                                                                                                                                                                                                                                                                                                                                         | 10.270   | Sqm  | 502.850   | 5164.27   |
| 11.5 | Edges of Slab (under 20cm wide)                                                                                                                                                                                                                                                                                                                                                                                                                      | 117.180  | RM   | 242.300   | 28392.71  |
| 11.6 | Arches, Domes, walls upto 60 mtr span                                                                                                                                                                                                                                                                                                                                                                                                                | 17.910   | Sqm  | 2086.800  | 37374.59  |
| 12   | 12mm cement plaster of mix 1:4 (1-cement: 4-sand)                                                                                                                                                                                                                                                                                                                                                                                                    | 515.140  | Sqm  | 357.995   | 184417.54 |
| 13   | Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete                                                                                                                                                                                                                                                          | 200.000  | Kg   | 67.650    | 13530.00  |
| 14   | Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.                                                                                      | 545.000  | Kg   | 102.140   | 55666.30  |
| 15   | Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.                                                                                                                                                                                                                                                       | 1774.500 | Kg   | 102.140   | 181247.43 |
| 16   | Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.                                                                                                                                                                                                                                                                                                                          | 5110.470 | Kg   | 87.175    | 445505.22 |
| 17   | Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.                                                                                                                                                                                                                                                                                   | 178.260  | Kg   | 102.140   | 18207.48  |
| 18   | Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.50 mmthick with 20mm nominal size stone aggregate. Crushed                                                                                                                                                                         | 42.360   | Sqm  | 555.500   | 23530.98  |
| 19   | Providing and lying 50mmthick DPC with cement concrete 1: 2: 4 and curing complete                                                                                                                                                                                                                                                                                                                                                                   | 23.720   | Sqm  | 410.135   | 9728.40   |
| 20   | Providing woodwork in frames of doors, windows, celestory, windows and other frames, wrought frames and fixed in position with hold fast lugs with dash fastness of required dia and length (hold fast lugs or with dash fastness shall be paid for separately Second Class Kail Wood                                                                                                                                                                | 0.740    | Cum  | 92065.350 | 68128.36  |
| 21   | Brick work with common burnt clay F.P.S.(non-modular) bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement:6 coarse sand)                                                                                                                                                                                                                                                                                          | 22.210   | Cum  | 7507.400  | 166739.35 |
| 22   | Providing and fixing 35mm panelled or pannelled glazed shutter for doors, windows ad celestory widows including ISI Marked, M.S Pressed, but hinges, bright finished of required size with necessary screws excl. pannelling which will be paid for separately all complete.                                                                                                                                                                         | 10.810   | Sqm  | 3093.800  | 33443.98  |
| 23   | Providing and fixing paneling or panelig & glazing in pannelled & glazed shutter for doors, windows & clear stove windows. (Area of opening for pannel inserts excluding position inside groves or rebates to be measured). Pannelling for pannelled or panelled glazed shutters Decorative ply wood both sides decorative vaneer and ommericla vane or other type conformig to IS 1328 BWR Tp. (Including all sorts of carriages upto site of work) | 8.140    | Sqm  | 1931.200  | 15719.97  |
| 24   | Providing and fixing glazed shutters for doors, windows and celestory windows using 10Kg/Sqm (4mm Thick) float glass panes including ISI Marked M.S Pressed but hinges bright finished of required size with necessary screws. (Including all sorts of carriages upto site of work)                                                                                                                                                                  | 7.350    | Sqm  | 3726.050  | 27386.47  |

21/12/12  
  


| #    | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty     | Unit | Rate     | Amount   |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|----------|----------|
| 25   | Providing and fixing 35 mm thick wire gauze shutters using galvanised M.S. wire gauze of average width for aperture 1.4 mm in both directions with wire of dia. 0.63 mm for doors, windows and clerestory windows with hinges and necessary screws, Second class kail wood. (Including all sorts of carriages upto site of work)                                                                                                 | 9.010   | Sqm  | 3651.650 | 32901.37 |
| 26   | Providing and laying of 1st quality ceramic glazed wall/floor tiles conforming to IS 13753 of minimum thickness 5mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalent in all colours, shades except burgundy, bottle green black of any size as approved by Engineer Incharge laid on 20mm thick bed of cement mortar (1:4) including pointing the joints with white cement and matching pigments etc complete. | 36.670  | Sqm  | 1216.050 | 44592.55 |
| 27   | Flooring with marble stone of specified thickness as per sample of marble approved by Engineer Incharge over 20mm (average) thick base of cement mortar 1:4 (1 Cement 4: coarse sand) laid and jointed with grey cement slurry including rubbing, polishing and curing complete with Udaipur Green Marble                                                                                                                        | 4.180   | Sqm  | 2206.450 | 9222.96  |
| 28   | Finishing walls with water proofing cement paint (Two or more coats) Work applied @3.84Kg/10Sqm                                                                                                                                                                                                                                                                                                                                  | 101.730 | Sqm  | 91.800   | 9338.81  |
| 29   | Applying One coat of Cement Primer of approved brand manufacture on wall shape                                                                                                                                                                                                                                                                                                                                                   | 101.730 | Sqm  | 59.350   | 6037.68  |
| 30   | Applying Priming coat with ready mixed primer of approved brand and manufacture on wood work (hard and soft wood)                                                                                                                                                                                                                                                                                                                | 37.340  | Sqm  | 59.500   | 2221.73  |
| 31   | Painting with synthetic enamel paint of approved brand and manufacture 2 or more coats on new works                                                                                                                                                                                                                                                                                                                              | 37.340  | Sqm  | 121.950  | 4553.61  |
| 32   | Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat                                                                                                                                                                                                                                                               | 49.080  | Kg   | 190.190  | 9334.53  |
| 33   | Providing and fixing of Pre colour coated galvanized iron sheets (Size, shape and pitch of corrugation as approved by Engineer Incharge at site (0.5mm Thick) including self drilling, self tapping, Screw, EPDM seal or with Polymer coated J or L hooks, bolts, and nuts etc including ridges/valleys of required width as approved by Engineer Incharge at site                                                               | 88.000  | Sqm  | 830.250  | 73062.00 |
| 34   | Providing and fixing of plained eaves boarding 250X32mm nominal size (Kail wood)                                                                                                                                                                                                                                                                                                                                                 | 37.500  | RM   | 693.900  | 26021.25 |
| 35   | Providing ridges or hips of width 60cm overall width plain G.S Sheets fixed with Polymer coated J or L hooks, bolts and coating not less than 275 gram/m <sup>2</sup> impet and bitumen washers complete                                                                                                                                                                                                                         | 10.670  | RM   | 691.350  | 7376.70  |
| 36   | Providing and fixing of hold fasts embedded in concrete                                                                                                                                                                                                                                                                                                                                                                          | 38.080  | Kgs  | 112.000  | 4264.96  |
| 37   | Providing and fixing of water closet (Indian Type) squatting pan with 10mm dia PR s trap flushing cistern with handle lower with all fittings and fixtures                                                                                                                                                                                                                                                                       | 1.000   | No   | 5062.500 | 5062.50  |
| 38   | Supply and filling in plinth level with fine sand under floor including watering ramming consolidating and dressing complete                                                                                                                                                                                                                                                                                                     | 17.280  | Cum  | 787.400  | 13606.27 |
| 39   | Providing and fixing of soil, waste and vent pipes                                                                                                                                                                                                                                                                                                                                                                               |         |      |          | 0.00     |
| 39.1 | 10mmDia Pipe                                                                                                                                                                                                                                                                                                                                                                                                                     | 20.000  | M    | 898.870  | 17977.40 |
| 39.2 | 75mm dia pipe                                                                                                                                                                                                                                                                                                                                                                                                                    | 15.000  | M    | 772.120  | 11581.80 |
| 40   | Providing and Fixing white vitreous China pedestal for wash basin completely recessed at back for reception of pipes and fittings                                                                                                                                                                                                                                                                                                | 1.000   | No   | 1249.250 | 1249.25  |
| 41   | Stainless Steel Kitchen sink with CI brackets and plug 40mm with drain board.                                                                                                                                                                                                                                                                                                                                                    | 1.000   | No   | 3068.130 | 3068.13  |
| 42   | PVC waste pipe for sink and wash basin 40mm semi right                                                                                                                                                                                                                                                                                                                                                                           | 2.000   | No   | 78.000   | 156.00   |
| 43   | Trap for self cleaning design with hinged grating                                                                                                                                                                                                                                                                                                                                                                                | 2.000   | No   | 773.500  | 1547.00  |
| 44   | 600mm long towel rail                                                                                                                                                                                                                                                                                                                                                                                                            | 1.000   | No   | 300.000  | 300.00   |

20/11/2017  
  


|      | Particulars                                                                                                                                                                                                                                                                                   | Qty       | Unit  | Rate      | Amount   |
|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------|-----------|----------|
| 45   | Providing and fixing of 450X450 main hole cover and frame for septic tank                                                                                                                                                                                                                     | 4.000     | No    | 600.000   | 2400.00  |
| 46   | Providing and fixing of chlorinated polyvinyl Chloride (CPVC) pipes having thermal stability for hot and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer incharge         | 36.000    | No    | 234.150   | 8429.40  |
| 47   | Providing and fixing of electric wiring 3/22 for electric point through conduit (lighting )(including switch, sockets conduit wiring complete job                                                                                                                                             | 20.000    | Point | 2250.000  | 45000.00 |
| 48   | Providing and fixing of electric wiring 7/20 for electric points (including switch, sockets conduit wiring complete job                                                                                                                                                                       | 10.000    | Point | 3750.000  | 37500.00 |
| 49   | Providing and fixing of MCB mounted on wall as required at site complete job                                                                                                                                                                                                                  | 4.000     | Point | 1500.000  | 6000.00  |
| 50   | Providing and fixing of mirror of superior (approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing (rectangular shape 453*357mm                                                                            | 2.000     | No    | 1100.000  | 2200.00  |
| 51   | Providing and fixing of 600x120mm x 5mm glass shelf with edges round of supported on anodise aluminium angle frame with cp brass bracket and guard rail complete fixed with 40mm long screws complete job                                                                                     | 1.000     | No    | 850.000   | 850.00   |
| 52   | Providing and fixing of bends of required degree with excess door, insertion rubber insertion etc                                                                                                                                                                                             |           |       |           | 0.00     |
| 52.1 | 100mm dia                                                                                                                                                                                                                                                                                     | 4.000     | No    | 530.000   | 2120.00  |
| 52.2 | 75mm dia                                                                                                                                                                                                                                                                                      | 4.000     | No    | 350.000   | 1400.00  |
| 53   | Providing and fixing double equal junction of required degree                                                                                                                                                                                                                                 |           |       |           | 0.00     |
| 53.1 | 100mm dia                                                                                                                                                                                                                                                                                     | 3.000     | No    | 800.000   | 2400.00  |
| 53.2 | 75mm dia                                                                                                                                                                                                                                                                                      | 3.000     | No    | 700.000   | 2100.00  |
| 54   | Providing and fixing of floor traps                                                                                                                                                                                                                                                           |           |       |           | 0.00     |
| 54.1 | 100 mm dia                                                                                                                                                                                                                                                                                    | 2.000     | No    | 950.000   | 1900.00  |
| 54.2 | 75mm dia                                                                                                                                                                                                                                                                                      | 1.000     | No    | 780.000   | 780.00   |
| 55   | Providing and fixing of water heating gysers I.S.I Mark standard quality 50 liter capacity with inlet outlet connection and electric connection complete job                                                                                                                                  | 1.000     | No    | 8500.000  | 8500.00  |
| 56   | Providing and fixing of hardware items, i.e handles tower bolts locking arrangement etc as per the direction of in charge engineer complete Job                                                                                                                                               | 1.000     | Job   | 30000.000 | 30000.00 |
| 57   | Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)                                                                                                              |           |       |           | 0.00     |
| 57.1 | 65mm dia                                                                                                                                                                                                                                                                                      | 4.000     | Nos   | 5000.000  | 20000.00 |
| 57.2 | 50mm dia                                                                                                                                                                                                                                                                                      | 2.000     | Nos   | 4000.000  | 8000.00  |
| 58   | Providing and fixing GI Bend in dome slab with one and provided with wire gauge mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality                                                                                                                  |           |       |           | 0.00     |
| 58.1 | 50mm dia                                                                                                                                                                                                                                                                                      | 5.000     | Nos   | 500.000   | 2500.00  |
| 59   | Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia length                                                                                                                                                                                       | 20.000    | No    | 200.000   | 4000.00  |
| 61   | Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer |           |       |           | 0.00     |
| 61.1 | Cement and Steel (40Kms)                                                                                                                                                                                                                                                                      | 69.950    | Mton  | 534.280   | 37372.89 |
| 61.2 | Sand. (45Kms)                                                                                                                                                                                                                                                                                 | 63.290    | Cum   | 650.690   | 41182.17 |
| 61.3 | Agg. 20mm (90Kms)                                                                                                                                                                                                                                                                             | 80.650    | Cum   | 1097.810  | 88538.38 |
| 61.4 | Agg. 40mm (90Kms)                                                                                                                                                                                                                                                                             | 14.150    | Cum   | 1193.190  | 16883.64 |
| 61.5 | Bricks (110Kms)                                                                                                                                                                                                                                                                               | 11105.000 | No    | 3.450     | 38312.25 |

2/11/24  
mmx

1/2

|                   | Particulars                                                                                                                                                                                                                                                                                            | Qty           | Unit | Rate              | Amount            |
|-------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|------|-------------------|-------------------|
| .6                | Timber (80Kms)                                                                                                                                                                                                                                                                                         | 0.740         | Cum  | 1141.480          | 844.70            |
| 62                | Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer |               |      |                   | 0.00              |
| 62.1              | Cement (2500Mtrs)                                                                                                                                                                                                                                                                                      | 38.040        | Mton | 995.550           | 37870.72          |
| 62.2              | Steel (2500Mtrs)                                                                                                                                                                                                                                                                                       | 31.610        | Mton | 2138.670          | 67603.36          |
| 62.3              | Sand. (2500Mtrs)                                                                                                                                                                                                                                                                                       | 63.290        | Cum  | 2449.250          | 155013.03         |
| 62.4              | Agg. 20mm (2500Mtrs)                                                                                                                                                                                                                                                                                   | 80.650        | Cum  | 2449.250          | 197532.01         |
| 62.5              | Agg. 40mm (2500Mtrs)                                                                                                                                                                                                                                                                                   | 14.140        | Cum  | 2647.710          | 37438.62          |
| 62.6              | Stone Soling (500Mtrs)                                                                                                                                                                                                                                                                                 | 23.630        | Cum  | 730.800           | 17268.80          |
| 62.7              | Bricks (2500Mtrs)                                                                                                                                                                                                                                                                                      | 11105.000     | No   | 4.560             | 50638.80          |
| 62.8              | Timber (2500Mtrs)                                                                                                                                                                                                                                                                                      | 0.740         | Cum  | 1374.890          | 1017.42           |
|                   |                                                                                                                                                                                                                                                                                                        |               |      | <b>Total</b>      | <b>3729717.26</b> |
| <b>Excess (+)</b> |                                                                                                                                                                                                                                                                                                        | <b>2.630%</b> |      | <b>3827808.83</b> |                   |

Rupees Thirty Eight Lakh(s) Twenty Seven Thousand Eight Hundred Eight And Paise Eighty Three Only

Checked by

Head DAM  


**Executive Engineer**  
**Hydraulic Division Uri**