

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urfhydraulic@gmail.com

Allotment Order No. 111 of 12/2022

M/S : Mir Constructions Company
Prop: : Mukhtyar Ahmad Mughal
S/O : Liaqat Ali Mughal
R/O : Kundi Birjala
Registration No. : SHEP/CE/AAAY/Civil/Sanitary/003
Class : AAAY
TIN No./GST : 01AOAPM8579C2Z3

Name of work : *Retrofitting of Water Supply Scheme Shahdara Chapper by way of Construction/Commissioning and Testing of Intake Chambers/PSTs/SRs/SSFPs/ Protection works, Chain Link fencing, providing and laying of GI Pipes and other allied works (for providing 100% FHTC) under JJM*

eNIT No. : 04 /Hyd/Uri of 2022-23 TENDER ID 2022_IFC_167384_4
Your Tender Received in response to : 04 /Hyd/Uri_of_2022-23 Dated: 20/04/2022 issued under endorsement No:- HDU/CC-02/272-83 Dated:-20/04/2022 (S. No: 04) Tender ID : 2022_IFC_167384_4

Reference :

(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.

(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.

(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.

(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HO Sopore authorization No: SE/Hyd/DB/7071-83 Dated:- 07/09/2022

Ref: to AAA : Accorded vide Order No. 40/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022, issued under Endorsement No:- SE/Hyd/DB/6402-07 Dated:- 26/08/2022

Ref: to TS : Accorded vide Order No. CE/PHE/DB/535 of 09/2022 Dated:- 10/09/2022 issued under endorsement No:- CE/PHE/DB/21415-19 Dated:- 10/09/2022

LOI issued under NO:- : HDU/CC-02/eNIT-4/2490-2503 Dated:- 12/09/2022

Advertisement cost

Allotted cost

: Rs:130.40Lacs

: ₹ 13562442.97

Rupees One Crore Thirty Five Lakh(s) Sixty Two Thousand Four Hundred Forty Two And Paise Ninety Seven Only

Time of completion : 90-days

M.H. of Account : (JJM)

Ref. To CDR No. : CDR NO: 3385878 Dated: 18/11/2022

Name of the Bank : J&K Bank Ltd.

Amount: ₹ 280,000.00
Branch Office KB Adda Bla.

[Handwritten signatures and initials]

For and on behalf of L.T. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

- 1 Time of completion is essence of the contract.
- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depositions of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by

Head Draftsman

NO: HDU/CC-04/4097-4909

DATED: 13.01.2023.

Copy to the:


Technical Officer to
Executive Engineer
Hydraulic Division Uri





Executive Engineer
Hydraulic Division Uri
(Syed Shafiq)

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: SE/Hyd/DB/7071-83 Dated:- 07/09/2022
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information. This is in continuation to this office LOI issued under No: HDU/CC-02/eNIT-4/2490-2503 Dated:- 12/09/2022
- 13 File.



Annexure "A" to the Allotment Order No. /// of 12/2022

Retrofitting of Water Supply Scheme Shahdara Chapper by way of Construction/Commissioning and Testing of Intake Chambers/PSTs/ SRs/SSFPs/ Protection works, Chain Link fencing, providing and laying of GI Pipes and other allied works (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1.00	EW in excavation by manual means in trenches for foundations, drains, pipes, cables etc (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth within 1km from cutting edge disposed earth to be leveled and neatly dressed.				
1.10	In all kinds of soils (Trenches)	4607.60	Cum	436.00	2008913.60
2.00	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m	3401.51	Cum	198.70	675880.04
3.00	Providing and laying stone soling 2nd class incl. cost of stones	71.36	Cum	616.40	43986.30
4.00	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	48.76	Cum	4861.84	237063.07
5.00	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	121.77	Cum	6465.20	787266.80
6.00	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	82.32	Cum	7800.76	642158.56
7.00	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size	113.44	Cum	9408.14	1067258.83
8.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	8.01	Cum	9849.35	78893.25
9.00	Providing and fixing upto floor five level precast cement concrete string or lacing, courses copings bed plates anchor blocks plain window sills, shelves, louvers, steps stair cases etc including hoisting and setting fr position with cement mortar 1:3 (1 cement: 3 coarse sand) cost of required centring shuttering and curing complete I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	1.12	Cum	8679.00	9720.48
10.00	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level incliding curing but excluding cost of centering and shuttering, finishing and reinforcement	4.98	Cum	10404.52	51814.48
11.00	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	50.00	Cum	2500.00	125000.00
12.00	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
12.10	Foundations, footings, bases of columns	132.09	Sqm	262.30	34647.21
12.20	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	1446.40	Sqm	573.85	830016.64
12.30	Suspended floors, roofs, landings, balconies and access platform.	56.14	Sqm	635.60	35682.58
12.40	Arches, Domes, walls upto 60 mtr span	49.64	Sqm	2086.80	103588.75
12.50	Columns, Pilers, abutment, posts and struts.	25.20	Sqm	680.15	17139.78
13.00	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	1273.30	Sqm	358.00	455835.03
14.00	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	935.00	Kg	61.50	57502.50

MM  Ken  2nd 

Particulars		Qty	Unit	Rate	Amount
15.00	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job	1635.00	Kg	92.85	151809.75
16.00	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	3950.00	Kg	102.25	403867.75
17.00	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	20025.58	Kg	87.18	1745729.94
18.00	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	508.52	Kg	102.25	51993.63
19.00	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat	233.14	Kg	191.68	44687.11
20.00	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
20.10	100mm dia	2.00	Nos	9000.00	18000.00
20.20	65mm dia	2.00	Nos	9000.00	18000.00
20.30	50mm dia	4.00	Nos	9000.00	36000.00
20.40	40mm dia	2.00	Nos	9000.00	18000.00
21.00	Providing and fixing GI Bend in dome slab with one and provided with wire gauge mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality				0.00
21.10	50mm dia	18.00	Nos	500.00	9000.00
22.00	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engh	60.00	No	200.00	12000.00
23.00	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	91.00	Cum	8500.00	773500.00
24.00	Providing and fixing of MS Flanges (8-mmThick) to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carriages upto site of work complete job				0.00
24.10	100mm dia	31.00	Joints	1135.00	35185.00
24.20	80mm dia	48.00	Joints	800.00	38400.00
24.30	65mm dia	73.00	Joints	700.00	51100.00
24.50	50mm dia	153.00	Joints	600.00	91800.00
25.00	Laying and fitting of GI Pipes with GI fitting excluding trenching and refilling etc.				0.00
25.10	80 mm dia GI pipes	1500.00	Mtr	73.05	109575.00
25.20	65 mm dia GI pipes	2800.00	Mtr	73.05	204540.00
25.30	50 mm dia GI pipes	7500.00	Mtr	40.80	306000.00
25.40	40 mm dia GI pipes	3400.00	Mtr	40.80	138720.00
25.50	25 mm dia GI pipes	4000.00	Mtr	30.65	122600.00
25.60	20 mm dia GI pipes	3500.00	Mtr	20.25	70875.00
25.70	15mm dia GI pipes	1500.00	Mtr	20.25	30375.00
26.00	Making connection of GI distribution branch with GI main of following sizes, by P/F of tees. incld. cutting and threading the pipe etc. complete				0.00
26.10	25 to 40 mm dia nominal bore	20.00	No	666.25	13325.00
26.20	Above 40 mm nominal bore	4.00	No	1268.75	5075.00
27.00	Providing and Fixing of GI chain link fabric fencing (4mmDia wire) of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	312.00	Sqm	733.50	228852.00
28.00	Providing and fixing of bolts of 16mm Dia 25Cm Long fully threaded to be embed in cement concrete with bolts including all sorts of carriages Complete Job	40.00	No	200.00	8000.00
29.00	Providing and fixing of MS Plates for anchoring of pipe over saddle/anchor blocks with nuts and bolts already fitted in concrete 4mm thick 200 wide and average length 50cms MS Plate complete job in all respect	62.80	Kg	112.00	7033.60

	Particulars	Qty	Unit	Rate	Amount
10.00	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duty recommended by Junior Engineer/Assistant Executive Engineer				0.00
30.10	Cement and Steel (21-Kms)	258.13	Mton	366.47	94597.16
30.20	Sand. (25-Kms)	196.53	Cum	451.97	88826.25
30.30	Agg. 20mm (60-Kms)	291.91	Cum	799.73	233450.06
30.40	Agg. 40mm (60-Kms)	43.90	Cum	869.24	38159.59
30.50	Stone Soling (05Kms)	125.34	Cum	276.35	34637.08
31.00	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duty recommended by Junior Engineer/Assistant Executive Engineer				0.00
31.10	Cement (600-Mtrs)	139.33	Mton	317.77	44274.62
31.20	Steel (600-Mtrs)	115.14	Mton	682.59	78593.87
31.30	Sand. (600-Mtrs)	192.21	Cum	712.61	136970.58
31.40	Agg. 20mm (600-Mtrs)	283.18	Cum	712.61	201796.62
31.50	Agg. 40mm (600-Mtrs)	43.90	Cum	770.36	33818.89
31.60	Stone Soling (600-Mtrs)	58.76	Cum	838.33	49260.09
				Total	13040810.55
Excess (+)		4.00%		13562442.968	

Checked by

Head D/Men
21/2
[Signature]Executive Engineer
Hydraulic Division Uri
[Signature]