OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 793 - 96 Dated. 00 - 05 - 202)

Mr. Mohammad Shafi Dar. Contractor S/o. Ghulam Nabi, R/o Rohmu-Pulwama, Regd. No. CE/UEED/BEE/338/2003-04

Retrofitting of Water Supply Scheme Hanji Khulla by way of providing, laying & fitting of GI pipes including installation of 41 No. FHTC's for Hanji Khulla including maintenance for a period of 3 years which includes DLP of 12 months (JJM).

E-NIT S.No. 101/PHEP/Fresh of 2020-21, job No. (1), Circulated vide this office No. PHEP/5709-19 Dated:-18-01-2021 and S.E. Hydl. Circle, Shopian's No. SE/Hyd/331-32 dtd. 17-04-2021

> Advertised Amount of work: ₹ 10,52,000.00 Alloted Amount of work: ₹ 11,78,000.00 Rupees Eleven Lakh(s) Seventy Eight Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

SI. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	421.50	Cum	240.45	280.00	Rupees Two Hundred Eighty Only
2.00	Dismantling of G.I. pipes (external work) including excavation and fefilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.		, " J			'/
2.10	15mm to 40mm nominal bore	200.00	Mtr	52.60	70.00	Rupees Seventy Only
3.00	P/F of flanged pipe with flanged joints 12mm thick of flanges cost of nuts, botts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.		7			
3.10	80 mm dia GI flanged pipe.	100.00	Mtr	RQC	1000	Rupees One Thousand Only
3.20	65 mm dia GI flanged pipe.	600.00	Mtr	RQC	750	Rupees Seven Hundre Fifty Only
4.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.		* *1	V No. 11		
4.10	40mm dia	300.00	Mtr	RQC	386.00	Rupees Three Hundre Eighty Six Only
4.20	25mm dia	300.00	Mtr	RQC	249.00	Rupees Two Hundred Forty Nine Only
4.30	20mm dia	1000.00	Mtr	RQC	182.00	Rupees One Hundred Eighty Two Only
4.40	15mm dia	500.00	[§] Mtr	RQC	145.00	Rupees One Hundred Forty Five Only
5.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.			T		
5.10	25mm to 40mm nominal bore	30.00	No	403.65	450.00	Rupees Four Hundred Fifty Only
6.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	379.35	Cum	102.20	90.00	Rupees Ninety Only
7.00	L/F of GI pipes excluding cost of pipes and earth work (pipe available fromdismantling site)					
7.10	25mm dia	100.00	Mtr	19.40	23.00	Rupees Twenty Three Only
7.20	20mm dia	100.00	Mtr	13.05	15.00	Rupees Fifteen Only

Terms and Conditions:-

- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 - double will hold good even before the drawl of an agreement with the department.
- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. Howeve,r the non drawl of agreement will not prevent the contract from being enforced upon you.
- That the works is required to be completed within (30) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- Earnest Money of ₹ 43700/- deposited by your vide CDR No. 2954506 dated 14-12-2020 has been retained in the divisional office as security deposit.
- All other terms and conditions will remain same as per the original agreement form No. 25-double, Form FC 33 and detailed E-NIT.

Head Draftsman m

Copy to the:-

- Superintending Engineer, Hydraulic Circle, Shopian, for information District Development Commissioner Pulwarna for information.
- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.

Executive Engineer, ISD (PHE) Div. Pulwama