

OFFICE OF THE
EXECUTIVE ENGINEER JAL SHAKTI PHE (HYD) DIVISION BANDIPORE

Subject: -

Renovation of Slow Sand Filtration Plant, Laying/ Fitting of pipe network, construction of protection wall, chain link fencing, anchor/ saddle blocks, intake/ collection chamber, sluice chamber and crate protection works at head site WSS Tangath.

Reference: -

1. This office E-NIT No 04-PHE/Hyd/Bpr of 2022-23 issued under endorsement No PHE/Hyd/Bpr/397-407 dated 18/04/2022.
2. Revised District Action Plan of District Bandipore approved by DJJM vide No DDCB/BPR/2022/2056 dated 16/07/2022.
3. Minutes of Meeting held with District Development Commissioner Bandipore (Chairman DDJM) on 04/07/2022 minutes issued vide order No 154-DDCB of 2022 dated 28/07/2022 issued under endorsement No DDCB/JJM/2022-23/2279-82 dated 28/07/2022
4. Amendment in operational guidelines for the implementation of Jal Jeevan Mission issued by NJJM, DDW&S Ministry of Jal Shakti GOI vide F. No W-11016/10/2022-JJM-IV-DDWS Dated 21/06/2022
5. Modus operandi communicated by Chief Engineer Jal Shakti PHE Kashmir vide Circular No CE/PHE/MC/DB/13745-83 Dated 26/07/2022
6. Superintending Engineer Hydraulic Circle Bla/ Bpr H.Q Sopore's Authorization No SE/Hyd/DB/4901-14 dated 29/07/2022
7. Letter of intent issued vide this office No PHE/Hyd/Bpr/JJM/3984-97 dated 30/07/2022
8. Administrative Approval Accorded by Superintending Engineer Hydraulic Circle Bla/ Bpr H.Q Sopore's order No 56/SE/Hyd/DB/JJM of 2022-23 dated 24/09/2022 issued endorsement No SE/Hyd/DB/8141-46 dated 24/09/2022.
9. Technical Sanction issued by Chief Engineer Jal Shakti (PHE) Department Kashmir's Order No CE/PHE/DB/749 of 11/2022 Dated 16/11/2022 issued under endorsement No CE/PHE/DB/30202-08 dated 16/11/2022.

ORDER NO. PHE/HYD/BPR/42 OF 2022-2023

DATED: 28/11/2022

Major Head of Account: JAL JEEVAN MISSION

Advertised Cost: Rs.75.22 Lacs

Allotted Cost: Rs.76,72,140.00

Time of Completion: 90 Days

(GST No: -01GMBPM9821C1ZE)

For and on behalf of the Lieutenant Governor of Union Territory of Jammu and Kashmir, contract for the work "Renovation of Slow Sand Filtration Plant, Laying/ Fitting of pipe network, construction of protection wall, chain link fencing, anchor/ saddle blocks, intake/ collection chamber, sluice chamber and crate protection works at head site WSS Tangath" is hereby fixed with Showkath Ahmad Malik S/o Mohammad Shafi Malik R/o Nusso Bandipore bearing Regd No SB-123-SE (R&B)/A/Class/1998-99, on the allotted cost of Rs.76,72,140.00 (Rupees Seventy Six Lac Seventy Two Thousand One Hundred Forty only) on the rates quoted and subsequently negotiated / accepted by bidder on percentage basis as per the Annexure "A" of this allotment order with the standard terms and conditions as laid down in Annexure "B" of this allotment and Detailed E-NIT and SBD.

Technical Officer

Executive Engineer
PHE (Hyd) Division
Bandipore

No: - PHE/Hyd/Bpr/CC/ 0321-34

Dt: - 28/11/2022

Copy to the: -

01. Chief Engineer Jal Shakti PHE Department Srinagar for favour of information.
02. District Development Commissioner Bandipore (Chairman DJJM) for favour of information.
03. Additional District Development Commissioner Bandipore (Member DJJM) for favour of information.
04. Superintending Engineer Hydraulic Circle Bla/ Bpr H.Q Sopore (Member Secretary DJJM) for favour of information.
05. Assistant Commissioner Development Bandipore (Member DJJM) for favour of information.
06. Divisional Forest Officer Bandipore (Member DJJM) for favour of information.
07. Chief Planning Officer Bandipore (Member DJJM) for favour of information.
08. Chief Medical Officer Bandipore (Member DJJM) for favour of information.
09. Chief Education Officer Bandipore (Member DJJM) for favour of information.
10. District Social Welfare Officer Bandipore/District Tribal Welfare Officer Bandipore (Member DJJM) for favour of information.
11. District Information Officer Bandipore (Member DJJM) for favour of information.
12. Assistant Executive Engineer PHE Sub-Division Bandipore for information.
13. WAPCOS Bandipore for information.
14. Office File.

**OFFICE OF THE
EXECUTIVE ENGINEER PHE (HYD) DIVISION BANDIPORE**

EXHIBITURE "A" TO ALLOTMENT Order No. 42 PHE/HYD/BPR/2022-23 Dated 28/11 /2022

Work:- "Renovation of Slow Sand Filtration Plant , Laying / Fitting of pipe network, construction of protection wall, chainlink fencing , Anchor/ saddle blocks , intake/ collection chamber sluice chamber, and crate protection works at head site for WSS Tanghat Under JJM"

Adv. Cost :- 75.22
Allotted Cost :- 7672140.00

No	Particulars	Qty.	Unit	Alloted Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All kinds of soil	1455.39	Cum	444.72	647241.04
1.1	Ordinary Rock	432.05	Cum	987.20	426522.78
2	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil	37.14	Cum	550.13	20432.09
2.01	Ordinary Rock	6.06	cum	872.76	5288.94
3	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres: All kinds of soil :	72.46	Cum	257.09	18628.81
4	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil :	9.45	Cum	83.28	787.02
5	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge : 15 mm to 40 mm nominal bore	100.00	mtr	101.74	10174.50
5.01	Above 40 mm nominal bore	2200.00	mtr	112.86	248298.60
6	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work:- 80 mm dia G.I pipe	210.00	mtr	74.51	15647.31
6.01	50mm dia G.I pipe	620.00	mtr	41.61	25801.92
6.02	40mm dia G.I pipe	2000.00	mtr	41.61	83232.00
6.03	25mm dia G.I pipe	2700.00	mtr	31.26	84410.10
6.04	20mm dia G.I pipe	3300.00	mtr	20.65	68161.50
6.05	15mm dia G.I pipe	1200.00	mtr	20.65	24786.00
7	Providing and fixing of 12mm thick M.S flanges G.I pipe incld. Cost of flanges, rubber gaskets, nuts bolts, welding charges cutting of threads exclud. Earth work and refilling:	287.00	joints	1224.00	351288.00
7.01	100mm dia	202.00	joints	1071.00	216342.00
7.02	80mm dia	133.00	joints	816.00	108528.00
7.03	65mm dia	0.00	joints	714.00	0.00
8	Providing and fixing of CI sluice valve with cap including all accessories like nuts, bolts rubber insertion etc and tail pieces of Kirloskar make including successful testing and commissioning. 100mm dia	8.00	No	45900.00	367200.00
8.01	80mm dia	4.00	No	30600.00	122400.00
8.02	65mm dia	3.00	No	25500.00	76500.00
9	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions incld. Tailpeices ,tapers, Gi pipe etc. complete 50 mm dia	3.00	No	10200.00	30600.00
9.01	25mm dia	8.00	No	7140.00	57120.00

[Signature]
Head Draftsman

Conts. On 2nd


[Signature]
Executive Engineer

p-2nd
"Renovation of Slow Sand Filtration Plant , Laying / Fitting of pipe network, construction of protection wall, chainlink fencing , Anchor/ saddle blocks , intake/ collection chamber sluice chamber, and crate protection works at head site for WSS Tanghal Under JJM"

	ing connection of G.I. distribution branch with G.I. main of wing sizes by providing and fixing Tee, including cutting and fitting the pipe etc. complete 25 to 40 mm nominal bore	162.00	Nos	679.57	110091.15
	40 mm nominal bore	50.00	Nos	1294.12	64706.25
	providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) 50 mm nominal bore	6.00	No	2040.00	12240.00
	65 mm nominal bore	9.00	No	2550.00	22950.00
12	Constructing masonry Chamber of specified size, in brick work with common burnt clay (non modular) bricks of class designation 7.5 cement mortar 1:4 (1 cement : 4 coarse sand) and R.C.C. top slab 1:1.5:3 mix (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) including necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick finished with a floating coat of neat cement complete as per standard design. For sluice valve, with C.I. surface box 100 mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid. Chamber 120x120x100 cm	1.00	No	21892.10	21892.11
13	Dumping stone including cost of stones. in Horizontal on level	96.15	Cum	628.72	60452.20
14	Hand packing stones into wire crates incld. Cost of stones but excld. Cost of crates	183.60	Cum	752.19	138103.74
15	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	1547.05	Cum	202.67	313546.81
16	Providing and laying of Baramulla stones of approved size and texture incld. All sorts of carriage	35.00	sqm	1836.00	64260.00
17	Providing and laying of filter media (gravel) to be laid in layers as per specification and site incharge incld. Testing and all sorts of carriage	66.52	Cum	7854.00	522448.08
18	Providing & laying stone soling in horizontal on level.	11.09	Cum	832.72	9234.95
19	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	9.55	Cum	4959.07	47359.13
20	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	4.53	Cum	7956.77	36044.19
21	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	6.51	Cum	9596.29	62471.90
22	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with : 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	67.43	Cum	10046.33	677424.16
23	Providing & fixing of main hole cover 0.90 x 0.90 of standard quality with angle iron frame incld all necessary fittings complete	4.00	No	4590.00	18360.00
24	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level: Thermo-Mechanically Treated bars of grade Fe-500D or more	1960.64	kg	88.918	174337.17


Head Draftsman

Conts. On 3rd


Executive Engineer

Renovation of Slow Sand Filtration Plant , Laying / Fitting of pipe network, construction of protection wall, chainlink fencing , Anchor/ saddle blocks , intake/ collection chamber sluice chamber, and crate protection works at head site for WSS Tanghat Under JJM"

27	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete Welded	316.38	kg	104.17	32959.74
27	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1186.00	kg	92.84	110114.76
27	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	210.68	sqm	267.54	56366.59
27	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	432.90	sqm	585.32	253388.06
27	Suspended floors, roofs, landings, balconies and access platforms	6.40	sqm	648.31	4149.20
27	Edges of slabs and breaks in floors and walls : Under 20 cm wide	33.00	Rm	247.14	8155.82
27.1	Columns, pillars, piers, abutments, posts and struts.	8.64	sqm	693.75	5994.03
28	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	22.50	Cum	5546.49	124796.13
29	12mm Cement plaster finished with a floating coat of neat cement of mix:1:3 (1 cement 3 sand)	86.43	sqm	350.62	30304.52
30	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	90.00	sqm	748.17	67335.30
31	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	319.60	sqm	265.25	84774.22
32	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	15.55	Cum	7118.24	110688.76
33	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness)including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses,string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shutteringand finishing with 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	69.21	Cum	7414.56	513162.30
34	Applying priming coat:- With ready mixed red oxide Zinc Chromate primer of approved brand and manufacture on steel work (second coat)	99.80	sqm	29.47	2941.90
35	Painting with aluminum paint of approved brand and manufacture to give an even shade. Two or more coats on new work	99.80	sqm	121.78	12154.44
36	Providing and fixing of nuts ,bolts and chips incld one end fix to anchor block	100.00	kg	80.83	8083.50
37	Providing & fixing of 80mm dia PVC pipe for aeration purpose	50.00	mtr	102.00	5100.00
38	Welding, including transportation of plant at site etc. complete By electric plant	3900.00	cm	6.27	24464.70
39	Provision for Providing and fixing of pipe specials of standard quality incld. testing complete	1.00	job	61200.00	61200.00
40	Supply of crates	8212.00	sft	21.42	175901.04
41	Carraige of materials from source to road site of work including loading , unloading and stacking:-- Stone / stone soling for an av lead of 15 km	291.29	Cum	409.86	119390.93
41	40mm aggregate for an av lead of 45 km	9.00	Cum	721.40	6492.65
41	20mm aggregate for an av lead of 45 km	106.45	Cum	663.70	70651.27
41	sand for an av lead of 30km	67.88	Cum	511.68	34733.04
41	Pipes for an av lead of 15km	20.00	MT	309.72	6194.46

Head Draftsman

Conts. On 4th

Executive Engineer

p-4"

"Renovation of Slow Sand Filtration Plant, Laying / Fitting of pipe network, construction of protection wall, chainlink fencing, Anchor/ saddle blocks, intake/ collection chamber sluice chamber, and crate protection works at head site for WSS Tanghat Under JJM"

	Crates for an av lead of 15 km	34.25	MT	309.72	10608.01
	Crates for an av lead of 15 km	3.56	MT	309.72	1102.61
	Crates for an av lead of 15 km	1.70	MT	309.72	526.53
	Carraige of materials from road site to site of work by manual labour including loading, unloading and stacking for an av lead of 500 Mtrs. Stone / stone soling	291.29	Cum	744.24	216790.54
	40mm aggregate	9.00	Cum	684.97	6164.74
	20mm aggregate	106.45	Cum	633.63	67450.36
42	sand	67.88	Cum	680.55	46196.02
42	pipes	20.00	MT	362.81	7256.28
42.1	Cement	34.25	MT	362.81	12426.38
42.1	Steel	3.56	MT	618.07	2200.36
42.1	Crates	1.70	MT	287.74	489.16
43	Providing, erecting and fixing of sign board 2'6"x4' made up of angle iron frame work 50x50x6mm with 1mm thick M.S sheet including priming, painting and proper lettering and embedding with 1:3:6 cement concrete complete job.	1.00	job	6120.00	6120.00
				TOTAL	7672140.00

Rupees (Seventy Six Lac Seventy Two Thousand One Hundred Forty only)


Head Draftsman


Executive Engineer
PHE (Hyd) Division
Bandipora.

ANNEXURE "B"

Construction of Slow Sand Filtration Plant, Laying/ Fitting of pipe network, construction of protection wall, chain link fence/ anchor/ saddle blocks, intake/ collection chamber sluice chamber and crate protection works at head site

TERMS AND CONDITIONS

01. The work shall be executed strictly as per approved design / drawing, specifications and JJM Guidelines. Any deviation or change in proposal/location is subject to the prior approval from the competent authority.
02. The rates allotted are inclusive of all taxes applicable as per norms amended by competent authorities from time to time. Labour cess and royalties shall have to be borne by the executing agency/contractor.
03. The execution of work shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department
04. No liability should be created on this account.
05. This letter of allotment will constitute a legal contract between the government and the contractor and the conditions as laid down in the master NIT for 2022-2023 and PWD Form No. 25 (Double) will also hold good even before the drawl of an agreement between the Government and the contractor.
06. That the date of start of the work shall be reckoned within two days from the date of issue of Letter of Intent issued vide this office No PHE/Hyd/Bpr/JJM/3984-97 dated 30/07/2022 and in case of delay on the part of the contractor in execution of the work within stipulated time of completion a penalty upto 10% of contract value shall be imposed upon him.
07. The total amount of work should not exceed Rs.76,72,140.00 in any case.
08. The contractor has deposited 3% Performance Security amounts to Rs.2,30,174.00 bearing No. 593388 dated 23/11/2022 in shape of earnest money (CDR) through J&K Bank Branch Unit Mini Secretariat Bandipore and which has been retained in the divisional office and shall be released after the successful completion/ commissioning of work and after observing DLP period is over.
09. In case the contractor fails to execute the work, the work shall be put to fresh tenders on the risk and cost of the contractor & the excess cost if involved shall be recovered from the contractor and strict action as warranted under contractual obligation shall be taken against the defaulter
10. The time of completion of the work is reckoned **90 Days (Ninety Days)** as per the condition laid down in the e-NIT.
11. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of subject work. If during warranty period any malfunctioning/ defects arise, the firm shall have to rectify the same within a period of ten days of receipt of intimation. In case of any failure on the part of the firm to remove the defect, the department may get the defects removed/ repaired by any other agency and cost thereof shall be recovered from the firm and shall be recommended for further punitive action as governed under the relevant clause of the contract including blacklisting
12. After testing and commissioning of work, the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department
13. The defects Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trial run. The bidder shall be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as deemed fit for getting the defect rectified subject to a maximum ceiling of 6 Months
14. In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the

and conditions of the contract, the Department shall with or without
judice to any other remedies available to it under any law for the time
being enforce in the UT:

Terminate the contract after 15 days' notice
and/or

Recover the amount of loss caused by damage, failure or default, as
may be determined by the department.

c). Recover the extra cost, if any, involved in allotting contract to other party.
and/or

d). Impose Liquidated damages on account of delay beyond the schedule completion
period to the tune of 0.5% of the delayed portion of contract every week but not
exceeding 10% value of the contract.

and/or

15. Any failure or commission to carry out the provision of the contract shall not give rise to any claim by the department or bidder one against the other if such failure of commission arises from the 'ACT OF GOD' which shall include all natural calamities such as fires, floods, earthquake, hurricane, strikes, riots, embargoes or from any political or other reasons beyond the control of the parties including war, or a state of insurgency
16. In the event of the death or insanity or insolvency or imprisonment of the bidder or where the bidder being a partnership or firm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineer-in-charge, be terminated by notice in writing posted at the site of the works
17. The bidder should ensure the safety of the water supply lines, sewer lines, telephone cables, power cables, storm water drains etc., pipe laying alignment and, if any damage occurs during execution it should be attended immediately at the cost of the bidder. Failing to attend immediately, the same will be got done by the Department at the risk and cost of the allottee
18. All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract are the responsibility of the Bidder
19. **The bidder shall not sublet the whole or part of the work.** The bidder shall not assign the work or any part thereof or any benefit or any interest thereon or any claim arising of the contract, without prior written consent of the allotting authority
20. From the commencement of the work to the completion thereof the same shall be under the bidder's charge. The bidder shall be held responsible for and make good any loss or injuries by fire or other causes / theft and shall hold the Government harmless for any claims for injuries to persons or damage to property happening from any neglect, default, want of proper care and misconduct on the part of the bidder, or any of his employees, during the execution of work. The bidder shall be responsible for the compensation if any, to labour under the existing labour laws of the country
21. The bidder shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under
22. The bidder shall at his own cost make arrangements for proper storage especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose the bidder shall, with the approval of Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work

bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the department for the protection of the work or safety and convenience of the Public etc. The bidder/firm shall make his own arrangement, at his own cost, for all lines, individual power points, etc. to the machinery and plant required by him for the execution, testing and commissioning of the equipment ordered on him. The bidder shall pay for all electrical energy consumed by him for this purpose at the prevalent electricity tariff in J&K State. Such charges shall be paid by the bidder/firm directly to the Power Corporation and the bidder's final bill shall be settled only after he gets a no outstanding certificate from the concerned Electric Division.

The Division shall not be responsible, and the bidder shall have no claim whatsoever for any interruption in power supply or voltage fluctuation or total cut off at the site. The bidder/firm must provide an alternative source of power, at his own cost, at the site for completion of the work. The bidder shall make his own arrangements for water to be used for the execution/Hydro-testing/ water tightness Test/ Curing, labour colony, Site Office etc

25. Forfeit the performance security and blacklist the firm

26. Geo Tagged Photographic evidences of the work; pre-execution, during execution and post execution should be maintained by the agency on his own expenses

27. The executing agency/contractor must execute the work as per the requirements/specifications detailed in the relevant/applicable IS codes

28. The tests for concrete and allied materials shall have to be carried out at reputed institute as per directions of Engineer in-charge and the charges for the same shall have to be borne by the executing agency/contractor

29. All Environmental norms, labour laws and all other guidelines issued by competent authorities shall be followed in letter and spirit

30. The payment of work shall be made as and when the funds are available to the tune within available provision of DPR by the competent authority under the proper scheme/ account head.


31. As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the bidder/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award in favour of successful firm.

32. Nothing shall be paid to the contractor on account of dewatering/ diversion even if involved at site of work.

33. If the Contractor have not start the work within 15 days of issuance of this letter of intent, the contract shall be cancelled at the risk and cost of contractor without serving any notice. The Assistant Ex. Engineer concerned shall intimate this office regarding the same.

34. All other terms and conditions as laid down in Master E-NIT, Tender documents and PWD form 25 shall remain in force.


Technical Officer


Executive Engineer
PHE (Hyd) Division
Bandipore