

2

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/1999-02  
Dated: 27-07-2021

Mr. Bashir Ahmad Naik,  
Contractor,  
S/o. Ghulam Ahmad Naik,  
R/o Zaglgam, Pulwama  
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Panzgam by way of Providing & laying of GI pipes, construction of chain link fencing around structures, providing CGI roofing over SR and face lifting of structures and electrical & mechanical works including installation of 168 No. FHTC's for Panzgam including maintenance for a period of three years which includes DLP of 12 months.(JMM).

Ref:- E-NIT S.No. 129/PHEP of 2020-21, job No. (2), Circulated vide this office No. PHEP/7073-83 Dated:- 08-03-2021, followed by Corrigendum No. PHEP/156-66 Dated. 10-04-2021 and Superintending Engineer, Hydl. Circle, Shopian's letter No. Se/Hyd/955-56 dated. 02-06-2021, Ex. Engineer, PHE Mech. Divn South Avantipora's No. MDSA/723 dated. 14-07-2021.

Advertised Amount of work: ₹ 54,05,000.00

Alloted Amount of work: ₹ 47,97,200.00

**Rupees Forty Seven Lakh(s) Ninety Seven Thousand Two Hundred Only**

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Dismantling G.I pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge					
1.10	15 mm to 40 mm nominal bore.	100.00	Mtr	99.75	99.00	Rupees Ninety Only
1.20	Above 40 mm nominal bore	150.00	Mtr	110.65	100.00	Rupees One Hundred Only
2.00	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts, wells, cesspits, and the like not exceeding 10sqm on plan, including dressing of sides and ramming of bottoms up to 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	968.78	Cum	436.00	350.00	Rupees Three Hundred Fifty Only
3.00	Providing and laying of stone rolling hand packed including watering dressing and ramming all complete	9.33	Cum	612.20	600.00	Rupees Six Hundred Only
4.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:3:6 mix (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	7.34	Cum	4419.85	4419.85	Rupees Four Thousand Four Hundred Nineteen And Paise Eighty Five Only
5.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:3:6 mix (1 cement: 3 coarse sand: 8 graded stone aggregate 20 mm nominal size)	35.06	Cum	4943.40	4843.4	Rupees Four Thousand Nine Hundred Forty Three And Paise Forty Only
6.00	Providing and laying specified grade of reinforced cement concrete including curing but excluding the cost of centring, shuttering, finishing and reinforcement all works upto plinth level 1:2:4 mix (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	58	Cum	6344.25	6300.00	Rupees Six Thousand Three Hundred Only
7.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centring shuttering, finishing and reinforcement. 1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	2.13	Cum	8552.85	8600.00	Rupees Eight Thousand Five Hundred Only
8.00	Brick work with common burnt clay (non-modular) bricks of class designation 7.5 in foundation and plinth including curing in: Cement mortar 1:6 (1 cement: 6 coarse sand)	5.25	Cum	6183.75	6183.75	Rupees Six Thousand One Hundred Eighty Three And Paise Seventy Five Only
9.00	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete upto plinth level thermo-Mechanically-Treated bars of grade Fe-500D or more	216.00	Kg	79.25	79.25	Rupees Seventy Nine And Paise Twenty Five Only
10.00	Centring shuttering including strutting, propping etc. and removal of form work for					
10.10	Foundation footings, bases for columns	219.26	Sqm	262.30	160.00	Rupees One Hundred Fifty Only
10.20	Columns, pillars, piers, abutments, posts and struts.	10.80	Sqm	680.15	600.00	Rupees Five Hundred Only
10.30	Suspended floors, roofs, landings, balconies and access platforms	9.21	Sqm	635.60	400.00	Rupees Four Hundred Only
10.40	Edges of slabs and breaks in floors and walls Under 20 cm wide	13.00	Mtr	242.30	200.00	Rupees Two Hundred Only
11.00	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixed with dash fastener of required dia. and size including necessary filling up of gaps at junctions i.e. at top, bottom and sides with required EPDM rubber / neoprene gasket felt etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-Charge (glazing, panelling and dash fasteners to be paid for separately) Anodized aluminum (Anodized transparent or dyed to required shade according to IS:1868 minimum anodic coating of grade AC15)	41.18	Kg	417.55	400.00	Rupees Four Hundred Only
12.00	12mm Cement plaster of mix 1:4 (1 cement: 4 fine sand)	181.04	Sqm	260.05	228.00	Rupees Two Hundred Twenty Only
13.00	Providing fixing flanged joints with 12mm thick flanges including cost of nuts, bolts, washers, cutting of thread and making good for jointing including testing and commissioning all cartriages head load complete 80 mm dia G.I pipe	25.00	Joint	RCC	750.00	Rupees Seven Hundred Fifty Only
14.00	Providing and fixing G.I pipes complete with G.I fittings excluding trenching and refilling etc. (external work)					
14.10	80 mm dia G.I pipes	400.00	Mtr	RCC	772.15	Rupees Seven Hundred Seventy Three And Paise Fifteen Only



Sub :- **Retrofitting of Water Supply Scheme Panzgam by way of Providing & laying of GI pipes, construction of chain link fencing around structures, providing CGI roofing over SR and face lifting of structures and electrical & mechanical works including installation of 168 No. FHTC's for Panzgam including maintenance for a period of three years which includes DLP of 12 months.(JMM).**

14.20	65 mm dia G.I pipes	200.00	Mtr	RQC	628.45	Rupees Six Hundred Twenty Eight And Paise Forty Five Only
14.30	50 mm dia G.I pipes	800.00	Mtr	RQC	477.50	Rupees Four Hundred Seventy Seven And Paise Fifty Only
14.40	40 mm dia G.I pipes	1386.00	Mtr	RQC	386.05	Rupees Three Hundred Eighty Six And Paise Five Only
14.50	25 mm dia G.I pipes	1300.00	Mtr	RQC	249.00	Rupees Two Hundred Forty Nine Only
14.60	20 mm dia G.I pipes	1500.00	Mtr	RQC	182.65	Rupees One Hundred Eighty Two And Paise Sixty Five Only
14.70	15 mm dia G.I pipes	2016.00	Mtr	RQC	144.40	Rupees One Hundred Forty Four And Paise Forty Only
15.00	Providing and laying S&S Centrifugally Cast (Spun) Ductile Iron Pipes conforming to IS : 8329 100 mm dia Ductile Iron Class K - 7 Pipes	200.00	Mtr	RQC	1108.15	Rupees One Thousand One Hundred Eight And Paise Fifteen Only
16.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete					
16.10	(a) 25 to 40 mm nominal bore	15.00	No	666.25	460.00	Rupees Four Hundred Only
16.20	(b) Above 40 mm nominal bore	8.00	No	1268.75	900.00	Rupees Nine Hundred Only
17.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	828.57	Cum	198.70	120.00	Rupees One Hundred Twenty Only
18.00	Providing repairs to 100mm dia flanges by way of providing welding, nuts, bolts, washers, all carriages by mechanical transport spot to spot including dismantling if any and excavation and refilling including commissioning complete job 100 dia flanges (to be paid as per actual details/measurements)	155.00	Joint	RQC	200.00	Rupees Two Hundred Only
19.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1454.73	Kg	82.75	82.75	Rupees Eighty Two And Paise Seventy Five Only
20.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer in-charge. Made of G.I. wire of dia 4 mm	182.99	Sqm	733.50	733.00	Rupees Seven Hundred Thirty Three Only
21.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	3.00	Cum	5877.45	6600.00	Rupees Five Thousand Five Hundred Only
22.00	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	250.00	Kg	133.30	110.00	Rupees One Hundred Ten Only
23.00	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc complete On steel work	154.80	Sqm	188.80	180.00	Rupees One Hundred Eighty Only
24.00	Providing fixing of poplar wood of standard quality including necessary nails, and carriage complete. (to be paid as per actual details/measurements with supporting vouchers duly verified by AEE concern)	140.00	Cft	RQC	450.00	Rupees Four Hundred Fifty Only
25.00	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal / vertical or curved surface) excluding the cost of purins, rafters and trusses and including cutting to size and shape wherever required 0.63mm thick with zinc coating not less than 275 gram/m <sup>2</sup>	81.19	Sqm	951.80	951.80	Rupees Nine Hundred Fifty One And Paise Eighty Only
26.00	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete with 0.63 mm thick with zinc coating not less than 275 gram/m <sup>2</sup>	20.00	Mtr	691.35	600.00	Rupees Six Hundred Only
27.00	Providing and fixing of coloured suits of standard quality including all necessary accessories including all sorts of carriage complete. (to be paid as per actual details/measurements with supporting vouchers duly verified by AEE concern)	18.96	Sqm	RQC	200.00	Rupees Two Hundred Only
28.00	Providing and fixing of sanitary items of standard quality like 1000 liters sintex, W.C Indian type, flush tank, with all accessories, pvc pipe, pipe specials, C.P items, p trap, floor trap, bends, steel sink, connecting with soakage, whichever be necessary to make functional all complete (to be paid as per actual details/measurements with supporting voucher duly verified by AEE concern)	1.00	Job	RQC	12000.00	Rupees Twelve Thousand Only
29.00	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete. In colour such as White, Ivory, Grey, Fume Red Brown	15.00	Sqm	1052.75	1000.00	Rupees One Thousand Only
30.00	Providing fixing supplying P.C.C rings including earthwork excavation and disposal of surplus excavated material outside the premises including providing and laying cement concrete in 1:2:4 mix over septic tank and soakage pit, construction of man hole chambers with angle iron frame and covering arrangements, providing fixing of P.V.C pipe (prince make B class) including bends whichever is required at site or as per directions of Engineer-in-charge (3 compartments for septic tank and 1 for soakage pit. (to be paid as per actual details/measurements)	20.00	Rft	RQC	600.00	Rupees Six Hundred Only
31.00	Providing, supplying fixing installation of electric fittings of standard quality incl. 18/18 copper wire cable connection with transformer, installation of panel board, switch board, switches, lighting points, heating points, fans, exhaust fans, pvc conduit, haveli wire, MCB, changeover, whichever is related to the item and found necessary at site or as per directions of Engineer-in-charge (to be paid as per actual details/measurements with supporting vouchers duly verified by AEE concern)	1.00	Job	RQC	3000.00	Rupees Three Thousand Only
32.00	Providing fixing double Flanges & sluice valves of standard quality Klokser Ivage make conforming to IS 780 of 1984 read with upto date amendments standard mark ISI make FN-1 including cost of nuts bolts IR cloth including all sorts of carriage upto site of work complete job including cost of pedestals and handles (to be paid as per actual details with supporting vouchers duly verified by AEE concern) 100 dia sluice valve	4.00	No	RQC	12000.00	Rupees Twelve Thousand Only
33.00	Carriage of material from source to site upto site of work by mechanical transport including loading/unloading at site complete					
34.00	Sand and Bajri avg lead 15km	64.79	Cum	297.02	200.00	Rupees Two Hundred Only
35.00	Cement and steel avg lead 15km	12.78	M.T.	264.04	200.00	Rupees Two Hundred Only



Sub :- **Retrofitting of Water Supply Scheme Panzgam by way of Providing & laying of GI pipes, construction of chain link fencing around structures, providing CGI roofing over SR and face lifting of structures and electrical & mechanical works including installation of 168 No. FHTC's for Panzgam including maintenance for a period of three years which includes DLP of 12 months.(JMM).**

36.00	Stone rolling avg lead 15km	9.33	Cum	349.42	300.00	Rupees Three Hundred Only
37.00	Bricks for avg lead 15 km	2949.00	No	0.79	.60	Rupees And Paise Sixty Only
38.00	Well No. 1: Design, supply, installation, Testing & Commissioning of Submersible Pumping Equipment Suitable for bore well (detailed specifications as per Annexure B)	1.00	Job	RQC	40000.00	Rupees Forty Thousand Only
39.00	P/F of 3 Core, 10 Sq mm Cu- Submersible Cable ( Flat Cable) as per IS964 1990 ( Standard Insulation) of L& T/ Havells Make	90.00	Mtr	RQC	200.00	Rupees Two Hundred Only
40.00	Fabrication, providing & fitting of 65 mm dia. (class-C) Flanged GI column pipes each of 10 ft length. The job includes the cost of 18 mm thick MS flanges on both sides and welding in two layers to make the flanged joint strong and leak proof. The pipe of 10 ft length is to be weld on both sides with flanges of standard size with Advani /Adore electrode (Advani/Oerlikon make). The job includes all types of skilled labours, power supply diesel Generator etc required for the job, with suitable size nuts, bolts, RI Cloth in the flanged joints of column pipes.	15.00	Job	RQC	3000.00	Rupees Three Thousand Only
41.00	Fabrication, providing & fitting of 65 mm dia (class-C) Flanged GI delivery pipes of standard length. The job includes the cost of 18 mm thick MS flanges and welding in two layers to make the flanged joint strong and leak proof. The delivery pipe is to be weld on both sides with flanges of standard size with Advani /Adore electrode (Advani/Oerlikon make). The job includes all types of skilled labours, power supply diesel generator etc required for the job, with suitable size nuts bolts RI Cloth in the flanged joints of delivery pipes. The pipe is to be laid underground in trenches by cutting of hard soil as per site condition.	24.00	Mtr	RQC	1000.00	Rupees One Thousand Only
42.00	Fabrication providing & fitting of split type MS Clamps 60mm dia, 6mm thick, 2.5' wide (dia) and 2.5 feet long for lowering of column pipes and holding of pumping unit after lowering. The job includes the cost of required size of nuts and bolts.	2.00	Pair	RQC	600.00	Rupees Five Hundred Only
43.00	Providing & fitting of 65 mm dia. 90 to 120 degree bend/offset/reducer made of (class-B) GI pipe and flanged on both ends after cutting threaded portion to make it leak proof. The bend shall have two no. flanges 18 mm thick weld on both sides in two runs of welding. The job includes p/f of suitable size nuts, bolts, RI Cloth required for jointing.	4.00	Job	RQC	1600.00	Rupees One Thousand Six Hundred Only
44.00	Fabrication, Providing and fitting of washout arrangement to the rising main by way of P/F of 65 mm dia G I flanged pipe length (c-class)-1mtr including Providing / Fitting of 65 mm dia. G. I. Tee of equal sides duty flanged 16mm thick on all three sides with welding in double layers to make leak proof joints. Nuts, bolts and rubber insertion washers required are also included in the job.	1.00	Job	RQC	3000.00	Rupees Three Thousand Only
45.00	Fab., Erection and Fixing of M.S Stool to the casing assy of the production well. The stool shall be fabricated out of ISMC - 100 and ISA 50x50x6mm in such a way that the top of the stool flushes with top of casing pipe. The size of stool shall be 2'x2' with a height of 3', adequate bracings are to be provided and a detachable M.S plate of 2'x2' size and 10mm thick, splitted in two parts having 3" dia. Size hole at the centre.	1.00	Job	RQC	4600.00	Rupees Four Thousand Five Hundred Only
46.00	Providing, fabricating and fitting of gravel Hooper fabricated out of angle iron ISA (50x50x5) and MS plates, chequered plate 6mm sheeting all over five sides including cover at top and excluding bottom side of size 3'x3' from top and 2'x2' at bottom having 3' depth (trusium type). The top over is to be split in to two parts with making/cutting of circular hole having overall diameter of 12 inch and hinged with the two sides of the hopper by way of P/F of required size of moveable hinges with locking arrangements at the top of the hopper. The job includes earth work excavation from the top of the well casing/flooring up to the ground level for making of gravel pit to accommodate gravel hooper. The job includes all head loads and lifts and anti corosive painting in Silver / Blue/ RED coating following by red oxide 2 coats.	1.00	Job	RQC	20000.00	Rupees Twenty Thousand Only
47.00	Fabrication / Erection of Channel iron column to act as support for resting of monorail crane (detailed specifications as per Annexure B)	1.00	Job	RQC	36000.00	Rupees Thirty Five Thousand Only
48.00	Providing/fitting of manual type chain pully block (detailed specifications as per Annexure B)	1.00	Job	RQC	16000.00	Rupees Fifteen Thousand Only
49.00	Providing, Fitting of 65 mm, PN 1 6/16, Ductile Iron double flanged, soft seated glandless gate/ sluice valve. Body and bonnet of ductile cast iron, wedge with fully vulcanized EPDM rubber (Approved for drinking water) and NBR seal. Gate /Sluice valve shall be compatible for buried application and shall be safe to install in both horizontal and vertical positions. It shall have electrostatic epoxy coating inside and outside approved for drinking water the valve shall be supplied along with hand wheel. The job includes providing and fitting of 02 No. M.S Flanges perfectly adaptable to the inbuilt flanges of the valve, which shall be fitted with delivery mains of the pumping unit. Cost on account of Nuts, bolts, gaskets, etc required for the job is included in the scope of work. Make VAG / TALIS /AVK	2.00	Job	RQC	3500.00	Rupees Three Thousand Five Hundred Only
50.00	Providing, Fitting of 65 mm, PN 1 6/16, Ductile Iron double flanged, Slanted seat swing check valve( NRV). Body of ductile cast iron with fully encapsulated vulcanized EPDM rubber (Approved for drinking water). Gate /Sluice valve shall be compatible for buried application and shall be safe to install in both horizontal and vertical positions. It shall have electrostatic epoxy coating inside and outside approved for drinking water. The job includes providing and fitting of 02 No. M.S Flanges perfectly adaptable to the inbuilt flanges of the valve, which shall be fitted with delivery mains of the pumping unit. Cost on account of Nuts, bolts, gaskets, etc required for the job is included in the scope of work. Make VAG / TALIS /AVK	1.00	Job	RQC	3000.00	Rupees Three Thousand Only
51.00	Creation of 63 KVA Electric Sub Stabon as per the technical (detailed specifications as per Annexure B)	1.00	Job	RQC	266000.00	Rupees Two Lakh(s) Sixty Five Thousand Only
52.00	Steel Tubular Poles - (detailed specifications as per Annexure B)	1.00	Job	RQC	19000.00	Rupees Eighteen Thousand Only
53.00	P/F of Guy Wire Complete with shekel insulator to MS poles at necessary locations. The Job includes excavation of pit for lowering Guy stone with guy wire and back filling of same	2.00	Job	RQC	1000.00	Rupees One Thousand Only
54.00	Earthing for Substation structure (detailed specifications as per Annexure B)	1.00	Job	RQC	2000.00	Rupees Two Thousand Only
55.00	Providing/ fitting of link rod for isolating link set.	1.00	No	RQC	1500.00	Rupees One Thousand Five Hundred Only
56.00	Providing and Fitting of 0.05 ACSR Aluminum conductor.	230.00	Mtr	RQC	60.00	Rupees Sixty Only
57.00	P/F of 35 Sq mm, 3 Core, ABC Al HT cable 11 KV of Havells/Glister/ Polycab/ at necessary locations.	60.00	Mtr	RQC	720.00	Rupees Seven Hundred Twenty Only
58.00	P/F of 11 KV HT Kit at necessary locations. (9 Nos)	3.00	Kit	RQC	4500.00	Rupees Four Thousand Five Hundred Only
59.00	Providing, fitting of G.O Link set suitable for 11 KV(3 pieces) of reputed make as per REC standard including pipe of suitable length and diameter for its operation. The job also includes earthing of link set handle as per REC norms, rod, handle etc	1.00	Job	RQC	5000.00	Rupees Five Thousand Only
60.00	Fabrication, providing and fitting of L.T Modular control panel " Pedestal type" of appropriate size duly powder coated & fabricated out of 2mm crca sheets sheet having required openings/vents and protection/ locking arrangements/ mountings for the fitting of devices and including arrangements of terminal for earthing to whole panel body (detailed specifications as per Annexure B)	1.00	Job	RQC	15000.00	Rupees Fifteen Thousand Only



(11) :- **Retrofitting of Water Supply Scheme Panzgam by way of Providing & laying of GI pipes, construction of chain link fencing around structures, providing CGI roofing over SR and face lifting of structures and electrical & mechanical works including installation of 168 No. FHTC's for Panzgam including maintenance for a period of three years which includes DLP of 12 months.(JJM).**

61.00	Providing, Installation, Testing & Commissioning 25 KVA voltage stabilizer (detailed specifications as per Annexure B)	1.00	Job	RQC	40000.00	Rupees Forty Thousand Only
62.00	Service line - Providing and fitting of 35 mm Sq 3.5 core XLPE Armored Al cable Havells /polycab/ finolex make to be used as service line, laying underground where ever required from the control panel to the change over system etc. the job includes the cost of all types of men and machines required. The cable terminals for connections to switch gear at various requisite points shall be Aluminium thimbles of Dowel's make and of appropriate size and connected by hydraulic crimp tool only.	50.00	Mtr	RQC	190.00	Rupees One Hundred Ninety Only
63.00	Interconnections - Providing & Fitting of 25 mm square single core copper cable of Havells/polycab/finolex make for inter connections laying under ground wherever required from the control panel to the changeover, MCCB, Voltage stabilizer & other system. The job includes the cost of all types of men & machines required. The cable terminals should be crimped with copper thimbles.	90.00	Mtr	RQC	300.00	Rupees Three Hundred Only
64.00	Providing and erection of 9 Mtr long Hot Dip Galvanized octagonal pole (single Section) with bottom 150mm, thickness 3mm with 70 Microns Zinc coating having inside arrangement for providing of power connection (detailed specifications as per Annexure B)	1.00	Job	RQC	6000.00	Rupees Six Thousand Only
65.00	Electrification of pump house - (detailed specifications as per Annexure B)	1.00	Job	RQC	20000.00	Rupees Twenty Thousand Only
66.00	Providing of heating Blower of reputed make.	1.00	No	RQC	1200.00	Rupees One Thousand Two Hundred Only
67.00	Well No. 2: Supply, installation, testing and commissioning of multistage bowl type Submersible clear water pumping (detailed specifications as per Annexure B)	1.00	Job	RQC	36000.00	Rupees Thirty Five Thousand Only
68.00	Providing and fixing of Budloo wood for basement, vertical posts, horizontal posts etc. for ply penalling of operators quarter. The job includes providing & fixing of nails, hinges, aldrops etc wherever required as per site requirement. (detailed specifications as per Annexure B)	22.71	Cft	RQC	800.00	Rupees Eight Hundred Only
69.00	Providing and fixing of 19mm thick ply board for basement of quarter as per following details: 15x10=150 sqft. Job includes all machining operations, all head loads, all leads & lifts, carriages, hardware items used & skilled labour used at site.	150.00	Sft	RQC	40.00	Rupees Forty Only
70.00	Providing and fixing of 12mm thick ply board for walls & ceiling of quarter (detailed specifications as per Annexure B)	612.00	Sft	RQC	10.00	Rupees Ten Only
71.00	Providing of tool kit consisting of following items: Spanner set= 12 pieces of size 4/5,6/7,8/9,10/11,12/13,14/15,16/17,18/19,21/23,24/26,24/27,30/32 Ring set of 12 pieces of same size as above Pliers= 2 No Cutting Pliers/Nose pliers=2 No Screw driver= 2 No Hammer= 01 No of 01 kg Pipe wrench= 2 No Multimeter= 01 No Job includes providing of 01 No bamboo link rod & 01 No bamboo ladder also	1.00	Job	RQC	8000.00	Rupees Eight Thousand Only
72.00	Providing & fitting of 12 volts 25 plate DC battery of 150 AH along with 850 Watt inverter in the operators room including the cost of wiring & 03 NO. lighting points in 3/20 copper conductor with energy saver bulbs fitted in holders along with conduit. Job includes all head loads, carriages, & skilled labours involved at site.	1.00	Job	RQC	27500.00	Rupees Twenty Seven Thousand Five Hundred Only
73.00	Providing of thermocoal along with Exel matting for operators room of 15x10' size. Job includes providing of 4 No cushion 01 NO Andus handy light 4 No plastic chairs for adults with a suitable table & crockery items/ utensils with all types of leads & carriages.	1.00	Job	RQC	8000.00	Rupees Eight Thousand Only
74.00	P/F of MUG 20 starte of L&T make.	2.00	Job	RQC	2500.00	Rupees Two Thousand Five Hundred Only
75.00	P/F of 100 ampere MCCB of Havells/ L&T make enclosed in a box to be locked with a lock & key.	1.00	Job	RQC	8000.00	Rupees Eight Thousand Only
76.00	Fabrication, Providing and fitting of Modular control panel of appropriate size fabricated out of required thickness SWG sheet having required openings / vents and protection Class : 1P 55 (detailed specifications as per Annexure B)	1.00	Job	RQC	7000.00	Rupees Seven Thousand Only

**Terms and Conditions:-**

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (90) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Tahab for information and necessary action.
- 4- File Concerned.

Executive Engineer  
USD (PHE) Div. Pulwama