

10

Government of Jammu and Kashmir  
**OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA**

No. PHEP/ 5247-50  
Dated: 22-12-2020

**Mr. Bashir Ahmad Naik,**  
Contractor,  
S/o. Ghulam Ahmad Naik,  
R/o Zagigam, Pulwama  
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

**Sub :-** Retrofitting of Water Supply Scheme Tiken Batapora by way of providing, laying and fitting of GI pipes, including face lifting of structures and electrical/ mechanical works including installation of 70 No. FHTCs for Tiken Batapora (JJM).

**Ref:-** E-NIT S.No. 41/PHEP of 2020-21, job No. (4), Circulated vide this office No. PHEP/3169-83 Dated: 29-09-2020.

\*\*\*\*\*  
**Advertised Amount of work: ₹ 32,57,000.00**  
**Alloted Amount of work: ₹ 35,45,000.00**  
**Rupees Thirty Five Lakh(s) Forty Five Thousand Only**

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	1276.50	Cum	324.00	Rupees Three Hundred Twenty Four Only
2.00	Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.	220.00	Mtr	71.00	Rupees Seventy One Only
2.10	15mm to 40mm dia bore	370.00	Mtr	80.00	Rupees Eighty Only
2.20	Above 40mm dia bore				
3.00	L/F of G.I. pipes excluding cost of ppe and earth work but including handling complete:-	220.00	Mtr	36.00	Rupees Thirty Six Only
3.10	40mm dia GI pipe				
4.00	P/F of flanged pipe with flanged joints 12mm thick of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete. Including cost of pipes	700.00	Mtr	1224.00	Rupees One Thousand Two Hundred Twenty Four Only
4.10	100mm dia GI pipe with flanges	300.00	Mtr	850.00	Rupees Eight Hundred Fifty Only
4.20	80mm dia GI pipe with flanges				
5.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.	200.00	Mtr	480.00	Rupees Four Hundred Sixty Only
5.10	65mm dia	1200.00	Mtr	350.00	Rupees Three Hundred Fifty Only
5.20	40mm dia	2000.00	Mtr	200.00	Rupees Two Hundred Only
5.30	25mm dia	2000.00	Mtr	162.00	Rupees One Hundred Sixty Two Only
5.40	20mm dia	850.00	Mtr	135.00	Rupees One Hundred Thirty Five Only
5.50	15mm dia				
6.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.	50.00	No	530.00	Rupees Five Hundred Thirty Only
6.10	25mm to 40mm nominal bore	20.00	No	1210.00	Rupees One Thousand Two Hundred Ten Only
6.20	above 40mm nominal bore				
7.00	Providing, supplying, fixing of 12mm thick flanged joints incld cost of nuts, bolts, washers, cutting of threading incld making good for jointing with welding all carriage to and fro complete	60.00	Joint	800.00	Rupees Eight Hundred Only
7.10	80mm dia flanged joint				
8.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	125.97	Sqm	37.53	Rupees Thirty Seven And Paise Fifty Three Only
9.00	finishing walls with water proofing cement paint of required shade on new works (two or more coats) applied @ 3.84 Kg/10SqM	308.87	Sqm	78.81	Rupees Seventy Six And Paise Eighty One Only
10.00	P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	10000.00	Rupees Ten Thousand Only
11.00	P/F of different dias of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirkoskar or VAGC) including all carriages upto site of work complete including tail pieces	4.00	No	12000.00	Rupees Twelve Thousand Only
11.10	100mm dia sluice valve				
12.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr	1148.85	Cum	178.00	Rupees One Hundred Seventy Eight Only
13.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deeo and disposal of rubbish lead upto 50 mtr and lift upto 1.5 mtr all kinds of soil	353.10	Sqm	15.00	Rupees Fifteen Only
14.00	Providing and laying in position specified grade of reinforces cement concrete excluding the cost of centering shuttering finishing and reinforcement. All work upto plinth level in 1:2:4 mx (1 cement : 2 coarse sand:3 graded stone) 20mm nominal size.	7.90	Cum	5500.00	Rupees Five Thousand Five Hundred Only
15.00	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new works (two or more coats) over and including primary coat with cement primer.	64.58	Sqm	115.00	Rupees One Hundred Fifteen Only

Sub :- **Retrofitting of Water Supply Scheme Tiken Batapora by way of providing, laying and fitting of GI pipes, including face lifting of structures and electrical/ mechanical works including installation of 70 No. FHTCs for Tiken Batapora (JJM).**

16.00	Painting on G.S sheets with synthetic enamel paint of approved band and manufacture of required colour to give an even shade. New work (two or more coats) including a coat of. approved steel primer but excluding a coat of mordant solution.	125.97	Sqm	107.00	Rupees One Hundred Seven Only
17.00	Painting with synthetic enamel paint of approved band and manufacture of give an even shade two or more coats on new work	22.38	Sqm	90.58	Rupees Ninety And Paise Fifty Eight Only
18.00	Provision for electrical/mechanical cost for water supply scheme (for full specifications refer Annexure A)	1.00	complete job	150000.00	Rupees One Lakh(s) Fifty Thousand Only
19.00	Carriage of material by MT including cost of loading unloading				
19.10	Sand + Bajri (avg lead 25 Kms)	10.31	Cum	370.00	Rupees Three Hundred Seventy Only
19.20	Cement + steel (avg lead 10 Kms)	2.44	M.T.	220.00	Rupees Two Hundred Twenty Only

**Terms and Conditions:-**

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (45) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 5- The pipe will be laid only after the manufacturers quality and test certificates and Third-Party inspection certificate (to be provided by the contractor at his own cost) shall be approved by the departmental quality control committee.
- 6- Earnest Money of ₹ 66000/- deposited by your vide CDR No. 381129 dated 15-10-2020 has been retained in the divisional office as security deposit.
- 7- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Tech. Officer

Executive Engineer,  
JSD (PHE) Div. Pulwama

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.