

Jammu & Kashmir

OFFICE OF THE EXECUTIVE ENGINEER PHE DIVISION SOPORE

M/s Fasil Firdous Dar
 S/o: Firdous Ahmad Dar
 R/o: Iqbal Nagar Sopore Baramulla
 Reg. No.: SE (R&B) SB-C-469 of 2018-19
 Phone No: 7006067437
 E-Mail: faisall.firdous@gmail.com
 Position of AAA : Accorded
 Position of T.S : Accorded

No:- 9106-12
 Dated:- 10-1-22
 Advt. Cost: Rs. 22.20 lacs
 Allott. Cost: Rs. 20.42 lacs
 Time of Complt.: 30 days

Subject: - Retrofitting of W.S.Scheme Cherhar by way of Laying and fitting of pipes, anchor blocks construction of lavatory block, Chain link fencing and other allied works under JJM (Tender ID: 2022_PHE_167238_4).

Ref: 1. Your on-line tender received in response to this office E-NIT No: 02/JJM/JSDS of 04/2022 dated: 20 - 04- 2022.
 2. Superintending Engineer Hyd. Circle Sopore's Authorization issued vide No: SE/Hyd./DB/ 3623-34 dated: 30-06-2022.
 2. This office letter of intent issued under No:JS/PHED/Spr/CS/DB 3100-05 dated: 16-07-2022..

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, contract for the work mentioned above is here by fixed with you on the following rates, terms and conditions.

A Rates:

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
1	Earth work in excavation by manual means over areas (exceeding 30cm and upto 1.5m in depth and width as well as 10 Sqm in Plan) including disposal of excavated earth upto 1m cutting edge, disposed earth to be levelled and neatly dressed in all kinds of soil.	Cum	1127.300	436.000	491502.80
2	Earth work in excavation by manual means over areas (exceeding 30cm and upto 1.5m in depth and width as well as 10 Sqm in Plan) including disposal of excavated earth upto 1m cutting edge, disposed earth to be levelled and neatly dressed in ordinary rock	Cum	7.780	855.850	6658.51
3	Earth work in bulk excavation by manual means over areas (exceeding 30 cm indepth, 1.5 m in width as well as 10 Sqm on plan) including disposal of excavated	Cum	25.480	539.350	13742.63
4	Providing and laying of dry Stone soling in horizontal on level.	Cum	3.720	816.400	3037.00

Head Draftsman

Technical Officer


Exen

Retrofitting of W.S.Scheme Cherhar

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone agg. 40 mm nominal size Crushed)	Cum	2.480	4861.850	12057.33
6	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	3.480	6465.190	22498.86
7	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	23.490	9408.130	220996.97
8	Centring and shuttering including strutting, propping etc, and removal of form work for Foundations, footings, bases for columns	Sqm	111.600	262.800	29272.68
9	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platforms.	Sqm	0.720	635.600	457.63
10	Centering and shuttering including strutting, propping etc. and removal of form for: walls (any thickness) including attached pilasters buttresses, plinth and string course fillets, kerbs and steps etc.	Sqm	15.690	573.850	9003.70
11	Reinforcement for RCC work including straightning, cutting, bending, binding all complete T.M.T bars	Kg	965.910	87.170	84198.37
12	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	1.440	9849.340	14183.05
13	Brick work in FPS bricksof class designation 75 in foundation and plinth in cement mortar 1:6 mix	Cum	7.960	6183.730	49222.65
14	Extra for brick work with common burnt clay bricks/cement concrete bricks in superstructure above plinth level upto floor five level	Cum	4.510	1323.650	5969.66



Head Draftsman



Technical Officer
Cont. on Page No: 3rd



Exen /

Retrofitting of W.S.Scheme Cherhar

No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
15	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs or with dash fasteners shall be paid for separately) 1st class kail wood	Cum	0.110	106894.15	11758.357
16	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note: -Butt hinges and necessary screws shall be paid separately). 35mm 1st class kail wood	Sqm	1.230	3093.80	3805.374
17	Providing and laying Ceramic glazed wall tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1: 4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete. In colour such as White, Ivory, Grey, Fume Red Brown	Sqm	13.140	1115.80	14661.612
18	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1: 4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete. In all colours, shades, except White, Ivory, Fume Red Brown	Sqm	3.750	1052.75	3947.813
19	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	Sqm	101.130	378.12	38239.276
20	Dry random rubble masonry with hard stone in foundation and plinth: using quarry stone with bond stone	Cum	9.500	2497.50	23726.250
21	Structural steel work welded in built up sections framed work welded included cutting, finishing, fixing in position.	Kg	2064.900	102.13	210888.23
22	Reinforcement for RCC Work including straightening , cutting , bending , placing in position and binding all complete (T.M.T Bars)	Kg	143.460	87.17	12505.408
23	Providing and fixing GI Chain Link fabric fencing of 4mm dia wire of required width in mesh 50mmx50mm including cost of nuts and bolts, washers as required at site with all carriages (Complete Job)	Sqm	144.000	733.50	105624.00
24	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel work	Sqm	158.400	52.750	8355.600


 Head Draftsman


 Technical Officer


 Exam

Retrofitting of W.S. Scheme Cherhar

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
25	Painting with synthetic enamel paint of approved brand and manufacture on steel galvanised iron/ steel work	Sqm	158.400	121.950	19316.880
26	Providing and fixing of nuts and bolts and chip including one end fix anchor block	Kg	40.000	100.000	4000.000
27	Laying and fitting of G.I Pipes incl cost of Pipe specials				
27.1	65mm ø G.I	m	1500.000	95.280	142920.00
27.2	50mm ø G.I	m	1600.000	58.300	93280.000
27.3	40mm ø G.I	m	2000.000	54.620	109240.00
27.4	25mm ø G.I	m	2000.000	39.140	78280.000
27.5	20mm ø G.I	m	1550.000	26.760	41478.000
27.6	15mm ø G.I	m	2000.000	25.400	50800.000
28	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	Cum	1014.520	198.700	201585.12
29	Providing & fixing water closet squatting pan(Indian type) along with "S" or "P" trap 10 litre low level flushing cistern incl flush pipe of approved make manually controlled device with all operations including all necessary materials, labour all complete as per the direction of Engineer-in charge.	No.	1.000	5534.850	5534.850
30	Providing & fixing 15 mm nominal bore C.P brass Bib cock brass bib cock of approved quality	No.	3.000	350.000	1050.000
31	Providing and laying of PVC pipes of 100 mm dia of prince made as directed by site Engineer	No.	21.340	100.000	2134.000
32	Providing and laying of PVC pipes of 80 mm dia of prince made as directed by site Engineer	m	24.400	80.000	1952.000
33	Providing and fixing of Gi pipes complete job as directed by site Engineer 15mm dia.	m	37.200	144.400	5371.680
34	Providing and fixing of Wash Basin 460 mm	No.	1.000	2900.000	2900.000
35	Providing and fixing of three layer PVC Tank Standard quality having 500 ltr capacity	Ltr	500.000	11.250	5625.000
36	Providing and fixing of 15 mm Gate Valve complete Job	No.	3.000	1200.000	3600.000
37	Providing and fixing 15 mm nominal bore Steel angle valve for basin mixer and geyser points of approved make conforming to IS : 8931	No.	2.000	1500.000	3000.000
38	Providing and fixing PTMT soap dish holder	No.	2.000	227.900	455.800
39	Carriage of material by mechanical transport				
39.1	Cement & Steel Avg lead 26 Km	Mt	15.300	410.630	6282.639

 Head Draftsman


 Technical Officer


 Exen

Retrofitting of W.S.Scheme Cherhar

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
39.2	Sand and Bajree for average lead of 35 Km	Cum	34.830	551.330	19202.824
39.3	Stone Soling for 35 Km	Cum	3.700	648.680	2400.116
39.4	Bricks for average 80 Km	No.	3780.000	2.920	11037.600
40.	Carriage of Pipes from Divisional Store to dumping site on road by M T for average 28km	MT	30.000	428.290	12848.700
	Total				2220609.00
	Below 8% on all items				177649.00
	Grand Total				2042960.00

Rates and quantities checked:


Head Draughtsman


Executive Engineer
Jal Shakti PHE Division
Sopore

B Terms and conditions:


1. Total amount of the work should in no case exceed beyond **Rs.20.42 lacs (Rs.Twenty lacs and forty two thousand only)** which includes all taxes, levies etc applicable as per norms amended by competent authority from time to time.
2. The work shall have to be completed by you within a period of **30 days** strictly in accordance with the approved design/drawings and specifications failing which penalty under rules shall be imposed upon you.
3. Performance security amounting @3% ie **Rs. 61300.00** .Shall have to be deposited by you in shape of CDR/FDR/BG in this office which shall be considered for release after three months beyond the warranty period of 18 Months as per SBD of ENIT is over.
4. Earnest money of **RS. 44400.** deposited by you in this office as a bid security against the contract vide CDR/FDR/BG No: **3144753** dated : **6-6-2022** shall be considered for release once the performance security @ **3%** of allotted amount is deposited by you.
5. The contractor/Agency shall be bound for satisfactory performance for the work for 18 months after the successful commissioning of work and will have to make a trial run of work for a period of 03 Months to the best satisfaction of the department
6. The DLP shall be for a period of 12 months which shall commence after the successful commission of trial run.
7. All environmental norms, labour laws and all other guidelines issued by the competent authorities shall have to be followed by you in letter and spirit.
8. An agreement shall have to be drawn by you with the department within a period of 07 days from the date of issuance of allotment, failure to executed such a formal deed shall not however prevent the contract from being enforced upon you. However payment on account of this work shall not be considered in absence of agreement.

Retrofitting of W.S.Scheme Cherhar


9. Geo tagged photographic evidence of the work, pre-execution during execution and post execution should be maintained by you on your own expenses.
10. The allotted work shall have to be monitored by Third Party Monitoring Agency (WAPCOAS) appointed by the department.
11. All other terms and conditions shall remain same as laid down in E-NIT/ Standard bidding document/PWD from No 25 and GFR-2017 and manual of procurement of works 2019.



**Assistant Accounts
Officer**



Technical officer



**Executive Engineer
Jal Shakti PHE Division
Sopore**

Copy to the:

- i) Chief Engineer Kashmir Jal Shakti PHE Department Srinagar for favour of information.
- ii) District Development Commissioner Baramulla (Chairperson DJJM) for favour of information.
- iii) Superintending Engineer Hydraulic Circle Baramulla/Bandipora (Member Secretary JJM) for favour of information.
- iv) Assistant Executive Engineer PHE Sub Division wallab for information and necessary action.
- v) M/S WAPCOAS Ltd Corporate office 76-C intuitional area sector 18 Gurgon for information
- vi) Head Draftsman for information.
- vii) File Concerned.