

OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 627-30
Dated: 01-05-2021

Haja Constructions,
P/o Nazir Ahmad Naikoo,
S/o. Mohammad Kamal Naikoo,
R/o Beighpora Awantipora, Pulwama
Regd. No. CE/FC/Sgr/73/AAy(Civil & Sanitary)/2017-18

Sub :- Retrofitting of Water Supply Scheme Wakherwan by way of construction of RCC jacketing to existing SR including replacement of sluice chamber, construction of chain link fencing, providing, laying and fitting of GI pipes and including electrical/ mechanical works by way of supply/ installation, testing and commissioning of pumping equipments and othr electrical works at Renzipora including installation of 127 No. FHTC's for Wakherwan including maintenance for a period of 3 years which includes 12 months DLP. (JMM)

Ref:- E-NIT S.No. 88/PHEP/Fresh of 2020-21, job No. (3), Circulated vide this office No. PHEP/5066-78
Dated:- 16-12-2020.

Advertised Amount of work: ₹ 53,05,000.00

Alloted Amount of work: ₹ 53,72,300.00

Rupees Fifty Three Lakh(s) Seventy Two Thousand Three Hundred Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work

is hereby fixed with you at the following rates quoted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	752.19	Cum	240.45	323.00	Rupees Three Hundred Twenty Three Only
2.00	Engagement of labour/carpenter for dismantling of CGI roofs/wood work truss/ domes including stacking of dismantled material within a lead of 50 mtrs etc. complete					
2.10	Carpenter	3.00	No	450.00	700.00	Rupees Seven Hundred Only
2.20	Labour	16.00	No	300.00	500.00	Rupees Five Hundred Only
3.00	Providing and laying of stone soling hand packed horizontally excluding cost of stones	1.77	Cum	327.05	425.00	Rupees Four Hundred Twenty Five Only
4.00	Dismantling of old plaster or skirting joint and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 mtrs lead	147.26	Sqm	18.05	20.00	Rupees Twenty Only
5.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering & shuttering all work up to plinth level in (1:3:6) Mix (1 cement:3course sand: 6 grade stone agg. 40 mm nominal size)	4.19	Cum	2707.40	4900.00	Rupees Four Thousand Nine Hundred Only
6.00	Reinforcement cement concrete work in wall (any thickness) including attached plaster buttresses plinth and string courses filets columns piers, piers abutments post and struts etc. upto floor five level excluding the cost of centering and shuttering finishing and reinforcement 1:2:4 (1 cement:2course sand :4crushed stone aggregate 20mm nominal size)	1.40	Cum	5587.45	7000.00	Rupees Seven Thousand Only
7.00	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement all work upto plinth level in 1:1.5:3 mix (1 Cement 1.5 coarse sand 3graded stone aggregate 20mm nominal size)	34.20	Cum	3504.20	7500.00	Rupees Seven Thousand Nine Hundred Only
8.00	Reinforced cement concrete work in arches , arch ribs , domes , valuts , shells, folded plate and roofs having slope more than 150 upto floor five level excluding the cost of centering , shuttering , finishing and reinforcement with 1:2:4 mix (1 cement 2: coarse sand 4: graded stone aggregate 20 mm nominal size crushed)	24.26	Cum	6033.05	7600.00	Rupees Seven Thousand Six Hundred Only
9.00	Reinforcement for R.C.C Work including straightening, cutting, bending, placing in position and binding all complete. (thermo-mechanically treated bar)	4146.50	Kg	71.05	89.00	Rupees Eighty Nine Only
10.00	Centering and shuttering including strutting, propping etc and removal of form for-					
10.10	Foundation, footings, bases of columns for mass concrete	52.21	Sqm	179.25	220.00	Rupees Two Hundred Twenty Only
10.20	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	147.26	Sqm	342.90	390.00	Rupees Three Hundred Ninety Only
10.30	Columns, pillars, piers, abutments posts and struts.	40.19	Sam	417.05	490.00	Rupees Four Hundred Ninety Only
10.40	Arches, domes valuts up to 6mtr span	161.77	Sqm	1125.70	1540.00	Rupees One Thousand Five Hundred Forty Only
10.50	Extra for arches, domes, valuts exceeding 6 mtr span	161.77	Sqm	784.65	900.00	Rupees Nine Hundred Only
11.00	12mm thick cement plaster in 1:4 mix with floating coat of neat cement(1 cement 4: fine sand)	567.75	Sqm	158.00	250.00	Rupees Two Hundred Fifty Only
12.00	Provision for making bypass arrangements till SR is made functional after jacketing by way of laying and fitting of pipes and removing the same and necessary fitting items whichever is required at site including carriage of pipes from salvaged site to and fro if required complete job	1.00	Lot	RCC	5000.00	Rupees Five Thousand Only
13.00	Providing fixing flanged pipes including coat of pipes with 12mm thick flanged joints including cost of nuts , bolts, washers, cutting of thread and making good for jointing including testing and commissioning all carriage head lead complete 100 mm dia G.I flanged pipes	1600.00	Mtr	RCC	1220.00	Rupees One Thousand Two Hundred Twenty Only

Retrofitting of Water Supply Scheme Wakherwan by way of construction of RCC jacking to existing SR including replacement of sluice chamber, construction of chain link fencing, providing, laying and fitting of GI pipes and including electrical/ mechanical works by way of supply, installation, testing and commissioning of pumping equipments and othr electrical works at Renzipora including installation of 127 No. FHTC's for Wakherwan including maintenance for a period of 3 years which includes 12 months DLP. (JJM)

14.10	Providing and fixing of G.I pipes including cost of pipes all carriages head load upto site of work all complete	700.00	Mtr	RQC	477.00	Rupees Four Hundred Seventy Seven Only
14.20	80 mm dia G.I pipes	750.00	Mtr	RQC	385.00	Rupees Three Hundred Eighty Five Only
14.30	40 mm dia G.I pipes	700.00	Mtr	RQC	249.00	Rupees Two Hundred Forty Nine Only
14.40	25 mm dia G.I pipes	700.00	Mtr	RQC	182.00	Rupees One Hundred Eighty Two Only
14.50	20 mm dia G.I pipes	1440.00	Mtr	RQC	144.00	Rupees One Hundred Forty Four Only
15.00	15 mm dia G.I pipes					
15.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.					
15.10	25mm to 40mm nominal bore	12.00	No	403.65	400.00	Rupees Four Hundred Only
15.20	above 40mm nominal bore	2.00	No	1022.15	1050.00	Rupees One Thousand Fifty Only
16.00	Providing fixing double flanges C.I sluice valves conforming to IS 780 of 1984 read with upto date amendments standard mark ISI make PN-1 including cost of nuts bolts IR cloth including all sorts of carriage upto site of work complete job including cost of pedestals and handles .Including dismantling of old damaged 150mm dia sluice valve to divisional store					
16.10	150mm dia sluice valve	2.00	No	RQC	15000.00	Rupees Fifteen Thousand Only
17.00	Structural steel work in single sections fixed with connecting plate including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer complete	1780.42	Kg	69.60	95.00	Rupees Ninety Five Only
18.00	Providing and fixing GI chain-link fencing (fabric fencing) of required width in mesh size 50x50mm including strengthening with 2mm dia wire or nuts bolts washer are required complete as per direction of engineer-in-charge (made of GI Wire of dia 4mm)	175.68	Sqm	571.00	770.00	Rupees Seven Hundred Seventy Only
19.00	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade new steel work (two or more coats)	297.22	Sqm	69.30	120.00	Rupees One Hundred Twenty Only
20.00	Provision for face lifting of various structures by way of painting , leveling and dressing etc complete job	1.00	Job	RQC	40000.00	Rupees Forty Thousand Only
21.00	Carriage of different materials from source upto site of work by mechanical transport including cost of loading, unloading and stacking complete.					
21.10	Sand + Bajri (avg lead 15 Kms)	149.62	Cum	207.83	100.00	Rupees One Hundred Only
21.20	Cement + Steel (avg lead 15 Kms)	40.59	M.T.	184.76	300.00	Rupees Three Hundred Only
21.30	Stone Soling (avg lead 15 Kms)	1.77	Cum	244.51	300.00	Rupees Three Hundred Only
22.00	Supply, installation, testing and commissioning of multistage bowl type submercible clear water pumping equipment (as per the specifications shown in Annexure "A")	1.00	Job	RQC	70000.00	Rupees Seventy Thousand Only
23.00	P/F of MUG 30 starter of L&T make	1.00	Job	RQC	30000.00	Rupees Thirty Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 106400/- deposited by your vide CDR No. 486072 dated 24-09-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Tahab for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,
S.D (PHE) Div. Pulwama