

No. PHEP/ 5239-42
Dated. 22-12-2020

Mr. Mr Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zaglgam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Zadoora by way of providing, laying & fitting of GI pipes, including construction of RCC Service Reservoir/ Collection Sump and sluiced chamber, chain link fencing around structures, CGI shed including electrical and mechanical works required for completion of scheme including installation of 94 No. FHTC's for Zadoora (JJM).

Ref:- E-NIT S.No. 48/PHEP of 2020-21, job No. (1), Circulated vide this office No. PHEP/3474-86 Dated: 09-10-2020.

Advertised Amount of work: ₹ 78,16,000.00 ✓

Alloted Amount of work: ₹ 75,61,000.00 ✓

Rupees Seventy Five Lakh(s) Sixty One Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	1316.00	Cum	324.00	Rupees Three Hundred Twenty Four Only
2.00	P/F of flanged pipe with flanged joints 12mm thick of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all cartages complete.	300.00	Mtr	1224.00	Rupees One Thousand Two Hundred Twenty Four Only
2.10	100mm dia GI pipe with flanges				
3.00	Providing, laying and fitting of GI pipes including all cartages head load upto site of work complete.	500.00	Mtr	477.00	Rupees Four Hundred Seventy Seven Only
3.10	50mm dia				
3.20	40mm dia	800.00	Mtr	388.00	Rupees Three Hundred Eighty Six Only
3.30	25mm dia	1500.00	Mtr	249.00	Rupees Two Hundred Forty Nine Only
3.40	20mm dia	1500.00	Mtr	182.00	Rupees One Hundred Eighty Two Only
3.50	15mm dia	1000.00	Mtr	144.00	Rupees One Hundred Forty Four Only
4.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.	25.00	No	550.00	Rupees Five Hundred Fifty Only
4.10	25mm to 40mm nominal bore				
5.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement:4 fine sand 8 grade stone agg.)	16.74	Cum	4200.00	Rupees Four Thousand Two Hundred Only
6.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement, 4 fine sand)	428.39	Sqm	250.00	Rupees Two Hundred Fifty Only
7.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3)Raft (1 cement:1 1/2 course sand:3 grade stone agg. 20 mm nominal size)	11.20	Cum	7100.00	Rupees Seven Thousand One Hundred Only
8.00	Providing and laying of stone soling hand packed horizontally excluding cost of stones	16.81	Cum	441.00	Rupees Four Hundred Forty One Only
9.00	Structural steel work welded in build up sections/ framed work including cutting hoisting fixing in position and applying priming coat of approved steel primer using structural steel etc as required in gratings, frames, guard bar ladders, railing, brackets gates and similar work	275.00	Kg	110.00	Rupees One Hundred Ten Only
10.00	Reinforced cement concrete work in walls (any thickness) including attached plasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement:1 1/2 course sand:3 graded crushed stone 20 mm nominal size)	18.17	Cum	8450.00	Rupees Eight Thousand Four Hundred Fifty Only
11.00	Centering and shuttering including strutting, propping etc and removal of form for-				
11.10	Foundation, footings, bases of columns etc. for mass concrete.	217.04	Sqm	241.00	Rupees Two Hundred Forty One Only
11.20	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	169.73	Sqm	431.00	Rupees Four Hundred Thirty One Only
11.30	Suspended floors, roofs, landings, balconies and access platform	16.00	Sqm	502.00	Rupees Five Hundred Two Only
11.40	Columns, pillars, piers, abutments posts and struts.	24.00	Sqm	520.00	Rupees Five Hundred Twenty Only
11.50	Lintel, beams, plinth beams, girders, bressumers and cantilevers	26.64	Sqm	390.00	Rupees Three Hundred Ninety Only
11.60	Arches, domes valuts up to 6mtr span	17.40	Sqm	1900.00	Rupees One Thousand Nine Hundred Only
12.00	Reinforcement for RCC works including Straightening cutting, bending, placing in position & binding all complete (Thermo Mechanically treated bars)	4339.00	Kg	95.00	Rupees Ninety Five Only
13.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	1933.02	Kg	100.00	Rupees One Hundred Only
14.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:3:6 (1 cement:3 coarse sand 6 graded stone agg. 40 mm nominal size)	48.60	Cum	4750.00	Rupees Four Thousand Seven Hundred Fifty Only

1
Retrofitting of Water Supply Scheme Zadoora by way of providing, laying & fitting of GI pipes, including construction of RCC Service Reservoir/ Collection Sump and sluicod chamber, chain link fencing around structures, CGI shed including electrical and mechanical works required for completion of scheme including installation of 94 No. FHTC's for Zadoora (JJM).

15.00	Reinforce cement concrete work in beams, suspended floors, roofs having slope upto 15 degree landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases, and spiral cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement, 2 coarse sand, 4 graded stone egg 20mm nominal size)	30.48	Cum	7800.00	Rupees Seven Thousand Six Hundred Only
16.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	1039.50	Cum	190.00	Rupees One Hundred Ninety Only
17.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, filets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:2:4 (1 cement 2 coarse sand 4 graded stone egg, 20 mm nominal size.	7.72	Cum	7600.00	Rupees Seven Thousand Five Hundred Only
18.00	Providing and fixing of G.I. chain link fencing of required width in mesh size 50x50mm including strengthening with 2mm dia wire or nuts, bolts and washers as required complete as per direction of Engineer incharge. Made of G.I. wire 4mm dia	172.94	Sqm	770.00	Rupees Seven Hundred Seventy Only
19.00	Providing corrugated G.S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/ vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63mm thick with zinc coating not less than 275 gm/sqm	72.57	Sqm	1022.00	Rupees One Thousand Twenty Two Only
20.00	Providing ridges or hips of width 60cm overall plain G.s. sheets fixed with ploymer coated J or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete 0.63mm thick with zinc coating not less than 275 gm/sqm	22.74	Mtr	660.00	Rupees Six Hundred Sixty Only
21.00	Structural steel work in single section fixed with connecting plates including cutting hoisting fixing in position and applying priming coat of approved steel primer all complete	1542.60	Kg	90.00	Rupees Ninety Only
22.00	Carriage of different materials from source upto site of work by mechanical transport including cost of loading, unloading and stacking complete.				
22.10	Cement + steel (avg lead 10 Kms)	35.69	M.T.	440.00	Rupees Four Hundred Forty Only
22.20	Sand+ Bajri (avg lead 15 Kms)	172.66	Cum	280.00	Rupees Two Hundred Eighty Only
22.30	Stone Solling (avg lead 5 Kms)	17.11	Cum	201.00	Rupees Two Hundred One Only
23.00	painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade two or more coats on new work over an undercoat of suitable shade with ordinary paint of approved brand and manufacture.	120.70	Sqm	135.00	Rupees One Hundred Thirty Five Only
24.00	Providing and laying in position reinforced cement concrete of specified grade excl. cost of centering & shuttering finishing and reinforcement all work upto plinth level 1:2:4 (1 cement:2 coarse sand 4 graded stone egg. 40 mm nominal size	4.41	Cum	6450.00	Rupees Six Thousand Four Hundred Fifty Only
25.00	Supplying and fixing rolling shutters of approved make made of required size M.S. laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets side guides and arrangements for inside and outside locking with push and pull operation complete including the cost of providing and fixing of necessary 27.5 cm long wire spring manufacture from high tensile steel wire of adequate strength conforming to IS: 4454 Part I and M/s top cover of required thickness for rolling shutters 80x0.90mm MS laths with 0.90mm thick top cover.	4.41	Sqm	2140.00	Rupees Two Thousand One Hundred Forty Only
26.00	Provision for providing, fixing of hinges etc complete job.	1.00	Job	2000.00	Rupees Two Thousand Only
27.00	P/F of 100mm dia sluice valve including cost of nuts, bolts, washers, tail pieces all carriages complete.	2.00	Job	12000.00	Rupees Twelve Thousand Only
28.00	Providing and fixing of electrical and mechanical works in all respects required for completion of scheme (for full description of job refer Annexure A (pages 1 to 8))	1.00	Completo job	2800000.00	Rupees Twenty Eight Lakh(s) Only
29.00	Maintenance cost for a period of two years	1.00	Completo job	100000.00	Rupees One Lakh(s) Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- The pipe will be laid only after the manufacturers quality and test certificates and Third-Party inspection certificate (to be provided by the contractor at his own cost) shall be approved by the departmental quality control committee.
- 5- Earnest Money of ₹ 156500/- deposited by your vide CDR No. 593497 dated 13-10-2020 has been retained in the divisional office as security deposit.
- 6- All other terms and conditions will remain same as per the original agreement form No. 25-double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech./Officer

Executive Engineer
 JSS (PHE) Div. Pulwama