

14

1

Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEPI 4299-4302
 Da.ed. 13.11.2020

Mr. Bashir Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zagigam, Pulwama
Regd. No. 24/AAY/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Draklaran Abhama by way of providing, laying & fitting of GI pipes, reiovation of chowkidar quarter and face lifting of structures, including installation of 45 No. FHTC's (JJM).

Ref:- E-NIT S.No. 49/PHEP of 2020-21, job No. (2), Circulated vide this office No. PHEP/3523-34 Dated:- 13-10-2020.

Advertised Amount of work: ₹ 35,15,000.00

Alloted Amount of work: ₹ 32,55,000.00

Rupees Thirty Two Lakh(s) Fifty Five Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

| Sl. No. | Description of work | No.or Qty. | Unit | Estd. Rate | RATE | |
|---------|--|------------|------|------------|---------|---|
| | | | | | Figures | Words |
| 1.00 | Earthwork in excavation by manual means in trenches for foundation, drains, pipes cablesetc (not exceeding 1.5mtrs in width and for shafts, wells cesspits and the like not exceeding 10 Sqm on plain depth upto 1.5 mtrs, including disposal of excavated earth upto 1mtr from cutting edge disposal earth to be levelled and neatly dressed in all kinds of soil | 1536.40 | Cum | 240.45 | 310.00 | Rupees Three Hundred Ten Only |
| 2.00 | Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs. | | | | | |
| 2.10 | Above 40mm dia bore | 500.00 | Mtr | 59.30 | 90.00 | Rupees Ninety Only |
| 3.00 | Providing, laying and fitting of G.I. pipes including cost of pipes but excluding cost of earth work: | | | | | |
| 3.10 | 65mm dia | 900.00 | Mtr | RQC | 510.00 | Rupees Five Hundred Ten Only |
| 3.20 | 50mm dia | 1000.00 | Mtr | RQC | 440.00 | Rupees Four Hundred Forty Only |
| 3.30 | 40mm dia | 1400.00 | Mtr | RQC | 370.00 | Rupees Three Hundred Seventy Only |
| 3.40 | 25mm dia | 1500.00 | Mtr | RQC | 230.00 | Rupees Two Hundred Thirty Only |
| 3.50 | 20mm dia | 1900.00 | Mtr | RQC | 170.00 | Rupees One Hundred Seventy Only |
| 3.60 | 15mm dia | 1500.00 | Mtr | RQC | 130.00 | Rupees One Hundred Thirty Only |
| 4.00 | Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete. | | | | | |
| 4.10 | 25mm to 40mm nominal bore | 40.00 | No | 403.65 | 600.00 | Rupees Six Hundred Only |
| 4.20 | Above 40mm nominal bore | 10.00 | No | 1022.15 | 1100.00 | Rupees One Thousand One Hundred Only |
| 5.00 | Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3)Raft (1 cement:1 ½ course sand:3 grade stone agg. 20 mm nominal size) | 2.35 | Cum | 5504.20 | 7000.00 | Rupees Seven Thousand Only |
| 6.00 | Centering and shuttering including shuttering, propping etc and removal of form work for:- | | | | | |
| 6.10 | Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc | 48.00 | Sqm | 342.80 | 410.00 | Rupees Four Hundred Ten Only |
| 7.00 | Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete (thermo-mechanically treated bars) | 312.00 | Kg | 71.00 | 95.00 | Rupees Ninety Five Only |
| 8.00 | P/F of MS Lid of size 2'-6"x2'x6" angle iron frame with iron sheet including locking arrangements complete job. | 1.00 | No | RQC | 3500.00 | Rupees Three Thousand Five Hundred Only |
| 9.00 | 12 mm thick cement plaster of mix 1:4 | 361.51 | Sqm | 158.00 | 230.00 | Rupees Two Hundred Thirty Only |
| 10.00 | Clearance of silt from PST, FP, clear water sump, SR intake filter media etc including disposal from the premises all leads and lifts complete job. | 58.50 | Cum | 87.10 | 107.00 | Rupees One Hundred Seven Only |
| 11.00 | Cleaning and washing of filter media after removing from lant complete job. | 1031.94 | Cft | RQC | 10.00 | Rupees Ten Only |
| 12.00 | Re-laying of filter media into filtration plant in layers after washing and cleaning complete job. | 28.25 | Cum | RQC | 250.00 | Rupees Two Hundred Forty Six Only |
| 13.00 | Extra for providing and mixing of water proofing material in cement conc work in doses by weight of cement as per manufacturer specification | 166.03 | Kg | 43.55 | 60.00 | Rupees Sixty Only |

Sub :- Retrofitting of Water Supply Scheme Draklaran Abhama by way of providing, laying & fitting of GI pipes, renovation of chowkidar quarter and face lifting of structures, including installation of 45 No. FHTC's (JJM).

| | | | | | | |
|-------|---|--------|------|---------|----------|--|
| 14.00 | Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works | 257.25 | Sqm | 27.80 | 37.53 | Rupees Thirty Seven And Paise Fifty Three Only |
| 15.00 | P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job. | 1.00 | No | RQC | 14000.00 | Rupees Fourteen Thousand Only |
| 16.00 | Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade old steel work (one or more coats) | 257.25 | Sqm | 45.60 | 61.56 | Rupees Sixty One And Paise Fifty Six Only |
| 17.00 | Finishing walls with water proofing cement paint of required shade on new works (two or more coats) applied @ 3.84 Kg/10Sqm | 293.66 | Sqm | 53.00 | 71.55 | Rupees Seventy One And Paise Fifty Five Only |
| 18.00 | Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:3:6 (1 cement:3 fine sand:6 grade stone agg 40 mm nominal size) all work upto plinth level | 5.40 | Cum | 3546.65 | 4400.00 | Rupees Four Thousand Four Hundred Only |
| 19.00 | Painting with synthetic enamel paint of approved brand and manufacture of give an even shade two or more coats on new work | 60.00 | Sqm | 67.10 | 90.58 | Rupees Ninety And Paise Fifty Eight Only |
| 20.00 | P/F of washbasin, indian type WC flush tank with all necessary fittings such as angle valve, CP fittings, P-Trap, door trap whichever is required for such type of fittings all leads lifts complete job. | 1.00 | Job | | 20000.00 | Rupees Twenty Thousand Only |
| 21.00 | Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete | 379.12 | Kg | 80.60 | 109.00 | Rupees One Hundred Nine Only |
| 22.00 | Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement:1½ course sand:3 graded crushed stone 20 mm nominal size) | 4.80 | Cum | 6280.95 | 8400.00 | Rupees Eight Thousand Four Hundred Only |
| 23.00 | Laying and fitting of G.I. pipes excluding cost of pipes and earth work: | | | | | |
| 23.10 | 50mm dia | 500.00 | Mtr | 27.75 | 40.00 | Rupees Forty Only |
| 24.00 | Rethreading of 50mm dia GI pipes including cutting of joints and making good of jointing complete | 100.00 | end | RQC | 35.00 | Rupees Thirty Five Only |
| 25.00 | P/F of glass panes including cost of nails, bedding, all complete as per requirement of site. | 10.00 | Sqm | RQC | 200.00 | Rupees Two Hundred Only |
| 26.00 | P/F of 65mm dia GI bend including flanged joints, nuts, bolts, washers fixing etc complete. | 4.00 | No | RQC | 850.00 | Rupees Eight Hundred Fifty Only |
| 27.00 | Carrage of materials from source upto actual site of work by mechanical transport including cost of loading, unloading, stacking complete. | | | | | |
| 27.10 | Sand + Bajri (avg lead 40 Kms) | 21.27 | Cum | 360.48 | 420.00 | Rupees Four Hundred Twenty Only |
| 27.20 | Cement + steel (avg lead 40 Kms) | 6.34 | M.T. | 320.41 | 460.00 | Rupees Four Hundred Sixty Only |

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (30) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 71000/- deposited by your vide CDR No. 2954425 dated 21-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25-double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,
USD (PHE) Div. Pulwama