

OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 6112.15
Dated. 06-02-2021

Mir. Muhammad Shafi Dar,
Contractor,
S/o. Ghulam Nabi,
R/o Rohmu-Pulwama,
Regd. No. CE/UEED/BEE/338/2003-04

Sub :- Retrofitting of Water Supply Scheme Parigam Khalisa by way of providing, laying & fitting of GI pipes, providing of RCC dome to existing SR and face lifting of structures including installation of 75 No. FHTCs for Parigam Khalisa (JJM).

Ref:- E-NIT S.No. 45/PHEP of 2020-21, job No. (1), Circulated vide this office No. PHEP/3358-70 Dated: 05-10-2020 and Superintending Engineer, Hydl. Circle, Shopians's No. SE/Hyd/ 3559-60 Dated:- 16-12-2020

.....
Advertised Amount of work: ₹ 23,49,000.00

Alloted Amount of work: ₹ 23,96,000.00

Rupees Twenty Three Lakh(s) Ninety Six Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	646.50	Cum	310.00	Rupees Three Hundred Ten Only
2.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.				
2.10	50mm dia	500.00	Mtr	470.00	Rupees Four Hundred Seventy Only
2.20	40mm dia	1000.00	Mtr	380.00	Rupees Three Hundred Eighty Only
2.30	25mm dia	1000.00	Mtr	240.00	Rupees Two Hundred Forty Only
2.40	20mm dia	1000.00	Mtr	170.00	Rupees One Hundred Seventy Only
2.50	15mm dia	1000.00	Mtr	135.00	Rupees One Hundred Thirty Five Only
3.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.				
3.10	25mm to 40mm nominal bore	75.00	No	500.00	Rupees Five Hundred Only
3.20	above 40mm nominal bore	20.00	No	1200.00	Rupees One Thousand Two Hundred Only
4.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3)Raft (1 cement:1 1/2 course sand:3 grade stone agg. 20 mm nominal size)	9.53	Cum	6990.00	Rupees Six Thousand Nine Hundred Ninety Only
5.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement:1 1/2 course sand:3 graded crushed stone 20 mm nominal size)	15.45	Cum	7977.00	Rupees Seven Thousand Nine Hundred Seventy Seven Only
6.00	Reinforce cement concrete work in beams, suspended floors, roofs having slope upto 15 degree landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases, and spiral cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement, 2 coarse sand, 4 graded stone agg 20mm nominal size)	8.26	Cum	7000.00	Rupees Seven Thousand Only
7.00	Extra for providing and mixing of water proofing material in cement conc work in doses by weight of cement as per manufacturer specification	25.00	Kg	60.00	Rupees Sixty Only
8.00	Reinforcement for RCC works including Straightening cutting, bending, placing in position & binding all complete (Thermo Mechanically treated bars)	2656.00	Kg	90.00	Rupees Ninety Only
9.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	627.26	Sqm	45.00	Rupees Forty Five Only
10.00	P/F of Sign: board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	12000.00	Rupees Twelve Thousand Only
11.00	P/F of different dias of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirtoskar or VAGE) including all carriages upto site of work complete including tail pieces				

Sub :- Retrofitting of Water Supply Scheme Parigam Khalisa by way of providing, laying & fitting of GI pipes providing of RCC dome to existing SR and face lifting of structures including installation of 75 No. FHTOs for Parigam Khalisa (JJM).

11.10	100mm dia sluice valve	2.00	No	13500.00	Rupees Thirteen Thousand Five Hundred Only
12.00	Painting on G.S sheets with synthetic enamel paint of approved band and manufacture of required colour to give an even shade. New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution.	627.26	Sqm	103.61	Rupees One Hundred Three And Paise Sixty One Only
13.00	Finishing walls with water proofing cement paint of required shade old work (one or more coats) applied @ 2.20 kg/10 Sqm over priming coat of primer applied @ 0.80 liters/10 Sqm complete including cost of priming coat.	637.45	Sqm	68.90	Rupees Sixty Eight And Paise Ninety Only
14.00	Painting with synthetic enamel paint of approved band and manufacture of give an even shade two or more coats on new work	58.61	Sqm	87.23	Rupees Eighty Seven And Paise Twenty Three Only
15.00	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new works (two or more coats) over and including primary coat with cement primer.	57.50	Sqm	110.00	Rupees One Hundred Ten Only
16.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement, 4 fine sand)	261.77	Sqm	205.00	Rupees Two Hundred Five Only
17.00	Supply of labours	10.00	No	340.00	Rupees Three Hundred Forty Only
18.00	Supply of Carpenters.	3.00	No	500.00	Rupees Five Hundred Only
19.00	Reinforce cement concrete work in arches, arch ribs, domes, valuts, shells, folded plate roofs having slope more than 15 degree upto floor 5 level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement, 2 coarse sand, 4 graded stone agg 20mm nominal size)	7.61	Cum	7500.00	Rupees Seven Thousand Five Hundred Only
20.00	Centering and shuttering including strutting, propping etc and removal of form for:-				
20.10	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	101.42	Sqm	445.00	Rupees Four Hundred Forty Five Only
20.20	Lintels, beams, plinth beams girders, bressumers and centilevers.	36.20	Sqm	397.41	Rupees Three Hundred Ninety Seven And Paise Forty One Only
20.30	Arches, domes valuts up to 6mtr span	76.19	Sqm	1853.00	Rupees One Thousand Eight Hundred Fifty Three Only
20.40	Extra for arches, domes, valuts exceeding 6 mtrs span.	76.19	Sqm	1020.00	Rupees One Thousand Twenty Only
21.00	Dismantling of old plaster or skirting out joint and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 mtrs lead.	103.14	Sqm	23.46	Rupees Twenty Three And Paise Forty Six Only
22.00	Carriage of dismantled CGI sheets/ wood from site of work upto divisional store including cost of loading unloading complete (avg lead 15 Kms)	1.00	Trip	3500.00	Rupees Three Thousand Five Hundred Only
23.00	Carriage of different materials from source upto actual site of work by mechanical transport including cost of loading, unloading and stacking complete.				
23.10	Sand + Bajri (avg lead 15 Kms)	103.30	Cum	270.00	Rupees Two Hundred Seventy Only
23.20	Cement + steel (avg lead 15 Kms)	23.29	M.T.	240.00	Rupees Two Hundred Forty Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (30) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 47000/- deposited by your vide CDR No. 2954430 dated 27-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,
JSB (PHE) Div. Pulwama